STA

Revisions in Stratigraphic Nomenclature of the Columbia River Basalt Group

By D. A. SWANSON, T. L. WRIGHT, P. R. HOOPER, and R. D. BENTLEY

CONTRIBUTIONS TO STRATIGRAPHY

GEOLOGICAL SURVEY BULLETIN 1457-G



UNITED STATES GOVERNMENT PRINTING OFFICE, WASHINGTON: 1979

# UNITED STATES DEPARTMENT OF THE INTERIOR

CECIL D. ANDRUS, Secretary

**GEOLOGICAL SURVEY** 

H. William Menard, Director

Library of Congress Cataloging in Publication Data

Main entry under title:

Revisions in stratigraphic nomenclature of the Columbia River Basalt group.

(Contributions to stratigraphy) (Geological Survey bulletin: 1457-G) Bibliography: p. G54-G59.

Supt. of Docs. no.: 119.3:1457-G

**计划程序设** 

 Geology, Stratigraphic-Nomenclature-Northwest, Pacific. I. Swanson, Donald A. II. Series, III. Series: United States. Geological Survey. Bulletin; 1457-G.

QE75,B9 no. 1457-G [QE645] 557,3'08s [551,7'8]

79-607047

For sale by the Superintendent of Documents, U. S. Government Printing Office
Washington, D. C. 20402
Stock Number 024-001-03217-1

Abstract Introduction -----Acknowledgments -----Imnaha Basalt Picture Gorge Basalt -----Yakima Basalt Subgroup Grande Ronde Basalt Contact relations Flows of Prineville chemic: Redefinition of the Vantage Sa Wanapum Basalt Eckler Mountain Member Frenchman Springs Memb Roza Member Squaw Creek Diatomi Priest Rapids Member ... Saddle Mountains Basalt \_\_\_\_ Umatilla Member Wilbur Creek Member \_\_ Asotin Member Weissenfels Ridge Member Esquatzel Member Pomona Member Elephant Mountain Memb Buford Member -----Ice Harbor Member Lower Monumental Memb References cited \_\_\_\_\_ ILL PLATE 1. Maps showing inferred

the Columbia River I

ered by Columbia Ri-2. Chart showing proposed

Group ------3. Schematic stratigraphi

showing chemical typ

FIGURE 1. Map showing localities

を見ることでは、これには、日本のでは、日本

\_\_

C

# CONTENTS

	Page
Abstract	G1
Introduction	1
Acknowledgments	8
Imnaha Basalt	8
Picture Gorge Basalt	12
Yakima Basalt Subgroup	
Grande Ronde Basalt	
Contact relations	21
Flows of Prineville chemical type	24
Redefinition of the Vantage Sandstone Member	24
Wanapum Basalt	25
Eckler Mountain Member	
Frenchman Springs Member	31
Roza Member	33
Squaw Creek Diatomite Bed and Quincy Diatomite Bed	34
Priest Rapids Member	35
Saddle Mountains Basalt	. 38
Umatilla Member	40
Wilbur Creek Member	42
Asotin Member	
Weissenfels Ridge Member	44
Esquatzel Member	. 45
Pomona Member	46
Elephant Mountain Member	48
Buford Member	
· Ice Harbor Member	
Lower Monumental Member	
References cited	. 54
References cited	
<del></del>	
ILLUSTRATIONS	
_ <del></del>	
	Page
PLATE 1. Maps showing inferred original distribution of stratigraphic units in the Columbia River Basalt Group	ocke
FIGURE 1. Map showing localities mentioned in text and approximate area covered by Columbia River Basalt Group	. G2
2. Chart showing proposed terminology for the Columbia River Basalt	. <del>-</del>
Group	
3. Schematic stratigraphic section in Benjamin Guich, Washington	
showing chemical types	22
attounts circumous alkan	

The state of the s

OF THE INTERIOR

ecretary

VEY

irector

)ata. .....

1.7'8]

102 3217-1

32

Islumbia River Basalt group.

nwest, Pacific. I. Swanson, ates. Geological Survey.

79-607047

S. Government Printing Office

vey bulletin ; (457-G)

IV

CONTENTS

#### **TABLES**

Table	1. Comparison of stratigraphic terminology used by Bingham and Grolier (1966) and Wright and others (1973) with that of this paper	
	2. Average major-element composition of chemical types in the Colum-	-
	bia River Basalt Group	10

CONTRIBUT

# REVISIONS NOMENO COLUMBIA F

By D. A. Swanson

New stratigraphic nomenclatu is introduced to revise and expa divisions made informally by T. I The Yakima Basalt is raised to Ronde Basalt, Wanapum Basalt, age-are defined within it. The from oldest to youngest, the Eck Rapids Members. The Saddle M oldest to youngest, the Umatilla, Pomona, Elephant Mountain, Bu The Picture Gorge Basalt is rest Imnaha Basalt, is used for basa area of Washington, Oregon, ar tween basalt flows are excluded the group is revised to early, m argon dates ranging from about 1 vertebrate fossils in the interbec

te del ange bir enter the benefit in the land

I

The basalt on the Columgon, and Idaho has been the years. As geologic mapping formal stratigraphic nome: ture used by current worknames based largely on the (1955; 1961), Bond (1963) (1973), and Hooper (1974)

<sup>1</sup> Department of Geology, Washington Sta

<sup>&</sup>lt;sup>3</sup> Department of Geology, Central Washir

CONTRIBUTIONS TO STRATIGRAPHY

iology used by Bingham and

thers (1973) with that of this

of chemical types in the Colum-

のも、するからは日本教育教育を受けるのでは、中国の教育主義教育教育教育教育教育教育教育教育教育、これであるとでは、これ

# REVISIONS IN STRATIGRAPHIC NOMENCLATURE OF THE COLUMBIA RIVER BASALT GROUP

By D. A. Swanson, T. L. Wright, P. R. Hooper, and R. D. Bentley<sup>2</sup>

#### ABSTRACT

New stratigraphic nomenclature for units within the Columbia River Basalt Group is introduced to revise and expand that currently in use; it is based largely on subdivisions made informally by T. L. Wright, M. J. Grolier, and D. A. Swanson in 1973. The Yakima Basalt is raised to subgroup status, and three formations—the Grande Ronde Basalt, Wanapum Basalt, and Saddle Mountains Basalt, in order of decreasing age-are defined within it. The Wanapum contains four formally named members, from oldest to youngest, the Eckler Mountain, Frenchman Springs, Roza, and Priest Rapids Members. The Saddle Mountains Basalt is divided into 10 members, from oldest to youngest, the Umatilla, Wilbur Creek, Asotin, Weissenfels Ridge, Esquatzel. Pomona, Elephant Mountain, Buford, Ice Harbor, and Lower Monumental Members. The Picture Gorge Basalt is restricted to north-central Oregon, and a new name, the Imnaha Basalt, is used for basalt probably of pre-Picture Gorge age in the tristate area of Washington, Oregon, and Idaho. All significant sedimentary interbeds between basalt flows are excluded from the Columbia River Basalt Group. The age of the group is revised to early, middle, and late Miocene, on the basis of potassiumargon dates ranging from about 16.5 to about 6 m.y. and reinterpretation of the age of vertebrate fossils in the interbedded Ellensburg Formation.

#### INTRODUCTION

The basalt on the Columbia Plateau (fig. 1) in Washington, Oregon, and Idaho has been the subject of much study during the last 20 years. As geologic mapping has progressed, the need for a revised formal stratigraphic nomenclature has become apparent. Nomenclature used by current workers is a mixture of formal and informal names based largely on terms suggested by Mackin (1961), Waters (1955; 1961), Bond (1963), Schmincke (1967a), Wright and others (1973), and Hooper (1974). Despite the proliferation of informal

\* Department of Geology, Central Washington University, Ellensburg.

<sup>&</sup>lt;sup>1</sup> Department of Geology, Washington State University, Pullman.




FIGURE 1.-Localities mentioned in text and approximate area covered by Columbia River Basalt Group (outlined).

# NUMERICAL KEY

1.	Grangeville	18, Enterprise	30, Eckler Mountain	60, Reese
	Rocky Canyon	19. Little Sheep Creek	41, Rodgers Guich	61, Pasco
	Dug Bar	20, Silcott	42, Crall Hollow	62. Wallula Gap
	Impaha	21. Alpowa Summit	43, Robinette Mountain	63. Benton City
-	Lewiston Orcharde	22. Uniontown Plateau	44. Tucamnon River	64, Richland
-	Lewiston, Idaho and	23. Puliman	(mouth)	65, Ward Gap
-•	Clarkston, Wash.	24. Wilbur Creek	45. Paiouse Falls	6δ, Manton
7.	Asotin	25. Maiden	46, Skookum Canyon	67, Wahatis Peak
	Weissenfels and	26, Almota Creek	47, Devils Canyon	68, Priest Rapids Da
	Montgomery	27, Horton Grade	48. Lower Monumental	69, Sentinel Gap
	Ridges	28. Hastings Hill Road	Dam	70. Huntzinger
9.	Grande Ronde	29, New York Guich	49, Cow Creek	71. Wanapum Dam
	Basait type	30. Dodge	50, Warden	72, Frenchman Sprin
	locality	31. Pomeroy	51, Othello	Coulee
10.	Joseph Creek	32. Benjamin Gulch	52, Scooteny Reservoir	73, Quincy Basin (SV
•	(mouth)	33. Anatone Butte	53, Esquatzei Coulee	pert)
11.	Slippery Creek	34, Troy, Oreg.	54, Old Maid Coulee	74. Rattlesnake Spri
	Shumaker Creek	35. China Cap Ridge	55, Mesa	75, Crescent Bar
	Anatone	36, La Grande	56, Basin City	76. Ellensburg
14.	Cloverland Grade	37. Wenatchee Guard	57, Eltopia	77, Roza Station
	Puffer Butte	Station	58, Walker grain	78, Pomona
	Buford Creek	38. Patrick Grade	elevator	79, Selah Gap
	<b>F</b> 1	- 11	to the United Dam	90 Values

81. Elephant Mountain	93, Izee
82, Donald Pass	94, Flat Creek
83. Union Gap	95, Dayville
84. Tieton River area	96, Picture Gorg
85, Bickleton	97, Force Fossil
86, Arlington	98, Holmes Cre-
87, Maryhill	99, Spray
88. Biggs	100, Service Cree
89, Camus Creek	101, Twickenhar
90, Dale	102, Girds Creek
91, Monument	103, Hardman
Mountain and	104, Lone Rock
Monument	105, Butte Creek
92. John Day	106, Beef Hollow

an' nera	IVA, GIROS CIGOR
91, Monument	103, Hardman
Mountain and	104, Lone Rock
Monument	105, Butte Creek
92. John Day	106, Beef Hallow
-2. voiii -2.	100, 1000 11000
	ALF
26, Almota Creek	76. Ellensburg
21, Alpowa Summit	57, Eltopia
IJ. Anatone	18, Enterprise
33. Anatone Butte	53, Esquetzel C
36, Arlington	94. Flat Creek
7, Asotin	17. Flora
6, Basin City	97. Foree Fossi
06, Beef Hollow	72. Frenchman
32. Benjamin Gulch	Springs C
32, Benton City	102, Girds Creek
55, Bickleton	9, Grande Ror
38, Biggs	9, Grande Roi Basait tv
13. Bingen	locality
16, Buford Creek	1. Grangeville
15. Bull Run area	103, Hardman
05. Butte Creek	28, Hastings F
89. Camus Creek	98, Holmes Cr
24, Cavendish	27, Horson Gra
35, China Cap Ridge	70. Huntzinger
14. Cloverland Grade	59, Ice Harbor
28. Colfax	4. Imnaha
08, Cow Canyon	93. lzee
49, Cow Creek	92, John Day
42. Crall Hollow	10. Joseph Cre
75, Crescent Bar	(mouth)
90. Dale	119, Kahlotus
95, Dayville	127, Kennewick
22. DDH-1 Drill	36, La Grande
holes	6. Lewiston.
} in	and Clas
Pasco	Wash.
21. DDH-3 Basın	5. Lewiston (
47. Devils Canyon	125, Lind
30, Dodge	19, Little She-
92. Donald Pass	104. Lone Rock
3. Dug Bar	48, Lower Mo
40. Eckler Mountain	tai Darr


names, agreement among : sequence, lateral variations lent. It appears timely to re clature to take into account across the Columbia Plates

81. Elephant

Mountain

66. Mabton

25, Maiden



roximate area covered by Columoutlined).

AD. Reese

Y (3

xler Mountain -igers Guitch all Hollow mnette Mountain . wonth) iouse Falls ookum Canyon wils Canyon ·wer Mönyimental Dam w Creek arden

heile oteny Reservoir quetzei Coulos d Maid Coules ---- City

Itopia alker grain ejevator ÷ Harbor Dam 61. Pasco Wailula Gap 62. 63. Benton City 64, Richland 65, Ward Gap 66. Mabton Wahatis Peak 68. Priest Rapide Dam Sentinel Gap 70. Huntzinger

71, Wanapum Dam 72. Frenchman Springs Coules

73, Quincy Basin (SW part) 74. Rattlesnake Spring

75. Crescent Bar 76. Ellensburg

77, Roza Station 78. Pomona

79, Selah Gap 80, Yakima

31, Elephant Mountain 82. Donald Pass

83. Union Gap 84. Tieton River area 85. Bickleton

86. Arlington 87. Maryhill 88. Biggs

89, Camus Creek 90. Dale 91. Monument Mountain and Monument

92. John Day

1

93. [zee 94, Flat Creek 95. Dayville 96. Picture Gorge

97, Force Fossil Beds 98, Holmes Creek 99. Spray 100, Service Creek

102, Girds Creek 103, Hardman 104. Lone Rock 105, Butte Creek

106, Beef Hollow

101. Twickenham

107, Prineville Dam 108, Cow Canyon 109, Maupin 110. Sherars Bridge 111, Tygh Ridge

112, Mosier 113, Bingen 114. White Salmon 115. Bull Run area 116. Pack Sack Lookout 117, Umatilla

118. Milton-Freewater 119, Kahlotus 120, Pikes Peak

121, DDH-3 Drall holes

Pasco 122, DDH-1 123, Orofino

124. Cavendish 125, Lind 126. Palouse River (mouth) 127. Kennewick

128, Colfax

ALPHABETICAL KEY

26. Almota Creek 21. Alpowe Summit 13, Anatone 33. Anatone Butte 86. Arlington 7, Asotin 56. Basin City 106, Beef Hollow 32. Benjamin Gulch 63. Benton City 85. Bickleton 88. Biggs 113, Bingen 16. Buford Creek 115. Bull Run area

105. Butte Creek 89. Camus Creek 124. Cavendish 35, China Cap Ridge 14. Cloverland Grade 128, Colfax 108, Cow Canyon 49. Cow Creek 42, Crall Hollow

75, Crescent Bar 90. Dale 95. Dayville 122. DDH-1 Drill hales ŧп 121. DDH-3 Basın

17. Devils Canyon 30, Dodge 82. Donald Pass 3. Dug Bar

40. Eckler Mountain 81. Elephant

76. Ellensburg 57. Eltonia 18. Enternrise 53. Esquatzel Coulee 94, Flat Creek 17. Flora 97. Force Fossil Beds 72. Frenchman Springs Coulee 102. Girda Creek 9. Grande Ronde Basalt type locality 1. Grangeville 103, Hardman 28. Hastings Hill Road 98. Holmes Creek 27. Horton Grade 70. Huntzinger 59, Ice Harbor Dam 4. Imnaha 93. Izee 92, John Day 10. Joseph Creek mouthi 119, Kahlotus 127. Kennewick 36. La Grande 6. Lewiston, Idaho and Clarkston. Wash.

5. Lewiston Orchards 125, Lind 19, Little Sheep Creek

104. Lone Rock 48. Lower Monumen tal Dam

66. Mapton 25. Malden 39, Marengo 87, Maryhill

109, Maupin 55, Mesa 118, Milton-Freewater

91. Monument Mountain and Monument

112, Mosier 29, New York Gulch 54. Old Maid Coulee 123. Orofino 51. Othello

116, Pack Sack Lookout 45. Palouse Falls 126. Palouse River

(mouth) 61. Pasco 38, Patrick Grade 96. Picture Gorge

120, Pikes Peak 31. Pomeroy 78. Pomona 68. Priest Rapids Dam 107. Prineville Dam 15. Puffer Butte

23. Pullman 73. Quincy Basin (SW part) 74. Rattlesnake Spring 50, Recse

64, Richland 43. Robinette Mountain

2. Rocky Canyon 41. Rodgers Guich 77. Roza Station

52. Scooteny Reservoir 79. Selah Gap

69, Sentinel Gap 100, Service Creek

110, Sherars Bridge 12. Shumaker Creek 20, Silcott

46. Skookum Canyon 11, Slippery Creek

99, Spray 84, Tieton River area 34, Troy, Oreg.

44. Tucannon River (mouth)

101. Twickenham 111, Tygh Ridge 117. Umatilla

83. Union Gap 22. Uniontown Plateau.

67, Wahatis Peak 58. Walker grain elevator

62. Waliula Gap 71, Wanapum Dam

65, Ward Gap 50, Warden 8. Weissenfels and

Montgomery Ridges 37. Wenatchee Guard

Station 114. White Salmon

24, Wilbur Creek 80, Yakima

names, agreement among current workers regarding stratigraphic sequence, lateral variations, and flow correlations is generally excellent. It appears timely to revise and supplement the existing nomenclature to take into account the persistence of stratigraphic relations across the Columbia Plateau.

وريه

Table 1.—Comparison of stratigraphic terminology within the Columbia River Basalt Group used by Bingham and Grolier (1966) and Wright and others (1973) with that of this paper

Bing	gham and Grolier (1966, fig. 1)	1	Informal nomenciature of ght and others (1973, table 1)		This report
Yakina Busalt	cham and Groller (1966, fig. 1)  Saddle Mountains Member	Yakima basalt	Upper Yakima basait:  Flows at Ice Harbor Dam  Ward Gap and Ele- phant Mountain basait of Schmincke (1967a) Fomona basait of Schmincke (1967a)	Yakima Baselt Subgroup	This report  Saddle Mountains Basalt: Lower Monumental Member (new) Ice Harbor Member (new) Buford Member (new) Elephant Mountain Member  Pomona Member  Esquatzel Member (new) Weissenfels Ridge Member (new) Wilbur Creek Member (new) Umatilla Member
Y	Priest Rapids Member Quincy Diatomite Bed  Roza Member	Yaki	Middle Yakima basalt: Priest Rapids member, including Umatilla basalt of Schmincke (1967a); Lolo Creek flow of Bond (1963) Roza Member	Yakima B.	Wanapum Basalt (naw); Priest Rapids Member Roza Member
	Squaw Creek Diatomite Bed Frenchman Springs Member		Frenchman Springs Member		Frenchman Springs Member Eckler Mountain Member (new)
	Vantage Sandstone Member Lower basait flows		Lower Yakima basalt		Grande Ronde Basalt (new)
			Picture Gorge basalt Lower basalt of Bond (1963)		Picture Gorge Basait Imnaha Basait

One reviewer of this paper anced" because the Columbia subgroup. He suggested abar group, or introducing a new t Imnaha and Picture Gorge B Picture Gorge to subgroup st clature provides more flexi changes. The term Yakima i gained by dropping it from for contain the Imnaha and Pict: mations. Elevating each to : the Code of Stratigraphic No within them, a premature ste work progresses, the Imnah divided into members. If thes into mappable units, the two elevated to subgroup and for progress on the Columbia Pla nition of more members wit. even new formations. The s this paper is flexible enough

Many whole-rock potassiur made on rocks of the Columb Early results were inconsist nearly all dates published sir m.y. and 6 m.y. (Holmgren, kins and Baksi, 1974; Atlant and others, 1977). Flows stra m.y. are known. The young youngest known flow in the g ing to Berggren and Van Miocene extends from about : m.v. (14.8 to 15.3 m.y.), and (10.5 to 10.8 m.y.). Their wo Gill and McDougall, 1973; K and Page, 1975; McDougall & Pliocene boundary is no olde lumbia River Basalt Group, middle, and late Miocene, t potassium-argon age determ

のでは、100mmの

The group was previously on the basis of vertebrate fos. intertongues with and over The vertebrate ages have

phic subdivision have been 1), Mackin (1961), and Bingecently introduced the term le all the extrusive volcanic imbia River Group and to ionbasaltic. We follow this bgroup, 5 formations, and 14 menclature, in some cases evised stratigraphic nomenrelation to the terminology √right and others (1973) in

y within the Columbia River Basalt Wright and others (1973) with that

	i	* * * * * * * * <del>* * * * * * * * * * * </del>
	1	
1)		This report
		Saddle Mountains Basalt:
	1	Lower Monumental
	1	Member (new)
•		ice Harbor Member
_		(new)
* L 4	1 :	Buford Member (new)
		Elephant Mountain
		Member
• `		
E-040007%		Pomona Member
		t quique member.
		Esquatzel Member
		(new)
		Weissenfels Ridge
0	۱.	Member (new)
	5	Asotin Member (new)
	4	Wilbur Creek Member
. • •	ą.	(new)
	3	Umatilia Member
N	34	Wanspum Basait (new):
r,	#	Priest Rapids Member
	X	,
	,ª	
	ı	
60	ļ	
	- 1	Roza Member
~	- 1	Ì
	- 1	Frenchman Springs
		Мешьег
	1	Eckler Mountain
}		Member (new)
1	- 1	
		Grande Ronde Basalt (new)
î	i i	0
•••	•	Picture Gorge Basait
	1.2 . 9 3	Yakını Basalı Subgroup

One reviewer of this paper felt that the nomenclature was "unbalanced" because the Columbia River Basalt Group contains only one subgroup. He suggested abandoning the name Yakima Basalt Subgroup, or introducing a new term for a subgroup containing both the Imnaha and Picture Gorge Basalts, or raising both the Imnaha and Picture Gorge to subgroup status. We believe the proposed nomenclature provides more flexibility than any of these suggested changes. The term Yakima is well known, and there is little to be gained by dropping it from formal status. Coining a new subgroup to contain the Imnaha and Picture Gorge in effect freezes them as formations. Elevating each to subgroup status requires, according to the Code of Stratigraphic Nomenclature, that formations be defined within them, a premature step at this time. We recommend that, as work progresses, the Imnaha and Picture Gorge Basalts be subdivided into members. If these members are themselves subdivisible into mappable units, the two formations and their members can be elevated to subgroup and formational status, respectively. Work in progress on the Columbia Plateau is expected to result in the recognition of more members within all of the formations, and perhaps even new formations. The stratigraphic nomenclature proposed in this paper is flexible enough to accommodate such changes readily.

Many whole-rock potassium-argon age determinations have been made on rocks of the Columbia River Basalt Group in recent years. Early results were inconsistent (Gray and Kittleman, 1967), but nearly all dates published since 1970 have been between about 16.5 m.y. and 6 m.y. (Holmgren, 1970; Baksi and Watkins, 1973; Watkins and Baksi, 1974; Atlantic Richfield Hanford Co., 1976; McKee and others, 1977). Flows stratigraphically below those dated at 16.5 m.y. are known. The youngest date is from the stratigraphically youngest known flow in the group (McKee and others, 1977). According to Berggren and Van Couvering (1974, p. 172), the early Miocene extends from about 23.5 m.y. (22.7 to 24.2 m.y.) to about 15 m.y. (14.8 to 15.3 m.y.), and the middle Miocene to about 10.7 m.y. (10.5 to 10.8 m.y.). Their work and that of others (Berggren, 1972; Gill and McDougall, 1973; Kennett and Watkins, 1974; McDougall and Page, 1975; McDougall and others, 1977) indicate the Miocene-Pliocene boundary is no older than about 5.3 m.y. Rocks of the Columbia River Basalt Group, then, were erupted within the early, middle, and late Miocene, but not the Pliocene, according to the potassium-argon age determinations.

The group was previously considered to extend into the Pliocene on the basis of vertebrate fossils in the Ellensburg Formation, which intertongues with and overlies the group in central Washington. The vertebrate ages have recently been reinterpreted as late

			Sub -	Formation	A.A. B.	K-Ar age	Magnetic	Chemical type 1										
Se	Series Group g		Group Sub Fo		Member	(m. y.)	polarity	Dominant	Subordinate									
	l .				Lower Monumental Member	62	Ŋ	31										
	<u>د</u>				Erosional unconformity													
	]													Ice Harbor Member			***************************************	Ī
	0				Basali of Goose Island	8.5 <sup>2</sup>	N	30										
	€ .				Basalt of Martindale	8 5 <sup>2</sup>	R	29										
	-						Basali of Basin City	8.5 <sup>2</sup>	N	28								
m	Q.	٩	<u>a</u>	Saddle Mountains		Erosional unconformity												
z	ء ا	Group	Subgroup		Buford Member		R	27										
ш			6qn			Elephant Mountain Member	10.52	N, T	26									
							Erosional unconformity											
U		'	Basolt	Basali	Pomona Member	122	Ř	25										
0					Erasianal unconformily:													
_		포	Үокіто		Esquatzel Member		N	24										
	ب	Basati	ç	]	Erosional unconformity													
≥	ء				Weissenfels Ridge Member													
	٥	ĺ			Basalt of Slippery Creek		N	22										
	٥				Basali of Lewiston Orchards		N	23	18									
	 				Asolin Member		И	1 21										
	_				Local erosional unconformily													
				ļ	Wilbur Creek Member		N	20										
		1			Umaiilla Member		N	19										
				ĺ	Local erosional unconformily:													

				In i A Davida Mamber		R <sub>3</sub>	18	17
			1 1	Priest Rapids Member		R <sub>3</sub>	16	
, 1	U		Basalt	Roza Member		<sub>1</sub>	<del></del> -+	
	-			Franchman Springs Member		N	15	
	o o			Eckler Mountain Member Basalt of Shumaker Creek		N <sub>2</sub>	14	
۱ س	. <u>-</u> .≨	River		Bosali of Dodge		N <sub>2</sub>	13	
Z	_	~		Basali of Robinette Mountain		N <sub>2</sub>	12	
ш			1 1 4		14-16.5	N <sub>2</sub>		
U		į	Grande	ļ			Į	
0	ے ا	olumbio	Ronde Basalt	/Basali of Dayville \5		R <sub>2</sub>	9,10	
-	٥	6	Pictura	Basalt of Monument Mountain	()46.		(6, 7) 5	8, 11

COLUMBIA

Liquatzel Member	N	24	
Leosional inconformity			
Weissenfels Ridge Member	*******		
Basali of Slippery Creek	N	22	ŀ
Basalt of Lewiston Orchards	N	23	18
Asolin Member	N	21	<del></del> -
Local erosional unconformity			
Wilbur Creek Member	N	20	
Umatilla Member	N	10	
local erosional unconformily			

ı	ı	i	l	Wanapum	Priest Rapids Member		R <sub>3</sub>	18	17
١	- }			Basali	Roza Member		R <sub>3</sub>	16	
١	l	-			Frenchman Springs Member		N	15	
1	ш	70 70 	ň		Eckler Mountain Member Basalt of Shumaker Creek		N <sub>2</sub>	14	
1	$_{z}$	₹	River		Bosali of Dodge		N <sub>2</sub>	13	
1				1)	Basalt of Robinette Mountain		N <sub>2</sub>	12	
1	U	<b>.</b>		Grande	·	14-16.5 3	N <sub>2</sub>		
	0	c 6	Columbio	Ronde Basalt	Basalt of Dayville  (Basalt of Monument Mountain)		R <sub>2</sub>	9,10	
	\$	۰ ¥	ŭ	Gorge Basoli 4 - ? - ? -	Basalt of Twickenham	(14.6- 15.8) \$, 3	N <sub>1</sub>	(6, 7) <sup>5</sup>	8, 11
		٠.					R,		
		w 0 1	    - 	lmríaha Basali <sup>4</sup>		R	N <sub>o</sub>	2, 4	1, 3, 5

See table 2 for key to chemical types.
 Data from McKee and others (1977)
 Data mostly from Waikins and Baksi (1974)

4 The Imnaha and Picture Garge Basalts are nowhere known to be in cantact. Interpretation of preliminary magnetostratigraphic data suggests that the Imnaha is everywhere older than the Picture Gorge. See text.

Information in parentheses refers to Picture Gorge Basalt

FIGURE 2.-Proposed terminology for the Columbia River Basalt Group. N is normal magnetic polarity; R, reversed; and T, transitional. Polarity intervals are numbered sequentially, oldest to youngest, for the Imnaha through Wanapum Basults, as we believe no major intervals are missing. Polarity intervals are not numbered in the Suddle Mountains Basalt, as one or more major intervals are probably missing owing to long periods of time between eruptions. For the Ice Harbor Member, probably no major intervals are missing, as potassium-argon ages for flows of the three magnetostratigraphic units are similar. Interbedded sedimentary deposits not shown.

Miocene by C. A. Repenning (written commun., 1977). The age of the Columbia River Basalt Group as presently known is therefore almost certainly restricted to the Miocene on a paleontologic as well as a radiometric basis.

The stratigraphic units shown in figure 2 are described here, oldest to youngest, and their inferred original distributions are presented in plate 1. Localities mentioned in the text are indicated on figure 1, which should be referred to whenever type or reference localities or other sites of interest are given. Township and range designations are referenced to the Willamette Base Line and Meridian in Washington and Oregon and the Boise Base Line and Meridian in Idaho. Chemical analyses used to define chemical types in the Yakima Basalt Subgroup are given by Wright and others (1979).

### **ACKNOWLEDGMENTS**

Discussions with many geologists have led to the terminology introduced in this paper. We particularly thank D. J. Brown, R. K. Ledgerwood, C. W. Myers, and S. M. Price, all of Atlantic Richfield Hanford Co.; A. C. Waters, University of California, Santa Cruz; V. E. Camp, formerly of Washington State University; M. R. Ross, University of Idaho; and R. T. Helz, U.S. Geological Survey, for their help in defining the stratigraphy and selecting appropriate names. We also thank R. W. Kopf, U.S. Geological Survey, for constant prodding to get these names on record. The suggestions of J. M. Donnelly, N. S. MacLeod, and G. W. Walker substantially improved the manuscript.

#### IMNAHA BASALT

The Imnaha Basalt is the oldest formation within the Columbia River Basalt Group. The Imnaha was informally named by Hooper (1974), following a suggestion by Taubeneck (1970). Hooper designated a type locality at Dug Bar, on the Snake River near the mouth of the Imnaha River in extreme northeast Oregon. The formal name Imnaha Basalt is adopted here and replaces the informal term "lower basalt" used by Bond (1963) and Wright and others (1973).

The type locality is the exposures in cliffs on the west side of the Snake River above the north end of Dug Bar, Wallowa County, Oreg. (Cactus Mountain quadrangle, Idaho-Oregon: pl. 1, fig. A). It is reached by boat or by a dirt road down the Imnaha Valley from the town of Imnaha, Oreg. Fourteen flows, totaling nearly 500 m in thickness, have been described at the type locality by Kleck (1976) and Vallier and Hooper (1976). The base of the formation is not exposed at the type locality but can be seen at the south end of Dug Bar, where the basalt unconformably overlies deformed pre-Tertiary rocks. The Imnaha Basalt is conformably overlain by the Grande

Ronde Basalt at the type loca Good reference localities fo near the confluence of Lower near the town of Imnaha, Or faulted anticline forming the ticularly near the center of T. the lower part of Rocky Canyo km west of Grangeville, Idah den and Hooper, 1976).

Waters (1961) tentatively Imnaha Basalt in his Picture slight petrographic difference work (Wright and others, 197 1974; McDougall, 1976) has a in different areas and that a nificant chemical and isoto mapping, discussed in a later the upper part of the Pictur than the Imnaha. For these rate formations.

The Imnaha Basalt has be adjacent Washington and Ida underlies the Grande Ronde cussed in the section on the may occur as far west as a southwest of La Grande, O Tertiary metamorphic and p unconformity having local r flows are as much as 120 m t irregular surface.

THE CANADA TO SEE STATE DESIGNATION OF THE PROPERTY OF THE PRO

Most flows of Imnaha Bas phyric, some, such as the (Hooper, 1974; see also Kleck chemical types have been Knowles (1976), Holden and Hooper (1976), and Reic zeolite amygdules (Kleck, 19 tion is widespread. Most floweather to a grus owing to t secondary minerals. Waters between the Imnaha and marked by a distinct topogradeveloped in the Imnaha and erally fresher Grande Ronda

ommun., 1977). The age of resently known is therefore ie on a paleontologic as well

re 2 are described here, oldginal distributions are prein the text are indicated on enever type or reference lon. Township and range destte Base Line and Meridian · Base Line and Meridian in chemical types in the Yakht and others (1979).

### ENTS

e led to the terminology inthank D. J. Brown, R. K. ce, all of Atlantic Richfield of California, Santa Cruz; ate University: M. R. Ross, Geological Survey, for their lecting appropriate names. gical Survey, for constant The suggestions of J. M. ker-substantially improved

ation within the Columbia formally named by Hooper neck (1970). Hooper designake River near the mouth t Oregon. The formal name places the informal term Vright and others (1973). iffs pa the west side of the ug Bar, Wallowa County, ho-Oregon: pl. 1, fig. A). It n the Imnaha Valley from s, totaling nearly 500 m in be locality by Kleck (1976) of the formation is not exn at the south end of Dug rlies deformed pre-Tertiary ly overlain by the Grande

Ronde Basalt at the type locality.

Good reference localities for the Imnaha Basalt are: (1) the area near the confluence of Lower Sheep Creek and the Imnaha River near the town of Imnaha, Oreg. (Kleck, 1976); (2) the core of the faulted anticline forming the north side of the Lewiston Basin, particularly near the center of T. 11 N., R. 45 E. (Camp, 1976); and (3) the lower part of Rocky Canyon in SE4 sec. 18, T. 30 N., R. 1 W., 25 km west of Grangeville, Idaho, in the Salmon River drainage (Holden and Hooper, 1976).

Waters (1961) tentatively included what is here defined as the Imnaha Basalt in his Picture Gorge Basalt, although he recognized slight petrographic differences between them (1961, p. 608). Later work (Wright and others, 1973; Nathan and Fruchter, 1974; Hooper, 1974; McDougall, 1976) has demonstrated that the two units occur in different areas and that most flows in the two units show significant chemical and isotopic differences. Magnetostratigraphic mapping, discussed in a later section, further suggests that at least the upper part of the Picture Gorge in central Oregon is younger than the Imnaha. For these reasons, we designate the two as separate formations.

The Imnaha Basalt has been found only in northeast Oregon and adjacent Washington and Idaho (pl. 1, fig. A), where it conformably underlies the Grande Ronde Basalt. These contact relations are discussed in the section on the Grande Ronde Basalt. Imnaha flows may occur as far west as along the upper Grande Ronde River southwest of La Grande, Oreg. The Imnaha Basalt overlies pre-Tertiary metamorphic and plutonic rocks along a rugged erosional unconformity having local relief of more than 500 m. Some of its flows are as much as 120 m thick as a result of local ponding on this irregular surface.

Most flows of Imnaha Basalt are coarse grained and plagioclase phyric, some, such as the informally named Rock Creek flow (Hooper, 1974; see also Kleck, 1976, and Bond, 1963), highly so. Five chemical types have been distinguished by Hooper, Kleck, and Knowles (1976). Holden and Hooper (1976), Kleck (1976), Vallier and Hooper (1976), and Reidel (1978) (table 2). Many flows contain zeolite amygdules (Kleck, 1976; Hooper, 1974), and smectitic alteration is widespread. Most flows in a typical section of the Imnaha weather to a grus owing to their coarse grain size and abundance of secondary minerals. Waters (1961) accurately described the contact between the Imnaha and Grande Ronde Basalts as commonly marked by a distinct topographic break between grus-covered slopes developed in the Imnaha and bold cliffs in the fine grained and generally fresher Grande Ronde.

Table 2-Average major-element compositions for chemical types in the Columbia River Basalt Group

[Averages include analyses available through March 1977. Variation within chemical types 9-31 given by Wright and others (1979, table 3)]

Chemical type	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15 (
Oxide	(7)4	(44)	(21)	(68)	(7)	(8)	(4)	(13)	(13)	(8)	(10)	(9)	(20)	(4)	(8)
SiO <sub>1</sub> ALO <sub>1</sub> TeGO** MgO CaO Na <sub>1</sub> O K <sub>2</sub> O TiO <sub>2</sub> P <sub>2</sub> O <sub>3</sub> MnO Totul <sup>3</sup>	50.99 15.42 12.24 5.94 10.11 2.55 .53 1.66 .34 .22	51.14 15.06 13.04 5.07 9.31 2.58 91 2.24 -42 -22 99.99	51.18 14.06 14.11 4.60 8.59 2.65 1.19 2.93 .48 .22	49.53 16.34 12.38 6.06 9.15 2.58 .93 2.41 .20 100.00	50.73 17.10 11.26 5.42 9.30 2.45 .85 2.32 .38 .19	50.36 15.54 11.25 6.68 10.67 2.95 .57 1.56 .22 .20	51.46 15.39 12.46 4.86 9.45 3.29 .74 1.79 .33 .23	61.57 13.87 12.28 4.44 8.12 3.36 2.02 2.71 1.39 24	53.78 14.46 11.36 5.25 9.07 2.83 1.05 1.78 .28 .19	55.94 14.04 11.77 3.36 6.88 3.14 1.99 2.27 .43 .19	54.37 15.28 9.46 5.91 9.79 2.80 .77 1.17 .29 .16	50.01 17.08 10.01 7.84 11.01 2 44 .27 1.00 .19 .14	52.13 15.41 10.68 5.92 10.18 3.00 .68 1.48 .35 .19	54.80 13.88 13.32 2.84 5.48 3.18 1.87 2.46 .93 .26	52.29 13.21 14.38 4.04 7.90 2.67 1.41 3.17 .71 .22

Table 2—Average major-element compositions for chemical types in the Columbia River Basalt Group—Continued

Chemical type	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
Oxide	(35)	(15)	(55)	(13)	(11),	(6)	(3)	(2)	1121	(30)	(41)	(8)	(12)	(13) .	(8)	(24)
SiO, Al.O, FeO	13.91 4 39 8 48 9 79	50 27 13.69 15.04 4.29 8.31 2.67 1.16	50.09 14.31 13.78 5.18 8.88 2.57 1.07	54.70 14.10 12.63 2.71 6.14 3.20 2.68	54.41 14.51 11.07 4.51 8.32 2.69 1.77	50 72 16 23 9 64 8 19 10 70 2 22 51	52.12 14.33 11.64 5.58 9.64 2.69 .87	49 75 15.26 11.82 7.10 10.13 2 32 .46	54.16 13.84 12.60 3.91 7.71 2.66 1.70	51.88 14.88 10.55 6.96 10.67 2.36	51.08 13.54 14.75 4.28 8.34 2.45 1.25	54.46 14.29 11.05 4.85 8.54 2.75 1.39	47.45 13.84 15.22 5.99 9.71 2.31 .72	48.73 13.88 14.41 5.88 9.72 2.42 .73 9.30	47.50 12.50 17.53 4.41 8.80 2.44 1.23 3.79	50.4 14.0 13.7 5.0 8.6 2.7

e a la managament fire fire freig to freig al manage en a constitue con mile o con the constitue and the fire fire fire freight freight and constitue and the fire fire freight freigh

COLUMBIA R

3 18 1.87

2.46 .93 .26

100.00

_	
L	1
_	ī

	к	
•		J
	d.	
	11. 数重五	
A CALL CONTROL OF THE PROPERTY	desired to	

100.00

3.36 2.02 72.71 1.39.5 -24 100.00

100 01

3 14 1.99 2.27 .43 .19

100.01

2 44 .27 1.00 .19 .14

2.80 .77 1-17 29 .16

100.00

Table 2-Average major element compositions for chemical types in the Columbia River Basalt Group-Continued

Chemical type	16	17	18	19	(11)	(6)	(3)	(2)	(12)	25 (30)	(41)	(8)	28 (12)	131	30	31
	(35)	(15)		(13)												
\$iO,	51.19	50 27	50 09	54 70	54 41	50.72	52.12	49 76	54.16	51.88	51.08	54.46	47.45	48 73	47 50	50 44
Al <sub>2</sub> O <sub>3</sub>	14.07 13. <del>9</del> 1	13 69 15 04	14 31 13 78	14 10 12 63	14 51 11 07	16 23 9.64	14.33 11.64	15 26 11.82	13.84 12.60	14.88 10.55	13.54 14.75	14.29 11.05	13.84 15.22	13.88 14 41	12 50 17 53	14 07 13 78
MgO	4 39	1.29	5 18	271	4 61	8.19	5.58	7.10	3.91	6.96	4.28	4.85	5 99	5.88	4.41	5 01
C#O	8 48	831	સ લઘ	614	8.32	10.70	9.64	10 13	7.71	10.67	8.34	8.54	9.71	9 72	8 80	8 67
Na <sub>2</sub> O	2.72	2 67	2 57	3 20	2 69	2.22	2.69	2 32	2.66	2 36	2 45	2.75	2.31	2.42	2 44	2 79
к.б	1.22	1 16	1 07	2 68	1.77	.51	.87	46	1.70	64	1.25	1.39	.72	73	1.23	1 47
TiO,	3 13	3 55	3 15	2 80	1.95	1.45	2.48	2.42	2 82	1.62	3.52	2.17	3.62	3 30	3.79	2 90
P.O	.67	.81	78	88	56	16	49	.55	.41	.25	.59	.35	91	.73	1 54	.66
MnO	.23	21	19	17	21	.17	.17	.21	.19	.17	20	15	23	.20	.27	21
Total <sup>3</sup>	100.01	100 00	100 00	100 01	100 00	100 01	100.00	100 02	100.00	99.98	100.00	100.00	100.00	100.00	100 01	100 (x)

2.55 .51 .51

Total\* .... 100.00

Number of analyses used in computing average  $^{4}{\rm FeO}+0.9$  Fe,O  $_{\rm c}$  .  $^{2}{\rm FeO}_{\rm c}$  all fitterine between total and 100 is due to rounding during normalization.

100.00

2 55 91

100 60

100.00

100 00

- Chemical types defined by method of Wright and Hamilton (1978).

  1. Picture Gorge (Imnaha Basalt)

  2. American Bar (equivalent to the high-Ti Picture Gorge chemical type of Wright and others, 1973)

  3. Frenchman Springs (Innuha Basalt)

  4. Rock Creek

  5. Fall Creek (Kleck, 1976)

  6. High-Mg Picture Gorge (Wright and others, 1973)

  7. Low-Mg Picture Gorge (Wright and others, 1973)

  8. Prineville (recalculated from Upputur, 1974)

  9. High-Mg Grande Ronde (one flow)

  10. Low-Mg Grande Ronde (one flow)

  11. Very high Mg Grande Ronde (one flow)

- 12. Robinette Mountain

- Dodge Shumaker Creek Frenchmen Springs (one flow)
- 15. 16. Roza

- 17. Rosalis 18. Lolo 19. Umutilla 20. Wilbur Creek

- 21. Auotin 22. Slippery Creek

- 23. Lewiston Orchards
  24. Esquatzel
  25. Permona
  26. Elephant Mountain
  27. Buford
  28 Basin City
  29. Murtindale (Ice Harbor 1)
  30. Goose Island tice Harbor 2)
  31 Lower Monumental

A few thick feeder dikes of the Imnaha Basalt have been found along the Imnaha River in extreme northeast Oregon (Kleck, 1976), and many others are inferred, on the basis of chemical composition and the age of the rocks cut by the dikes, to be present in western Idaho and northeast Oregon (pl. 1, fig. A; W. H. Taubeneck, T. L. Wright, and D. A. Swanson, unpub. data, 1978).

Most flows of Imnaha Basalt have normal magnetic polarity (Hooper, Camp, Kleck, Reidel, and Sundstrom, 1976; Hooper and others, 1979). The upper two flows in the Imnaha area have transitional polarity. Several thin reversed flows along the Minam River east of La Grande, Oreg., conformably underlie reversely magnetized flows in the Grande Ronde Basalt, and two or three flows beneath a thick section of normally magnetized Imnaha Basalt on China Gap Ridge in the Wallowa Mountains are tentatively identified as magnetically reversed (W. H. Taubeneck, D. A. Swanson, and D. O. Nelson, unpub. portable fluxgate magnetometer data, 1976). These two reversed sequences are, respectively, the youngest and oldest flows in the Imnaha Basalt recognized to date. We consider it likely that future work may find that the uppermost Imnaha is interbedded with the lowermost Grande Ronde Basalt.

#### PICTURE GORGE BASALT

Miocene flood basalt in the John Day basin of north-central Oregon was named the Picture Gorge Basalt by Waters (1961) for exposures at the type locality (pl. 1, fig B), Picture George, Oreg. Waters tentatively extended the term to cover flows in extreme northeast Oregon herein assigned to the Imnaha Basalt. He considered the Picture Gorge to be separated from the younger Yakima Basalt (now subgroup) by an angular unconformity.

The original definition of the Picture Gorge Basalt is retained here, except that the term is restricted to basalt in north-central Oregon (pl. 1, fig B) and excludes the flows in northeast Oregon, southeast Washington, and western Idaho herein assigned to the Imnaha Basalt (pl. 1, fig. A). Stratigraphic and magnetostratigraphic relations, described in a later section, indicate that the Picture Gorge is locally interlayered and hence coeval with the middle part of the Grande Ronde Basalt of the Yakima Basalt Subgroup.

The type section of the Picture Gorge Basalt is in roadcuts along U.S. Highway 26 near its junction with Oregon State Highway 19, SW¼ sec. 17, NE¼ sec. 18, and NW¼ sec. 20, T. 12 S., R. 26 W., in Picture Gorge, western Grant County, north-central Oregon (Waters, 1961). Here the formation contains 17 flows and is about 430 m thick, values revised from those in Waters (1961, table 1) as a result of unpublished mapping by R. D. Bentley in 1975. At Picture Gorge.

the formation unconformably Day Formation and conforma sequence of Miocene volcan Gorge ranges in thickness t Brown (1966a) reported mor though faulting may have di

Nathan and Fruchter (197the formation, one along Girc (Oles and Enlows, 1971; Swa 207 between Spray and Har two sections, but faulting (R. D. Bentley, unpub. mapp erence locality exposes more Mountain, in the south half quadrangle. Another good u: Holmes Creek road in secs. Gorge quadrangle.

Reconnaissance mapping erham, 1973) suggests that divided into three mappabl underlain and overlain by pla here informally referred to a sures along Kentucky Butte Kinzua quadrangle) near T sections occur along Highwa; in the cliffs above Foree Fo. Monument Mountain north o enham consists of two to s thickness from about 30 to 13 part of the unit. The flows ar coarse grained, and common zeolites (Lindsley, 1960; Linc exposed at the type locality

The middle unit, herein i Monument Mountain for expcurs as the lower six flows ir Good reference sections are f Kimberly, on Adler Butte r Butte near Twickenham. The sists of three to eight aphygrained and have well form top breccias and zeolite an phyric flow is present near tand Dale. The unit is norm

*c.* 

**\*** 

. ;

المراث الم

inaha Basalt have been found ortheast Oregon (Kleck, 1976), basis of chemical composition likes, to be present in western Ig. A; W. H. Taubeneck, T. L. lata, 1978).

ve normal magnetic polarity Sundstrom, 1976; Hooper and the Imnaha area have transiflows along the Minam River ably underlie reversely magnasalt, and two or three flows magnetized Imnaha Basalt on ountains are tentatively ident. Taubeneck, D. A. Swanson, fluxgate magnetometer data, are, respectively, the youngest it recognized to date. We connd that the uppermost Imnaha andé Ronde Basalt.

# E BASALT

ay basin of north-central Oresalt by Waters (1961) for expo-, Picture George, Oreg. Waters er flows in extreme northeast ha Basalt. He considered the e younger Yakima Basalt (now ty.

ure Gorge Basalt is retained

ted to basalt, in north-central le flows in northeast Oregon, Idaho herein assigned to the tigraphic and magnetostratisection, indicate that the Pichenic coeval with the middle he Yakima Basalt Subgroup. ge Basalt is in roadcuts along ith Oregon State Highway 19, sec. 20, T. 12 S., R. 26 W., in sy, north-central Oregon (Wans 17 flows and is about 430 maters (1961, table 1) as a result they in 1975. At Picture Gorge,

the formation unconformably overlies tuffaceous rocks of the John Day Formation and conformably underlies the Mascall Formation, a sequence of Miocene volcaniclastic rocks. Elsewhere, the Picture Gorge ranges in thickness to a maximum of 800 m. Thayer and Brown (1966a) reported more than 1,800 m along Flat Creek, although faulting may have duplicated part of this section.

Nathan and Fruchter (1974) described two reference localities for the formation, one along Girds Creek just southwest of Twickenham (Oles and Enlows, 1971; Swanson, 1969), the other along Highway 207 between Spray and Hardman; flows are well exposed in these two sections, but faulting obscures some stratigraphic relations (R. D. Bentley, unpub. mapping, 1973). An excellent unfaulted reference locality exposes more than 600 m of basalt on Monument Mountain, in the south half of sec. 19, T. 8 S., R. 28 E., Monument quadrangle. Another good unfaulted reference section is along the Holmes Creek road in secs. 4, 5, and 9, T. 10 S., R. 26 E., Picture Gorge quadrangle.

Reconnaissance mapping by R. D. Bentley (Bentley and Cockerham, 1973) suggests that the Picture Gorge Basalt can be subdivided into three mappable units, a sequence of aphyric flows underlain and overlain by plagioclase-phyric flows. The lower unit is here informally referred to as the basalt of Twickenham, for exposures along Kentucky Butte (sec. 13, 14, and 23, T. 9 S., R. 21 E., Kinzua quadrangle) near Twickenham, Oreg. Excellent reference sections occur along Highway 19 between Service Creek and Spray, in the cliffs above Force Fossil Beds, and along the lower part of Monument Mountain north of Monument, Oreg. The basalt of Twickenham consists of two to six plagioclase-phyric flows varying in thickness from about 30 to 130 m; the thicker flows are in the lower part of the unit. The flows are normally magnetized, generally very coarse grained, and commonly contain pegmatoids and abundant zeolites (Lindsley, 1960; Lindsley and others, 1971). The unit is not exposed at the type locality of the Picture Gorge Basalt.

The middle unit, herein informally referred to as the basalt of Monument Mountain for exposures north of Monument, Oreg., occurs as the lower six flows in the type section of the Picture Gorge. Good reference sections are found along Holmes Creek just south of Kimberly, on Adler Butte near Service Creek, and on Kentucky Butte near Twickenham. The basalt of Monument Mountain consists of three to eight aphyric flows that are medium to coarse grained and have well formed colonnades and entablatures. Flowtop breccias and zeolite amygdules are common. A plagioclasephyric flow is present near the top of the unit between Monument and Dale. The unit is normally magnetized (Watkins and Baksi,

۰.

: 1

1974; Nathan and Fruchter, 1974) and rests on the basalt of Twickenham everywhere except near the margins of the John Day basin, where it unconformably overlies the John Day Formation.

The upper unit, informally referred to as the basalt of Dayville for exposures near Dayville, Oreg., consists of 3 to 15 flows that are fine grained and generally plagioclase phyric. The upper 11 flows in the type section of the Picture Gorge belong to this unit. The flows have poorly formed colonnades but no entablatures. Thin flows of small areal extent are dominant, but some thick flows may extend long distances. The uppermost flows in the Monument-Picture Gorge area are magnetically reversed (Watkins and Baksi, 1974; Nathan and Fruchter, 1974), but elsewhere the unit is normally magnetized.

The three units within the Picture Gorge Basalt are used here in an informal sense, because we feel that more fieldwork must be done to confirm their lateral continuity. They can easily be elevated to member status if they prove to be valid discrete stratigraphic units.

The chemistry of the Picture Gorge Basalt varies gradationally within a rather well-defined compositional field termed the Picture Gorge chemical type by Wright and others (1973); two representative averages near the extremes of chemical variation are given in table 2. At the type locality, Mg and Cr decrease abruptly upward, and K, La, Th, Fe, Rb, and the rare-earth elements increase at the contact between the basalts of Monument Mountain and Dayville (Osawa and Goles, 1970; Wright and others, 1973; Bentley and Cockerham, 1973; Nathan and Fruchter, 1974).

Potassium-argon dating of samples from the type section suggests that the Picture Gorge Basalt is about  $15.2 \pm 0.6$  m.y. old, with a range of dates from 14.6 to 15.8 m.y. (Watkins and Baksi, 1974).

The formation is known to crop out only in the John Day basin south of the Blue Mountains uplift, except for the lower part of Butte Creek canyon (Cockerham and Bentley, 1973; Nathan and Fruchter, 1974) and a small area near Lone Rock (Robinson, 1975; Fruchter and Baldwin, 1975). Most vents for the Picture Gorge likewise occur in the John Day basin, comprising the Monument dike swarm (Waters, 1961; Wilcox and Fisher, 1966), which contains numerous feeder dikes of appropriate chemistry and magnetic polarity (pl. 1, fig. B; Fruchter and Baldwin, 1975). Two feeder dikes occur north of the basin in the small area near Lone Rock (Robinson, 1975); others are present south of the basin about 8 km north and northeast of Izee (Dickinson and Vigrass, 1965).

A few dikes having major-element chemistry similar to that of Picture Gorge Basalt occur in northeast Oregon within the Chief Joseph dike swarm (Taubeneck, 1970; W. H. Taubeneck and T. L. Wright, unpub. data, 1977), and the lowermost flow at Dug Bar, the

type locality of the Imnaha and Hooper, 1976: Kleck, 1: Basalt, and the dikes are con aha flows. The flow and di Gorge Basalt, as chemical sufficient evidence on which correlation. Moreover, stracates that the flow is con Gorge Basalt in north-cent

Calc-alkaline andesitic Strawberry Volcanics unde ture Gorge Basalt 20-30 1977: Robyn and others, 1 least two central-vent com basin and have a relative took place between 12 and as about 20 m.y., on the older ages substantially pr Volcanics is herein exclude because of its local nature than long fissures, its calcits earlier onset of eruptive bly "derived from high-sta Strawberry Volcanics cifically excluded from the 1976). This treatment of th Brown (1966b), who assign

## YAKIM#

Wright and others (197 (1961) into three units information upper Yakima basalt based and showed that these unithe Columbia Plateau an subdivision has been accedual use of the name Yak Stratigraphic Nomenclatu

は一般のでは、一般のでは、110日では、

Wright and others (197) tween basalt chemistry ar lower Yakima is characte ticular chemical type (defi Hamilton, 1978), the mi types, and the upper Yak Subsequent work has sho

rests on the basalt of Twickgins of the John Day basin, hn Day Formation.

as the basalt of Dayville for of 3 to 15 flows that are fine c. The upper 11 flows in the to this unit. The flows have latures. Thin flows of small hick flows may extend long onument-Picture Gorge area d Baksi, 1974; Nathan and is normally magnetized.

orge Basalt are used here in more fieldwork must be done y can easily be elevated to discrete stratigraphic units. Basalt varies gradationally nal field termed the Picture ters (1973); two representanical variation are given in r deoxease abruptly upward, th elements increase at the ent Mountain and Dayville others, 1973; Bentley and 1, 1974).

om the type section suggests  $15.2 \pm 0.6$  m.y. old, with a Vatkins and Baksi, 1974).

The state with the state of the

only in the John Day basin xcept for the lower part of Bentley, 1973; Nathan and Lone Rock (Robinson, 1975; ents for the Picture Gorge comprising the Monument isher, 1966), which contains emistry and magnetic polarn, 1975). Two feeder dikes a near Lone Rock (Robinson, asin about 8 km north and 3, 1965).

hemistry similar to that of t Oregon within the Chief W. H. Taubeneck and T. L. ermost flow at Dug Bar, the type locality of the Imnaha Basalt, has a similar compositon (Vallier and Hooper, 1976: Kleck, 1976). This flow is assigned to the Imnaha Basalt, and the dikes are considered as feeders for other similar Imnaha flows. The flow and dikes are not considered part of the Picture Gorge Basalt, as chemical similarity alone is not considered to be sufficient evidence on which to base such a long-range stratigraphic correlation. Moreover, stratigraphic and magnetic evidence indicates that the flow is considerably older than all known Picture Gorge Basalt in north-central Oregon.

Calc-alkaline andesitic and rhyolitic rocks belonging to the Strawberry Volcanics underlie, interfinger with, and overlie the Picture Gorge Basalt 20-30 km east-southeast of John Day (Robyn, 1977; Robyn and others, 1977). These rocks were erupted from at least two central-vent complexes along the margin of the John Day basin and have a relatively limited extent. Most eruptive activity took place between 12 and 15 m.y. ago, but some occurred as early as about 20 m.y., on the basis of K-Ar ages (Robyn, 1977); these older ages substantially pre-date the Picture Gorge. The Strawberry Volcanics is herein excluded from the Columbia River Basalt Group because of its local nature, its eruption from central vents rather than long fissures, its calc-alkaline chemistry, in part rhyolitic, and its earlier onset of eruptive activity. The Mascall Formation, probably "derived from high-standing volcanic centers represented by the \*\*\* Strawberry Volcanics" (Thayer and Brown, 1966b), is also specifically excluded from the Columbia River Basalt Group (Griggs, 1976). This treatment of the Mascall differs from that of Thayer and Brown (1966b), who assigned it to the Columbia River Group.

#### YAKIMA BASALT SUBGROUP

Wright and others (1973) divided the Yakima Basalt of Waters (1961) into three units informally designated the lower, middle, and upper Yakima basalt based on lithology and stratigraphic succession and showed that these units could be recognized across wide areas of the Columbia Plateau and in the Blue Mountains. The threefold subdivision has been accepted by most later workers, although the dual use of the name Yakima is improper according to the Code of Stratigraphic Nomenclature.

Wright and others (1973) found a very good correspondence between basalt chemistry and stratigraphic position. For example, the lower Yakima is characterized predominantly by flows of one particular chemical type (defined by a procedure outlined in Wright and Hamilton, 1978), the middle Yakima by flows of other chemical types, and the upper Yakima by flows of still other chemical types. Subsequent work has shown that the correlation between chemistry

and stratigraphic position is at least as good as initially believed (fig. 2).

Wright and others (1973) showed that their three informally named units could be further subidvided into mappable flows or sequences of flows, some of which had previously been formally named. For example, the Frenchman Springs Member, a formally named sequence of flows, occurs in their middle Yakima basalt. Thus, a hierarchy of mixed formal and informal terms is currently in use with the three basic subdivisions having only informal names but containing some formally named subdivisions.

In order to make this complicated hierarchy compatible with the Code of Stratigraphic Nomenclature, we hereby propose that the Yakima Basalt be raised to subgroup status and designated the Yakima Basalt Subgroup. We further propose dividing the subgroup into three formations, reflecting the three basic subdivisions of Wright and others (1973). The three formations are, from oldest to youngest, the Grande Ronde Basalt, the Wanapum Basalt, and the Saddle Mountains Basalt (fig. 2). These three formations are not only distinct lithologic units but also reflect a succession of petrologic changes fundamental to the development of the flood basalt province. Several formal members, some previously named and some new, can be recognized in the Wanapum and Saddle Mountains Basalt (fig. 2). The Grande Ronde Basalt cannot yet be formally subdivided, but it can be broken into four easily mappable magneto-stratigraphic units.

## GRANDE RONDE BASALT

The Grande Ronde Basalt, a name suggested by Taubeneck (1970, footnote, p. 75) is herein formalized to replace the informal designation lower Yakima basalt of Wright and others (1973). Its type locality (pl. 1, fig. C) is the prominent west-trending spur ridge extending from the NW4 sec. 23 across the N½ sec. 22 to the NE4 sec. 21, T. 7 N., R. 46 E., Black Butte quadrangle, in the lower part of the Grande Ronde River valley, Asotin County, extreme southeast Washington. Camp, Price, and Reidel (1978) describe in detail a stratigraphic section at this locality, consisting of approximately 34 flows totaling about 830 m in thickness. Camp (1976), Price (1977), and Reidel (1978) give additional chemical and magnetic information for the type section. The type Grande Ronde conformably overlies the Imnaha Basalt in exposures a short distance downriver from the type locality and disconformably underlies the Weissenfels Ridge Member of the Saddle Mountains Basalt.

The Grande Ronde Basalt is essentially equivalent to the Yakima Basalt as defined by Waters (1961), except that his "late textural

and mineralogic variant of and redefined as part of Basalts. As Waters showed widespread formation in th C). It underlies virtually al although covered by younge south of the Blue Mountai: east Washington. It is equ (1963) in the Clearwater et gon, the formation extends Mountains uplift but does John Day basin in the are: ter, 1974; unpub. data of th that of some past workers ( Brown, 1966b). The Grand Columbia River Gorge an along the lower Columbia Puget-Willamette Lowland

The thickness of the Gra on prebasalt topography a known section is about 1,1 holes DH-4 and DH-5 in 1973; Myers, 1973; Atlantithe Blue Mountains (Swansmore than 600 m thick; a. 450 m (Holden and Hoopalong the lower John Day laps out against older rock about 500 m in the Tieton the east flank of the Casc occur even near the margiflows to accumulate.

THE PROPERTY OF THE PROPERTY O

A much thicker section although another interpr. Rattlesnake Hills No. 1 we nia in 1957-58 at an elevat the Pasco Basin in the (Raymond and Tillson, 196 only the Yakima Basalt. from the 2,464-2469-m de mun., 1973), the only core from the low-Mg Yakima c consistent with assignmen contact with the Wanapur

good as initially believed

nto mappable flows or sepreviously been formally ings Member, a formally r middle Yakima basalt. rmal terms is currently in ring only informal names livisions.

. .

Ž;

こうちょちゃ 山ち春を持ち神 最高は一十年の日の

一種情報をからなるとのなる情報のよう。

achy compatible with the hereby propose that the tatus and designated the bose dividing the subgroup ree basic subdivisions of lations are, from oldest to Wanapum Basalt, and the three formations are not effect a succession of petopment of the flood basalt reviously named and some mand Saddle Mountains annot yet be formally subeasily mappable magneto-

ALT

ested by Taubeneck (1970, lace the informal designathers (1973). Its type localnding spur ridge extending 22 to the NE% sec. 21, T. in the lower part of the punty; extreme southeast 1978) describe in detail a sting of approximately 34 Camp (1976), Price (1977), cal and magnetic informate Ronde conformably overrt distance downriver from underlies the Weissenfels Basalt.

equivalent to the Yakima ept that his "late textural and mineralogic variant of the Yakima Basalt" (p. 600) is excluded and redefined as part of the Wanapum and Saddle Mountains Basalts. As Waters showed, the Grande Ronde Basalt is the most widespread formation in the Columbia River Basalt Group (pl. 1, fig. C). It underlies virtually all of the Columbia Plateau in Washington. although covered by younger rocks in much of this area, and extends south of the Blue Mountains uplift in northeast Oregon and southeast Washington. It is equivalent to most of Bond's "upper basalt" (1963) in the Clearwater embayment of Idaho. In north-central Oregon, the formation extends southward to the north flank of the Blue Mountains uplift but does not appear to cross the uplift into the John Day basin in the area west of Monument (Nathan and Fruchter, 1974; unpub. data of the authors), an interpretation contrary to that of some past workers (Waters, 1961; Lindsley, 1960; Thayer and Brown, 1966b). The Grande Ronde forms spectacular cliffs in the Columbia River Gorge and crops out west of the Cascade Range along the lower Columbia River valley and in adjacent parts of the Puget-Willamette Lowland.

The thickness of the Grande Ronde varies considerably depending on prebasalt topography and the amount of erosion. The thickest known section is about 1,000 m, with the base not found, in drill holes DH-4 and DH-5 in the Pasco Basin (Ledgerwood and others, 1973; Myers, 1973; Atlantic Richfield Hanford Co., 1976). Sections in the Blue Mountains (Swanson and others, 1977; 1979) are commonly more than 600 m thick; along the lower Salmon River, more than 450 m (Holden and Hooper, 1976); and in north-central Oregon along the lower John Day River, more than 450 m. The formation laps out against older rocks along its margins, but thick sections, to about 500 m in the Tieton River area (Swanson, 1967, 1978) along the east flank of the Cascade Range in south-central Washington, occur even near the margin wherever topographic basins permitted flows to accumulate.

A much thicker section of the Grande Ronde Basalt may exist, although another interpretation is preferred. The 3,248-m-deep Rattlesnake Hills No. 1 well, drilled by Standard Oil Co. of California in 1957-58 at an elevation of about 875 m along the west edge of the Pasco Basin in the central part of the Columbia Plateau (Raymond and Tillson, 1968), was at one time considered to contain only the Yakima Basalt. A chemical analysis of a section of core from the 2,464-2469-m depth interval (P. D. Snavely, written commun., 1973), the only core taken from the holes, is indistinguishable from the low-Mg Yakima chemical type of Wright and others (1973), consistent with assignment to the Grande Ronde Basalt. The upper contact with the Wanapum Basalt is readily identifiable at about

500-m depth on the basis of chemical analyses reported by Raymond and Tillson (1968). The Grande Ronde could therefore have a minimum thickness of 1,964 m, extending to at least 1,589 m below sea level. Evaluation of numerous spectrochemical analyses of sidewall cores and ditch samples (Raymond and Tillson, 1968), however, suggests that the base of the Grande Ronde Basalt is at about 1,280-m depth, nearly the same as the 1,265 m depth separating two district geoelectric intervals in the hole (Jackson, 1975). Most rocks at greater depths are chemically dissimilar to the Picture Gorge and Imnaha Basalts and are tentatively interpreted as Eocene to lower Miocene basalt and andesite on the basis of pollen (Newman, 1970; Raymond and Tillson, 1968). We prefer this interpretation, reached independently on chemical grounds by G. G. Goles (written commun., 1977), and thereby consider the drilled Grande Ronde Basalt to be only about 780 m thick, extending to about 405 m below sea level

Several excellent reference localities can be designated for the Grande Ronde Basalt. Smith (1901) first used the term Yakima Basalt for flows exposed in cliffs along the Yakima River south of Ellensburg in south-central Washington, and this area, well described by Diery and McKee (1969), serves as a fine reference locality in the western part of the Columbia Plateau. Other good localities in this general area, for which published information is available, include Cresent Bar (McDougall, 1976) and Divide Ridge and Windy Point in the Tieton River area (Swanson, 1967). In the southwest part of the plateau, easily accessible sections include Cow Canyon (Waters, 1961; Watkins and Baksi, 1974) and Tygh Ridge (Waters, 1961; Nathan and Fruchter, 1974; Watkins and Baksi, 1974), although both have experienced minor faulting (R. D. Bentley, unpub. data, 1976). Structurally undisturbed reference sections in northeast Oregon include the Sherars Bridge section along the Deschutes River (T. 3 S., R. 14 and 15 E) and Beef Hollow (Waters. 1961; R. D. Bentley, D. A. Swanson, and T. L. Wright, unpub. data, 1977), as well as along Butte Creek (Cockerham and Bentley, 1973; Nathan and Fruchter, 1974), in which the interlayered contact of Grande Ronde and Picture Gorge Basalts is well exposed. The Ortley anticline exposes an excellent reference section in the Columbia River Gorge east of White Salmon, Washington (Hammond and others, 1977). Good sections of the Grande Ronde occur in the southeast part of the Columbia Plateau along most roads connecting ridgetops with canyon bottoms, as, for example, those listed by Waters (1961) and Patrick Grade (sec. 24, T. 9 N., R. 40 E.), on the north flank of the Blue Mountains of southeast Washington. The Snake River Canyon from the mouth of the Grande Ronde River downstream to Devils Canyor lent cross section of the Colu thickness of more than 1,000

The Grande Ronde consist sparsely phyric fine-grained range in chemical compositio Ronde chemical type (a syno Wright and others, 1973); re positions and an unusually hi 2. Only rarely are flows high of the type locality and in the Valley, and lower Salmon Riv phyric flows occur in northdata, 1977), and one such flow Wash. (Tabor and others, 197 Basalt contain rare plagiocl clinopyroxene clots visible in Olivine is generally absent a in small amounts (less than but the least magnesian flow

Flows within the Grande F 1 m to more than 100 m. Ge breccia more common near interbeds of sedimentary det: plateau occur commonly, pa highs. Calc-alkaline andesiti clastic material between son

Few flows are distinctive a stratigraphic markers, excels such as jointing habit and we recognition over long dist documentation. The plagical the type locality are some known to us whose lithology definition. Even this usage is in a relatively small area in jacent Oregon and Idaho.

The only reliable means a stratigraphic breakdown of mapping of magnetic polarit (fig. 2) has been shown to (Swanson and Wright, 197 1977: 1979), and other work on the plateau (Hooper, Cam

nalyses reported by Raymond

nde could therefore have a

ling to at least 1.589 m below

spectrochemical analyses of

nond and Tillson, 1968), how-

nde Ronde Basalt is at about

1,265 m depth separating two

e (Jackson, 1975). Most rocks

tilar to the Picture Gorge and

iterpreted as Eocene to lower

sis of pollen (Newman, 1970;

r this interpretation, reached

y G. G. Goles (written com-

drilled Grande Ronde Basalt

ng to about 405 m below sea

s can be designated for the

first used the term Yakima the Yakima River south of

ton, and this area, well de-

rves as a fine reference local-

umbia Plateau. Other good

ich published information is

gall, 1976) and Divide Ridge

area (Swanson, 1967). In the

cessible sections include Cow

laksi, 1974) and Tygh Ridge . 1974; Watkins and Baksi,

nced minor faulting (R. D. lly undisturbed reference sec-

Sherars Bridge section along

i 15√E) and Beef Hollow (Wa-

on, and T. L. Wright, unpub.

zek-Cockerham and Bentley,

which the interlayered contact

Basaits is well exposed. The

reference section in the Co-

mon, Washington (Hammond e Grande Ronde occur in the

along most roads connecting

example, those listed by Wa-

 $\overline{\Gamma}$ . 9 N., R. 40 E.), on the north

east Washington. The Snake the Grande Ronde River ż

The state of the s

downstream to Devils Canyon (T. 13 N., R. 34 E.) provides an excellent cross section of the Columbia Plateau, exposing an aggregate thickness of more than 1,000 m of the Grande Ronde Basalt.

The Grande Ronde consists overwhelmingly of aphyric to very sparsely phyric fine-grained tholeiltic basalt having a continuous range in chemical composition within a field defined as the Grande Ronde chemical type (a synonym for the Yakima chemical type of Wright and others, 1973); representative high- and low-MgO compositions and an unusually high MgO composition are given in table 2. Only rarely are flows highly plagioclase phyric, as near the base of the type locality and in the Lewiston Basin, lower Grande Ronde Valley, and lower Salmon River Canyon. A few sparsely plagioclasephyric flows occur in north-central Oregon (R. D. Bentley, unpub. data, 1977), and one such flow was mapped southeast of Wenatchee, Wash. (Tabor and others, 1979). Most flows within the Grande Ronde Basalt contain rare plagioclase microphenocrysts and plagioclaseclinopyroxene clots visible in both hand specimen and thin section. Olivine is generally absent as phenocrysts but is commonly present in small amounts (less than 0.5 percent) in the groundmass of all but the least magnesian flows.

Flows within the Grande Ronde range in thickness from less than 1 m to more than 100 m. Generally flows are thinner and flow-top breccia more common near major vent areas. Thin, discontinuous interbeds of sedimentary detritus eroded from sources on and off the plateau occur commonly, particularly near prebasalt topographic highs. Calc-alkaline andesitic to rhyolitic tephra is mixed with epiclastic material between some flows near the Cascade Range.

Few flows are distinctive enough in the field to serve as regional stratigraphic markers, except in relatively limited areas. Criteria such as jointing habit and weathering color are unreliable for flow recognition over long distances, at least without independent documentation. The plagioclase-phyric flows found near the base of the type locality are some of the few flows in the Grande Ronde known to-us-whose lithology can be readily used for stratigraphic definition. Even this usage is limited, as these flows are found only in a relatively small area in extreme southeast Washington and adjacent Oregon and Idaho.

The only reliable means we have found for providing a regional stratigraphic breakdown of the Grande Ronde Basalt is by field mapping of magnetic polarities. The resulting magnetostratigraphy (fig. 2) has been shown to hold throughout southeast Washington (Swanson and Wright, 1976a; Camp, 1976; Swanson and others, 1977; 1979), and other workers are using it with success elsewhere on the plateau (Hooper, Camp, Kleck, Reidel, and Sundstrom, 1976).

of the selection of the selection of the file.

No stratigraphic section known to us contains all four magneto-stratigraphic units. Only the three older units occur at the type locality. The well-exposed sequence of N2 flows closest to the type locality is along Highway 12 at Alpowa Grade, between Clarkston and Pomeroy, Wash., in T. 11 N., R. 43 E. Thicker N2 sections are exposed along the Snake River Canyon downstream from the Almota Creek area (T. 14 N., R. 41–42 E.) and in the Blue Mountains south of Pomeroy. The geologic maps by Swanson and others (1977: 1979) and Tabor and others (1979) show the distribution of the informal magnetostratigraphic units in southeast and north-central Washington, respectively.

Single flows or sequences of flows in the Grande Ronde Basalt can be correlated for several tens of kilometers in southeast Washington and adjacent Idaho on the basis of similar chemical composition (Camp, 1976; Reidel, 1978; T.L. Wright and D. A. Swanson, unpub. data, 1977). In the western part of the Columbia Plateau, a sequence of flows of high-Mg Grande Ronde chemical type overlies flows of low-Mg Grande Ronde chemical type (Nathan and Fruchter, 1974; Taylor, 1976; Atlantic Richfield Hanford Co., 1976; M. H. Beeson and R. D. Bentley, unpub data, 1977). The contact between the two chemical types is consistently about three to five flows above the R<sub>7</sub>-N<sub>2</sub> contact and appears to be a good stratigraphic marker, although one low MgO flow occurs higher in the section near Wenatchee (D. A. Swanson and G. R. Byerly, unpub. data, 1978). In the eastern Columbia Plateau, several such chemical breaks defined locally may eventually prove to be of regional significance.

Feeder dikes for some flows in the Grande Ronde Basalt are found in the Chief Joseph dike swarm of northeast Oregon and adjacent Washington and Idaho (pl. 1, fig. C; Waters, 1961; Gibson, 1969: Taubeneck, 1970; Price, 1974; Camp, 1976; Swanson and others. 1977; 1979) A few dikes in the Rocky Canyon area, western Idaho, east of the eastern margin that Taubeneck (1970) placed on the

Chief Joseph swarm, have be The western margin of Taul extended westward to include the Grande Ronde in the dumatilla Rivers east and genson, 1964; Newcomb, 1: Swanson and T. L. Wright, for the Columbia River Basswestern margin of the plate pub. data), although some 1 1961; Stout, 1961). Many dil hidden by younger flows in

Potassium-argon dates pu and Watkins (1973; Watkins ically most reasonable dates that the Grande Ronde Bas old, consistent with an early Ronde Basalt.

CON

The contact of the Gran-Basalt is well exposed in the and Idaho. Everywhere stuck evidence of a major time be and Hooper, 1976). No interfound, although we conside local examples of interbeshows that the oldest known aha.

E

The Grande Ronde-Pictur only three general areas in Creek (Buckhorn Canyon & two formations intertongue and Fruchter, 1974), and m terbedded flows are in the N<sub>1</sub> (R. D. Bentley and D. Camus Creek (Bridge Cree formable, although a 3-m-t the two formations (Nathalikewise conformable south unpub. map, 1976). Elsewhelt of older rocks along th rate the Grande Ronde and

and simply in the field with a pare favorably with laboratory ons and single flows studied in Phoiniere and Swanson (1979), pt for transitional polarities, the field. Four informal magned within the Grande Ronde, where R means reversed and rities make some contacts diferally we find that the contacts wo flows.

7

The state of the s

us contains all four magnetoer units occur at the type locallows closest to the type locality rade, between Clarkston and. Thicker N2 sections are exdownstream from the Almota d in the Blue Mountains south anson and others (1977; 1979) the distribution of the informal outheast and north-central

eters in southeast Washington similar chemical composition in and D. A. Swanson, unpub. Columbia Plateau, a sequence hemical type overlies flows of Nathan and Fruchter, 1974; nord Co.. 1976; M. H. Beeson The contact between the two three, to five flows above the a good stratigraphic marker, higher in the section near Byerly, unpub. data, 1978). In I suothchemical breaks defined regional significance.

Grande Ronde Basalt are found northeast Oregon and adjacent; Waters, 1961; Gibson, 1969; p. 1976; Swanson and others, y Canyon area, western Idaho, ubeneck (1970) placed on the

Chief Joseph swarm, have been described by Price and others (1973). The western margin of Taubeneck's Chief Joseph swarm should be extended westward to include feeders for flows in and younger than the Grande Ronde in the drainage basin of the Walla Walla and Umatilla Rivers east and south of Milton-Freewater, Oreg. (Hogenson, 1964; Newcomb, 1965; Swanson and others, 1977; D. A. Swanson and T. L. Wright, unpub. mapping, 1977). No feeder dikes for the Columbia River Basalt Group have yet been found near the western margin of the plateau (Swanson, 1967, and subsequent unpub. data), although some had been previously suspected (Waters, 1961; Stout, 1961). Many dikes for the Grande Ronde Basalt may lie hidden by younger flows in the central part of the plateau.

Potassium-argon dates published by Holmgren (1970) and Baksi and Watkins (1973; Watkins and Baksi, 1974), as well as the geologically most reasonable dates in Gray and Kittleman (1967), indicate that the Grande Ronde Basalt is between about 14.0 and 16.5 m.y. old, consistent with an early and middle Miocene age for the Grande Ronde Basalt.

## CONTACT RELATIONS

The contact of the Grande Ronde with the underlying Imnaha Basalt is well exposed in the tristate area of Washington, Oregon, and Idaho. Everywhere studied, this contact is conformable, with no evidence of a major time break (Kleck, 1973; Camp, 1976; Holden and Hooper, 1976). No interbedding of the two formations has been found, although we consider it likely that future mapping will find local examples of interbedding. Magnetostratigraphic mapping shows that the oldest known Grande Ronde flows overlie the Imnaha.


The Grande Ronde-Picture Gorge contact has been recognized in only three general areas in north-central Oregon. Along lower Butte Creek (Buckhorn Canyon and Chimney Springs quadrangles), the two formations intertongue (Cockerham and Bentley, 1973; Nathan and Fruchter, 1974), and magnetostratigraphy suggests that the interbedded flows are in the upper part of magnetostratigraphic unit N<sub>1</sub> (R. D. Bentley and D. A. Swanson, unpub. data, 1977). Along Camus Creek (Bridge Creek quadrangle), the contact appears conformable, although a 3-m-thick bed of siltstone and peat separates the two formations (Nathan and Fruchter, 1974). The contact is likewise conformable south of Dale (Dale quadrangle; R. D. Bentley, unpub. map, 1976). Elsewhere throughout north-central Oregon, a belt of older rocks along the Blue Mountains uplift appears to separate the Grande Ronde and Picture Gorge Basalts. This area is in-

The observed contact relations of the Grande Ronde Basalt with the Imnaha and Picture Gorge Basalts differ from those suggested by Waters (1961), who believed that an angular unconformity separated the older and younger flows. Detailed and reconnaissance mapping in the years since publication of his classic paper has failed to demonstrate such an unconformity, and the interbedding of the Grande Ronde and Picture Gorge at Butte Creek clearly indicates that the two formations are, at least in part, coeval. The two formations have similar K-Ar ages within the error of measurement (Watkins and Baksi, 1974). On the basis of mangetostratigraphy, most or all of the Picture Gorge Basalt, the youngest flows of which are in the lower part of the R<sub>2</sub> magnetozone, is younger than the Imnaha Basalt.

The top of the Grande Ronde Basalt is generally well defined by a zone of weathering and (or) a sedimentary interbed separating the formation from the overlying Wanapum or Saddle Mountains Basalts. Absence of a saprolite or interbed makes field recognition of the top of the formation difficult if aphyric flows overlie it. However, the contact can be generally recognized by contrasting chemical compositions, particularly TiO<sub>2</sub> and FeO, of rocks above and below. This chemical change was labeled the "TiO<sub>2</sub> discontinuity" by Siems and others (1974), as rocks above the contact generally have markedly higher TiO<sub>2</sub> contents than those below. Chemical differences cannot be used to define lithostratigraphic units according to the Code of Stratigraphic Nomenclature, but we and many other workers have found them to be a reliable tool for distinguishing most of the stratigraphic units within the Columbia River Basalt Group.

Normally magnetized flows (unit  $N_2$ ) of Grande Ronde, Dodge, and Frenchman Springs chemical types (table 2) are interbedded at one known locality, Benjamin Gulch, 3 km south of Pomeroy in southeast Washington (fig. 3). This is interpreted as indicating local interfingering of the Grande Ronde and Wanapum Basalts. A saprolite is missing, despite its presence as a thick unit between the Grande Ronde and Wanapum Basalts in nearby areas. These relations are

COLUMBIA



1. 沙州中国中国城市

FIGURE 3.—Schematic stratigraphic section in Benjamin Gulch, showing chemical types of 13 basalt flows exposed in roadcuts along State Highway 128 in secs. 8, 9, and 16, T. 11 N., R. 42 E., Pomeroy quadrangle (Washington). Uncorrected for north dip of about 4°. Note interbedded nature of chemical types. In Pomeroy, 3 km to north, flow 72-55(?) overlies a continuous sequence of the Grande Ronde Basalt.

ther localities where the forma-

the Grande Ronde Basalt with alts differ from those suggested an angular unconformity sepasion. Detailed and reconnaissance on of his classic paper has failed ty, and the interbedding of the t Butte Creek clearly indicates in part, coeval. The two formation the error of measurement basis of mangetostratigraphy, alt, the youngest flows of which metozone, is younger than the

一年一學問題的問題的


it is generally well defined by a entary interbed separating the mapum or Saddle Mountains erbed makes field recognition of hyric flows overlie it. However, nized by contrasting chemical FeO; of rocks above and below. e "TiQ2 discontinuity" by Siems e contact generally have markse below. Chemical differences graphic units according to the but we and many other worktool for distinguishing most of olumbia River Basalt Group. 2) of Grande Ronde, Dodge, and table 2) are interbedded at one m south of Pomeroy in south-

a Benjamin Gulch, showing chemical along State Highway 128 in secs. 8, 9, jie (Washington). Uncorrected for north chemical types. In Pomeroy, 3 km to quence of the Grande Ronde Basalt.

rpreted as indicating local in-

Wamepum Basalts. A saprofite thick unit between the Grande

rby areas. These relations are



significant, as they indicate that magmas of greatly different compositions were available along local areas of the vent systems during a time in which weathering and sediment deposition prevailed across much of the rest of the Columbia Plateau.

### FLOWS OF PRINEVILLE CHEMICAL TYPE

Thirteen flows of a distinct chemical composition (table 2, col 8). termed Prineville chemical type by Uppuluri (1974), form a 240-mthick section near Prineville Dam, Crook County, north-central Oregon (fig. 1). They rest unconformably on the John Day Formation and are unconformably overlain by Pliocene basalt flows (Uppuluri, 1974; Waters, 1961, pl. 2A). These flows were considered part of the Columbia River Group by Swanson (1969), but they cannot be traced laterally into areas of known Yakima Basalt Subgroup or Picture Gorge Basalt. Nathan and Fruchter (1974) found flows of Prineville chemical type interlayered with flows of Grande Ronde chemical type along Butte Creek and at Tygh Ridge, and M. H. Beeson (oral commun., 1976) has found similar relations in the western Cascade Range. These observations suggest that at least some flows near Prineville Dam may be coeval with the middle part of the Grande Ronde Basalt. However, Uppuluri (1974) reported that 12 of 13 flows at the dam have reverse magnetic polarity, whereas the flows of Prineville type at Butte Creek and Tygh Ridge have normal polarity. We feel that too little is known about the stratigraphic relations to warrant assignment of the flows in the Prineville Dam section to any formal subdivision of the Columbia River Basalt Group. With further fieldwork, it may become advisable to elevate these flows to member or formational status in the Yakima Basalt Subgroup. At this time, we favor continuing to include in the Grande Ronde Basalt the Prineville-type flows that are interbedded with undoubted Grande Ronde Basalt along Butte Creek, at Tygh Ridge, and in the Western Cascades. The flows near Prineville Dam are not assigned herein to any formally named unit within the Columbia River Basalt Group.

# REDEFINITION OF THE VANTAGE SANDSTONE MEMBER

The sedimentary interbed commonly present between the Grande Ronde and Wanapum Basalt in the western part of the Columbia Plateau was formally named the Vantage Sandstone Member of the Yakima Basalt by Bingham and Grolier (1966). This definition presents no problem at the type locality, but farther west, the Vantage merges laterally with and cannot be separated from sedimentary deposits of the Ellensburg Formation. In such places, the deposit must be mapped as belonging to the Ellensburg. Schmincke (1964) recognized this problem and suggested that the Vantage be made a

part of the Ellensburg; he Basalt in order to conform t tion but believed the observtion (H.-U. Schmincke, oral

一十月重 为于通过为为特色的特殊一种

We agree that the eviden earlier suggestion and reass member of the Ellensburg I not change laterally depend deposited between basalt fl Vantage Member, because claystone, or tuffaceous roc

All major sedimentary ir edges of the Columbia Plat lumbia River Basalt Grot (1976). Those major interbe Washington are assigned to the northwestern part of the beds elsewhere are left una satisfactory and we wish to at this time.

The name Wanapum was mond, oral commun., 1976) and 1960's for basalt abov Saddle Mountains Basalt in tral Washington. These roci by Wright and others (1976)

We hereby adopt Maci Wanapum Basalt to forma cludes all of the flows prebasalt except for the Umapart of the Saddle Mount Wanapum is designated as along the east side of the Cc Sand Hollow in sec. 28, T. section near the Vantage S 16, T. 16 N., R. 23 E., Va County, Washington. Most along Highway 243 south o 120-m-thick section consists Member overlain by one fic Members.

The Wanapum Basalt co grained olivine-bearing co as of greatly different comof the vent systems during ment deposition prevailed Plateau.

MICAL TYPE

omposition (table 2, col 8). iluri (1974), form a 240-mook County, north-central on the John Day Formation ene basalt flows (Uppuluri, were considered part of the ), but they cannot be traced asalt Subgroup or Picture found flows of Prineville of Grande Ronde chemical ge, and M. H. Beeson (oral ns in the western Cascade at least some flows near middle part of the Grande eported that 12 of 13 flows rity,rwhereas the flows of Ridge have normal polarthe Stratigraphic relations Prineville Dam section to River Basalt Group. With ble to elevate these flows Yakima Basalt Subgroup. ludeon the Grande Ronde iterbedded with undoubted at Tygh Ridge, and in the :lle Dam are not assigned n the Columbia River Ba-

# NDSTONE MEMBER

esent between the Grande ern part of the Columbia Sandstone Member of the 1966). This definition prefarther west, the Vantage parated from sedimentary such places, the deposit nsburg. Schmincke (1964)

ten | tenthenitenten | menten femiliente

part of the Ellensburg; he later (1967a) assigned it to the Yakima Basalt in order to conform to the then generally accepted classification but believed the observed evidence supported his earlier suggestion (H.-U. Schmincke, oral commun., 1965, 1976).

We agree that the evidence strongly supports Schmincke's (1964) earlier suggestion and reassign the Vantage Sandstone Member as a member of the Ellensburg Formation, for the name of a unit should not change laterally depending simply on whether it was or was not deposited between basalt flows. We also shorten the name to the Vantage Member, because it commonly contains only siltstone, claystone, or tuffaceous rocks.

All major sedimentary interbeds between basalt flows along the edges of the Columbia Plateau are likewise excluded from the Columbia River Basalt Group, following the procedure of Griggs (1976). Those major interbeds in the western part of the plateau in Washington are assigned to the Ellensburg Formation, and those in the northwestern part of the plateau, to the Latah Formation. Interbeds elsewhere are left unassigned, as existing nomenclature is unsatisfactory and we wish to propose no new names for these deposits at this time.

#### WANAPUM BASALT

The name Wanapum was used by J. Hoover Mackin (P. E. Hammond, oral commun., 1976) in classroom lectures during the 1950's and 1960's for basalt above the Vantage Member and below the Saddle Mountains Basalt in the Vantage-Priest Rapids area of central Washington. These rocks were called the middle Yakima basalt by Wright and others (1973).

We hereby adopt Mackin's usage and formally assign the Wanapum Basalt to formational status. The Wanapum Basalt includes all of the flows previously included in the middle Yakima basalt except for the Umatilla Member, now defined as the basal part of the Saddle Mountains Basalt. The type locality of the Wanapum is designated as the area of nearly continuous exposure along the east side of the Columbia River near Wanapum. Dam, from Sand Hollow in sec. 28, T. 17 N., R. 23 E., south to the top of the section near the Vantage Substation above Wanapum Dam in sec. 16, T. 16 N., R. 23 E., Vantage and Beverly quadrangles, Grant County, Washington. Most of the section is also exposed in roadcuts along Highway 243 south of the intersection with Highway 26. This 120-m-thick section consists of three flows of the Frenchman Springs Member overlain by one flow of each of the Roza and Priest Rapids Members.

The Wanapum Basalt contains a sequence of generally mediumgrained olivine-bearing commonly slightly to moderately plagioclase-phyric flows, most of which have high Fe and Ti contents (table 2). Many of the flows recognized as a "late textural and mineralogical variant of the Yakima Basalt" by Waters (1961) are in the Wanapum. The generally high Fe and Ti nature of the formation is known to be broken only by flows in the Eckler Mountain Member in southeast Washington (table 2, Nos. 12-14).

The Wanapum Basalt is divided into four members on the basis of petrography and magnetic polarity, from oldest to youngest, the Eckler Mountain Member, Frenchman Springs Member, Roza Member, and Priest Rapids Member. All terms except Eckler Mountain Member, a new name, are used in the same sense as originally defined (Mackin, 1961; Bingham and Grolier, 1966). The Eckler Mountain Member contains flows of three different petrographic and chemical types, all of which have normal magnetic polarity. The dominant type of flow in the Eckler Mountain is coarse-grained, commonly grusy weathering, and plagioclase phyric; another type of flow, the oldest in the member, is diktytaxitic, aphyric, and olivine rich; a third, the youngest type of flow, is fine grained and aphyric. The Frenchman Springs Member contains several flows, some with moderately abundant large plagioclase glomerocrysts, and has normal magnetic polarity. The Roza Member is moderately plagioclase phyric, with single crystals greatly predominating over glomerocrysts, and has either a transitional or reversed magnetic polarity. The Priest Rapids Member commonly carries small plagioclase and olivine phenocrysts, although most local flows near the type locality are aphyric and coarse grained, and has a reversed magnetic polarity. The youngest Priest Rapids flow is notably more magnesian than most other high Fe and Ti flows in the Wanapum. Contacts between the four members are conformable, although sedimentary interbeds separate them in places.

On a local scale, the Wanapum Basalt overlies the Grande Ronde conformably or with local erosional disconformities, except for the interbedded relation in Benjamin Gulch south of Pomeroy, Wash. On a regional scale, however, the Wanapum disconformably overlies progressively older parts of the Grande Ronde Basalt eastward from the center of the plateau (Swanson and Wright, 1976b; Swanson and others, 1977; 1979). This relation is interpreted as indicating subsidence of the central plateau prior to Wanapum time. The regional unconformity between the two formations is caused by confinement of younger Grande Ronde flows to the deeper part of the subsidence basin, not by their erosion from the eastern limb of the plateau (Swanson and Wright, unpub. data, 1977). Such subsidence continued through Wanapum time and into late Saddle Mountains time.

A prominent saprolite mant Basalt in southeast Washingt progressively thickening east Local basins in which arkosic a ited occur above the saprolite Pullman areas. The saprolite is Grande Ronde-Wanapum conta

The Vantage Member of the Grande Ronde and Wanapum a Columbia Plateau. Where it is marks the contact. Where bot missing or very thin, such as i Freewater, Oreg., the Grande I to map except where the low phyritic.

The contact between the <sup>1</sup> Mountains Basalt is generally unconformities occur along Ya 1967, Bentley, 1977) and on (Bentley, 1977), and erosional areas in south-central Washin age basin. A saprolite or thin to the Ellensburg Formation c Saddle Mountains contact in Plateau.

Dikes and vent areas for W places in southeast Washington (fig. 1; Swanson and other 1979). Probably other vents are central part of the Columbia known to occur there and now

ECKLER M

In and adjacent to the Blue petrographically and chemical the basalt of Dodge (Swanson basalt of Robinette Mountain Grande Ronde Basalt and Frinctive flows overlie a well-care themselves somewhat wea lite. They most likely were e produced the extensive soil elsewhere in southeast Wasi Gulch south of Pomeroy, whe

igh Fe and Ti contents (table ate textural and mineralogi-Waters (1961) are in the l'i nature of the formation is the Eckler Mountain Member 12-14).

four members on the basis of om oldest to youngest, the in Springs Member, Roza I terms except Eckler Mounthe same sense as originally Grolier, 1966). The Eckler ee different petrographic and mal magnetic polarity. The Mountain is coarse-grained, clase phyric; another type of taxitic, aphyric, and olivine is fine grained and aphyric. ins several flows, some with glomerocrysts, and has norer is moderately plagioclase redominating over glomeroreversed magnetic polarity. arries small plagioclase and I flows near the type locality s a reversed magnetic polaris notably more magnesian in the Wanapum. Contacts able, although sedimentary

t overlies the Grande Ronde conformities, except for the h south of Pomeroy, Wash. pum disconformably overlies Ronde Basalt eastward from Wright, 1976b; Swanson and terpreted as indicating sub-Vanapum time. The regional has is caused by confinement eeper part of the subsidence castern limb of the plateau 977). Such subsidence connto late Saddle Mountains

A prominent saprolite mantles the surface of the Grande Ronde Basalt in southeast Washington and adjacent Oregon and Idaho, progressively thickening eastward from the Devils Canyon area. Local basins in which arkosic and subarkosic sediments were deposited occur above the saprolite in places, such as the Spokane and Pullman areas. The saprolite is an excellent guide to recognizing the Grande Ronde-Wanapum contact.

The Vantage Member of the Ellensburg Formation separates the Grande Ronde and Wanapum across much of the western part of the Columbia Plateau. Where it is missing, a thin saprolite commonly marks the contact. Where both the Vantage and the saprolite are missing or very thin, such as in the Blue Mountains east of Milton-Freewater, Oreg., the Grande Ronde-Wanapum contact may be hard to map except where the lowermost flow in the Wanapum is porphyritic.

The contact between the-Wanapum and the overlying Saddle Mountains Basalt is generally conformable, although local angular unconformities occur along Yakima Ridge near Yakima (Holmgren, 1967, Bentley, 1977) and on Umtanum Ridge near Priest Rapids (Bentley, 1977), and erosional unconformities are known from a few areas in south-central Washington and in the Spokane River drainage basin. A saprolite or thin deposit of tuffaceous rocks belonging to the Ellensburg Formation commonly occurs along the Wanapum-Saddle Mountains contact in the western part of the Columbia Plateau.

Dikes and vent areas for Wanapum flows are known from many places in southeast Washington, western Idaho, and northeast Oregon (fig. 1; Swanson and others, 1975; Swanson and others, 1977; 1979). Probably other vents are hidden beneath younger flows in the central part of the Columbia Plateau, as some Wanapum flows are known to occur there and nowhere else.

# ECKLER MOUNTAIN MEMBER

In and adjacent to the Blue Mountains in southeast Washington, petrographically and chemically distinctive flows, informally named the basalt of Dodge (Swanson and others, 1975) and the underlying basalt of Robinette Mountain, occur between typical flows of the Grande Ronde Basalt and Frenchman Springs Member. These distinctive flows overlie a well-developed saprolite in most places but are themselves somewhat weathered and locally overlain by a saprolite. They most likely were erupted during the period of time that produced the extensive soil on top of the Grande Ronde Basalt elsewhere in southeast Washington. Field relations at Benjamin Gulch south of Pomeroy, where three flows of Dodge type are inter-

...

bedded with Grande Ronde and Frenchman Springs flows (fig. 3), support this timing.

The name Eckler Mountain Member is here introduced for the flows between the underlying Grande Ronde Basalt and the overlying Frenchman Springs Member. The Eckler Mountain is designated a member of the Wanapum rather than the Grande Ronde Basalt, because the underlying saprolite, which represents a significant period of time following Grande Ronde volcanism, is more common and generally thicker than the overlying saprolite. The Eckler Mountain bears more resemblance chemically to the Grande Ronde than to the Wanapum, however. It may be desirable at some later time to raise the Eckler Mountain to formational status, but that is not done here because of its comparatively restricted occurrence.

The type locality is on the south and southeast side of Eckler Mountain (misspelled Echler Mountain on the Pullman 1° by 2° quadrangle), about 17 km southeast of Dayton, Columbia County. Wash, in the north halves of secs. 26 and 27, T. 9 N., R. 40 E., Eckler Mountain quadrangle (pl. 1, fig. D). This is the only known area in which flows of both the Dodge and Robinette Mountain chemical types (table 2, col. 12–13) occur in the same section. Two sites in the type locality where a Dodge-type flow overlies a Robinette Mountain flow are (1) roadcut and cliff below road in the NW4NW4NE4 sec. 26, T. 9 N., R. 40 E. and (2) roadcut and cliff below road along the border of the SW4NE4 and SE4NW4 sec. 27, T. 9 N., R. 40 E. The total thickness of the member in this area is 20 to 25 m.

All known flows in the Eckler Mountain Member have normal magnetic polarity (Choiniere and Swanson, 1979; Swanson and Wright, unpub. data, 1977).

The basalt of Robinette Mountain is named for a single flow in roadcuts on Robinette Mountain near a powerline crossing in the NE4NW4 sec. 22, T. 9 N., R. 39 E., Robinette Mountain quadrangle, Columbia County, Wash. Other excellent accessible exposures in this general area are (1) the Dayton city dump in Crall Hollow, SW4SW4 sec. 34, T. 10 N., R. 39 E., Dayton quadrangle, and (2) the prominent cliff along the upper part of Rodgers Gulch near Pioneer Memorial Park, NE4SW4 sec. 4, T. 9 N., R. 40 E., Cahill Mountain quadrangle. Nowhere have two or more Robinette Mountain flows been found in contact, and it is possible that only one such flow was erupted. The maximum exposed thickness of the basalt of Robinette Mountain is about 20 m.

The basalt of Robinette Mountain is coarse grained, has a distinctive coarsely diktytaxitic texture, and contains abundant olivine (commonly rimmed or replaced by iridescent iddingsite) but only

very rare, small plagiocla former throughout much minimum of 180 km² (pl. 1, a distinctive chemical comp est K²O and TiO² contents (Subgroup (table 2, No. 12). for the basalt of Robinette through the center of secs. 5 quadrangle (pl. 1, fig. D: Sv

The basalt of Dodge is n. along Highway 127, in the S quadrangle, 1.5 km by road and 12 at Dodge, Garfield grussy flow containing weat This type of weathering, typ vations below about 1,200 n ence localities: (1) switchbac 1 km north-northeast of Mar rangle, Wash.; (2) roadcut al 10 N., R. 42 E., Rose Springs of Shumaker Creek, extreme 45 E., Black Butte quadrang ary of the SE4NE4 sec. 31 a Saddle Butte quadrangle, W at 1,000 m (3,280 ft) elevatic Flora quadrangle, Oreg.

At higher elevations, the aspect and is more resistant cut near the base of the knoll northeast corner of sec. 2, Trangle, Wash.: (2) cliffs west SW4 sec. 7, T. 9 N., R. 42 and (3) roadcut at about 1,35 sec. 18, T. 7 N., R. 39 E., De.

The basalt of Dodge is characteristic abundant large pheno as much as 2 cm across. Smoriginally constituted more the been altered to clay minerals with some plagioclase-phyric is size and average glomerocrys Frenchman Springs flows. The similar to that of some very Basalt (table 2, Nos. 11 and

man Springs flows (fig. 3),

is here introduced for the onde Basalt and the overly-Eckler Mountain is desiger than the Grande Ronde e, which represents a sige Ronde volcanism, is more to overlying saprolite. The echemically to the Grande it may be desirable at some to formational status, but paratively restricted occur-

d southeast side of Eckler on the Pullman 1° by 2° Dayton, Columbia County, 27, T. 9 N., R. 40 E., Eckler is the only known area in binette Mountain chemical me section. Two sites in the erlies a Robinette Mountain in the NW4NW4NE4 sec. i clff below road along the sec. 27, T. 9 N., R. 40 E. is area is 20 to 25 m.

raiq Member have normal inson, 1979; Swanson and

named for a single flow in powerline crossing in the Robinette Mountain quadexcellent accessible expodayton city dump in Crall 39 E., Dayton quadrangle, oper part of Rodgers Gulch sec. 4, T. 9 N., R. 40 E., have two or more Robinette and it is possible that only mexposed thickness of the 0 m.

parse grained, has a distinccontains abundant olivine escent iddingsite) but only very rare, small plagioclase phenocrysts. It is a prominent cliff former throughout much of its outcrop area, inferred to be a minimum of 180 km² (pl. 1, fig. D; Swanson and others, 1977). It has a distinctive chemical composition, with the highest Al<sub>2</sub>O<sub>3</sub> and lowest K<sub>2</sub>O and TiO<sub>2</sub> contents of any known flow in the Yakima Basalt Subgroup (table 2, No. 12). A north-northwest-trending feeder dike for the basalt of Robinette Mountain extends for at least 3 km through the center of secs. 5 and 8, T. 7 N., R. 40 E., Godman Spring quadrangle (pl. 1, fig. D: Swanson and others, 1977; 1979).

The basalt of Dodge is named from a flow exposed in a roadcut along Highway 127, in the SW4NE4 sec. 16, T. 12 N., R. 40 E., Hay quadrangle, 1.5 km by road from the intersection of Highways 127 and 12 at Dodge, Garfield County, Wash. The roadcut displays a grussy flow containing weathering spheroids whose cores are fresh. This type of weathering, typical of Dodge flows at relatively low elevations below about 1,200 m, is well shown at the following reference localities: (1) switchback in road at 597 m (1,960 ft) elevation 1 km north-northeast of Marengo, Columbia County, Zumwalt quadrangle, Wash.; (2) roadcut along Highway 128 in SE4SE4 sed. 4, T 10 N., R. 42 E., Rose Springs quadrangle, Wash.; (3) roadcut at head of Shumaker Creek, extreme southeast corner of sec. 11, T. 7 N., R. 45 E., Black Butte quadrangle, Wash.; (4) roadcut along the boundary of the SE4NE4 sec. 31 and SW4NW4 sec. 32, T. 7 N., R. 43 E., Saddle Butte quadrangle, Wash.; and (5) roadcut along Highway 3 at 1,000 m (3,280 ft) elevation, NE4NE4 sec. 26, T. 6 N., R. 44 E., Flora quadrangle, Oreg.

At higher elevations, the basalt of Dodge tends to lose its grusy aspect and is more resistant to weathering. Examples are: (1) roadcut near the base of the knoll at Wenatchee Guard Station, extreme northeast corner of sec. 2, T. 7 N., R. 43 E., Saddle Butte quadrangle, Wash.; (2) cliffs west of Abels triangulation station. NE¼ SW¼ sec. 7, T. 9 N., R. 42 E., Rose Springs quadrangle, Wash.; and (3) roadcut at about 1,355 m (4,450 ft) elevation in NE¼SW¼ sec. 18, T. 7 N., R. 39 E., Deadman Peak quadrangle, Wash.

The basalt of Dodge is characterized by coarse grain size and moderately abundant large phenocrysts and glomerocrysts of plagioclase as much as 2 cm across. Smectitic alteration is common. Olivine originally constituted more than 5 percent of the rock, but most has been altered to clay minerals. The basalt of Dodge can be confused with some plagioclase-phyric Frenchman Springs flows, but its grain size and average glomerocryst size are both greater than in most Frenchman Springs flows. The chemical composition of the Dodge is similar to that of some very high MgO flows in the Grande Ronde Basalt (table 2, Nos. 11 and 13), but the coarse grain size and

49860 PS 200 PS

The basalt of Dodge generally consists of one flow in a single exposure but locally comprises as many as four flows. Its maximum thickness is about 40 m. The Dodge is the most widespread unit in the Eckler Mountain Member. It occurs principally in two major areas of outcrop (pl. 1, fig. D): the Blue Mountains east and south of Walla Walla, Wash., and a belt extending more than 80 km northwest from Buford Creek, Oreg., to the Snake River near the mouth of New York Gulch, Wash. (Swanson and others, 1977, 1979; Swanson and others, 1975; Price, 1977; and Ross, 1978). Flows of Dodge type also occur in the Shumaker Canyon area in extreme southeast Washington and in a small area near Walker grain elevator along the lower Snake River (Swanson and others, 1977, 1979; Price, 1977). Griggs (1976) reported one or more chemically similar flows along the lower St. Joe and St. Maries Rivers south of Coeur d'Alene Lake, Idaho; we feel that these flows may correlate with the basalt of Dodge, although they lack the large plagioclase phenocrysts typical of Dodge-type flows elsewhere. The Dodge is locally interbedded with the Frenchman Springs Member in Benjamin Gulch south of Pomeroy, Wash., and in the Blue Mountains southeast of Walla Walla (D. A. Swanson and T. L. Wright, unpub. data, 1978).

Dikes of Dodge chemical type, presumably feeders of the basalt of Dodge, occur at several locations in the Blue Mountains in Washington (pl. 1, fig D; Swanson and others, 1977, 1979; Ross. 1978), and a similar dike crops out along Little Sheep Creek east of Enterprise, Oreg. (Swanson and others, 1975; Kleck, 1976, table 29, no. I 148).

In extreme southeast Washington, the basalt of Dodge is locally overlain by one or two aphyric flows that are also low in Fe and Ti but considerably higher in alkalis and lower in Mg than the Dodge. These flows are informally named the basalt of Shumaker Creek for a flow prominently exposed in roadcuts above the basalt of Dodge at the head of Shumaker Creek, in the extreme southeast corner of sec. 11, T. 7 N., R. 45 E., Black Butte quadrangle, Asotin County, Wash. Another good locality is at Wenatchee Guard Station, Wash. (fig. 1), where the capping flow is the basalt of Shumaker Creek. These flows are overlain by the Roza Member between Wenatchee Guard Station and Anatone Butte but are nowhere known to occur in a section with flows of the Frenchman Springs Member. Consequently, we know little about the precise age relation of the basalt of Shumaker Creek to the Frenchman Springs Member, although we tentatively consider the Shumaker Creek to be older and assign it to the Eckler Mountain Member. The distribution of the basalt of Shumaker Creek is poorly known and not shown on plate 1.

The basalt of Shumaker of pearance to many flows of composition, however, is disthan the low-MgO Grande.

Camp (1976) described a Cloverland Grade, Wash. (f reversed part of the Grande what obscure in the Clover of Dodge is absent. We sugg that the George Creek flow Creek and should be assign

FRENCHA

The Frenchman Springs was named and described by type locality in Frenchma Coulee on the Evergreen 1 29-30, T. 18 N., R. 23 E., G (pl. 1, fig. E). Mackin consid units, the Ginkgo and overly the 75-m-thick member at i Sentinel Gap flow, overlies farther south. Work in progr ification of this scheme. A th at its type locality and h Diatomite Bed (Bingham as this paper). Elsewhere in so Springs consists of as many is the most extensive member referred to Mackin (1961), B (1977) for more information in south-central Washington

3

A good reference locality roadcuts and natural exposi in the Kahlotus and Lower (fig. 1). At least nine flows exposed here. The member weathered flow of the Granyon near the north end of Wright, 1976b; Siems and Member, exposed in roadcuthe head of Devils Canyon and Wright, 1976b).

Other easily accessible re

llows ready identification.
Its of one flow in a single expoas four flows. Its maximum
s the most widespread unit in
curs principally in two major
e Mountains east and south of
iding more than 80 km northSnake River near the mouth
and others, 1977, 1979; Swand Ross, 1978). Flows of Dodge
yon area in extreme southeast
r Walker grain elevator along
nd others, 1977, 1979; Price,
more chemically similar flows

Rivers south of Coeur d'Alene

may correlate with the basalt

e plagioclase phenocrysts typi-

re Dodge is locally interbedded

r in Benjamin Gulch south of

√lountains southeast of Walla

tht, unpub. data, 1978). umably feeders of the basalt of in the Blue Mountains in and others, 1977, 1979; Ross, ong Little Sheep Creek east of 5, 1975; Kleck, 1976, table 29,

the basalt of Dodge is locally that are also low in Fe and Ti d lower in Mg than the Dodge. basalt of Shumaker Creek for ts above the basalt of Dodge at xtreme southeast corner of sec. drangle, Asotin County, Wash. e Guard Station, Wash. (fig. 1), i Shumaker Creek. These flows ween-Wenatchee Guard Station e known to occur in a section gs Member. Consequently, we tion of the basalt of Shumaker mber, although we tentatively lder and assign it to the Eckler п of the basalt of Shumaker m on plate 1.

The basalt of Shumaker Creek is fine grained and similar in appearance to many flows of the Grande Ronde Basalt. Its chemical composition, however, is distinctly lower in MgO and higher in P2Os than the low-MgO Grande Ronde chemical type (table 2, No. 14).

Camp (1976) described a similar flow, the George Creek flow, at Cloverland Grade, Wash. (fig. 1) and assigned it to a magnetically reversed part of the Grande Ronde Basalt. Field relations are somewhat obscure in the Cloverland Grade area, however, as the basalt of Dodge is absent. We suggest, on the basis of chemical similarity, that the George Creek flow correlates with the basalt of Shumaker Creek and should be assigned to the Eckler Mountain Member.

#### FRENCHMAN SPRINGS MEMBER

The Frenchman Springs Member (Bingham and Grolier, 1966) was named and described by Mackin (1961) for flows exposed at its type locality in Frenchman Springs Coulee (named Frenchman Coulee on the Evergreen Ridge quadrangle), in secs. 19-21 and 29-30, T. 18 N., R. 23 E., Grant County, south-central Washington (pl. 1, fig. E). Mackin considered that two informally named cooling units, the Ginkgo and overlying multiple-flow Sand Hollow, compose the 75-m-thick member at its type locality; a third cooling unit, the Sentinel Gap flow, overlies the Sand Hollow several kilometers farther south. Work in progress by R. D. Bentley may result in modification of this scheme. A thin bed of diatomite overlies the member at its type locality and has been designated the Squaw Creek Diatomite Bed (Bingham and Grolier, 1966; see later discussion in this paper). Elsewhere in south-central Washington, the Frenchman Springs consists of as many as nine flows, generally three to six, and is the most extensive member of the Wanapum Basalt. The reader is referred to Mackin (1961), Bingham and Grolier (1966), and Bentley (1977) for more information about the Frenchman Springs Member in south-central Washington.

A good reference locality for the Frenchman Springs Member is in roadcuts and natural exposures in Devils Canyon, south of Kahlotus in the Kahlotus and Lower Monumental Dam quadrangles, Wash. (fig. 1). At least nine flows totaling about 190 m in thickness are exposed here. The member overlies the reddened top of a slightly weathered flow of the Grande Ronde Basalt at the mouth of the canyon near the north end of Lower Monumental Dam (Swanson and Wright, 1976b; Siems and others, 1974) and underlies the Roza Member, exposed in roadcuts along the Pasco-Kahlotus highway at the head of Devils Canyon (Bingham and Walters, 1965; Swanson and Wright, 1976b).

Other easily accessible reference localities where the Frenchman

Springs is well exposed are on both sides of Wallula Gap, Wash. (Atlantic Richfield Hanford Company, 1976, v. 2, p. B 24–B 26); on the Maryhill grade along Highway 97 north of Biggs, Oreg. (Hammond and others, 1977); along the Deschutes River just north of Maupin, Oreg. (R. D. Bentley, unpub. map, 1977); roadcuts and railroad cuts in Palouse Falls State Park, Wash. (Swanson and Wright, 1976b); and at Rattlesnake Springs in Moses Coulee, Wash. (Siems and others, 1974).

The Frenchman Springs Member rests on the Grande Ronde Basalt, except in parts of southeast Washington and northeast Oregon, where it overlies and is locally interbedded with the Eckler Mountain Member. A saprolite or, less commonly, arkosic to subarkosic siltstone and sandstone, occurs on the pre-Frenchman Springs surface in many places. Thin discontinuous subarkosic and tuffaceous interbeds occur between some flows of the Frenchman Springs Member in the central and western part of the Columbia Plateau. Examples can be seen at Palouse Falls (Swanson and Wright, 1976b, p. 17; Siems and others, 1974, p. 1063), in the Yakima area (Bentley, 1977), and near Maupin, Oreg. (R. D. Bentley, unpub. map, 1977).

Most flows in the member contain scattered glomerophyric clots of plagioclase a centimeter or more in diameter, generally unequally distributed through a flow. Large phenocrysts of olivine are very sparse in most flows but are notable in a few flows, such as the one atop Pikes Peak, Oreg. (sec. 22, T. 6 N., R. 37 E., Peterson Ridge quadrangle). In our experience, post-Eckler Mountain flows in the Yakima Basalt Subgroup containing numerous large plagioclase glomerocrysts almost certainly belong to the Frenchman Springs Member. However, flows containing very sparse glomerocrysts (perhaps one per 20 m<sup>2</sup> or fewer) are not necessarily in the member, as such flows have been found in definite Grande Ronde Basalt. On the other hand, not all Frenchman Springs flows contain glomerocrysts. Such aphyric flows, particularly common in the eastern part of the Columbia Plateau, cannot be distinguished in the field from the Grande Ronde Basalt. Their assignment to the Frenchman Springs is clearcut if they are interbedded with glomerophyric flows, but rather tenuous otherwise. Mapping in adjacent areas or chemical analysis of the suspect flows generally results in firm assignment.

All known flows within the Frenchman Springs, whether glomerophyric or not, are characterized by a chemical composition defined by Wright and others (1973) as Frenchman Springs chemical type; the average composition of one flow of this chemical type is given in table 2 (No. 15). Nearly all flows of this chemical type are in the Frenchman Springs Member.

All flows in the member that have been tested have normal

magnetic polarity (Rietman, 1). The Frenchman Springs Me areas of the Columbia Plateau Oregon, and Beeson and other man Springs petrographic at position occur in the Bull Run of western Oregon (pl. 1, fig. tinuity" (Siems and others, 1). Grande Ronde Basalt and the member generally thins away its eastern limit, mapped by S about long 117° 25′ W. in south

Dikes having appropriate chepolarity for the member occur Walla Walla and along the SWalker, Wash. (pl. 1, fig. E; Swothers, 1977: 1979). These dik flows: a good example of a dikalong the Snake River downst and others, 1975, fig. 1). Most cobut some east of Milton-Freew

RO7

The Roza Member (Binghan Mackin (1961) for exposures of locality, "a scarp on the east six Station" (a railroad siding in and Yakima), at about 460 m (1 T. 15 N., R. 19 E., Wymer quad 1, fig. F). For years a more acc the south, just above and sou Highway 97 in the W½ sec. 9 rangle, has served as a princ Diery and McKee (1969) esta tween the two localities. At bo overlying diatomite and under lensburg Formation.

Elsewhere, more than one flo chman Springs and Priest Rapi Bingham and Grolier (1966), wh Member. We follow this procec petrographic and chemical cha common vent system (Swanson

The Roza occurs across much

sides of Wallula Gap, Wash. 1976, v. 2, p. B 24-B 26); on i north of Biggs, Oreg. (Hambeschutes River just north of map. 1977); roadcuts and rail-Wash. (Swanson and Wright, Moses Coulee, Wash. (Siems

rests on the Grande Ronde ashington and northeast Oreinterbedded with the Eckler s commonly, arkosic to subaron the pre-Frenchman Springs tinuous subarkosic and tuffaows of the Frenchman Springs part of the Columbia Plateau. (Swanson and Wright, 1976b, in the Yakima area (Bentley, Bentley, unpub. map, 1977). cattered glomerophyric clots of diameter, generally unequally enoctysts of olivine are very in a few flows, such as the one N. R. 37 E., Peterson Ridge Eckler Mountain flows in the numerous large plagioclase ig tothe Frenchman Springs g very sparse glomerocrysts not necessarily in the member, nite Grande Ronde Basalt. On Forings flows contain glomeroy common in the eastern part of inguished in the field from the ent-to the Frenchman Springs with glomerophyric flows, but in adjacent areas or chemical ly results in firm assignment. renchman Springs, whether zed by a chemical composition s Frenchman Springs chemical e flow of this chemical type is flows of this chemical type are

Pier and the Lakery's First or grant by

ave been tested have normal

magnetic polarity (Rietman, 1966: Kienle and others, 1978).

The Frenchman Springs Member has been recognized over wide areas of the Columbia Plateau in eastern Washington and northeast Oregon, and Beeson and others (1976) found that flows of Frenchman Springs petrographic and chemical type and stratigraphic position occur in the Bull Run area and the lower Willamette Valley of western Oregon (pl. 1, fig. E). In most places, the "TiO2 discontinuity" (Siems and others, 1974) marks the contact between the Grande Ronde Basalt and the Frenchman Springs Member. The member generally thins away from the central Columbia Plateau; its eastern limit, mapped by Swanson and others (1977; 1979), is at about long 117° 25′ W. in southeast Washington.

Dikes having appropriate chemistry, lithology, and paleomagnetic polarity for the member occur in the Blue Mountains southeast of Walla Walla and along the Snake River slightly upstream from Walker, Wash. (pl. 1, fig. E; Swanson and others, 1975; Swanson and others, 1977; 1979). These dikes served as feeders for some of the flows; a good example of a dike merging with the flow it fed occurs along the Snake River downstream from Devils Canyon (Swanson and others, 1975, fig. 1). Most of the feeder dikes are nearly vertical, but some east of Milton-Freewater. Oreg., have dips as low as 20°.

## ROZA MEMBER

The Roza Member (Bingham and Grolier, 1966) was named by Mackin (1961) for exposures of a plagioclase-phyric flow at the type locality, "a scarp on the east side of the Yakima River opposite Roza Station" (a railroad siding in Yakima Canyon between Ellensburg and Yakima), at about 460 m (1.500 ft) elevation in the SE¼ sec. 16, T. 15 N., R. 19 E., Wymer quadrangle, south-central Washington (pl. 1, fig. F). For years a more accessible outcrop and roadcut 8 km to the south, just above and south of an abandoned tunnel on old Highway 97 in the W½ sec. 9, T. 14 N., R. 19 E., Pomona quadrangle, has served as a principal reference locality. Mapping by Diery and McKee (1969) established stratigraphic continuity between the two localities. At both, the Roza occurs as a single flow overlying diatomite and underlying volcaniclastic rocks of the Ellensburg Formation.

Elsewhere, more than one flow may be present between the Frenchman Springs and Priest Rapids Members. This was recognized by Bingham and Grolier (1966), who assigned all such flows to the Roza Member. We follow this procedure, as all these flows have similar petrographic and chemical characteristics and appear to share a common vent system (Swanson and others, 1975).

The Roza occurs across much of the Columbia Plateau (pl. 1, fig. F)

and was erupted from a narrow linear vent system more than 150 km long in southeast Washington and northeast Oregon. Each of its flows is characterized by numerous (about 5–8 percent) plagioclase phenocrysts, mostly single crystals averaging more than 5 mm in length, that are evenly distributed throughout the flow. The nature and distribution of the phenocrysts distinguish the Roza from the Frenchman Springs Member. The Roza generally consists of no more than two flows whose total thickness is about 50 m at any site. Most of the Roza has a transitional magnetic polarity (Rietman, 1966), but at least one cooling unit along the vent system in extreme southeast Washington has reversed polarity (Choiniere and Swanson, 1979); this reversed unit is considered to be the youngest flow in the Roza Member. A more complete description of the member is given by Swanson and others (1975), Lefebvre (1970), and Bingham and Grolier (1966).

Good reference localities showing characteristics of the member on a regional scale are along several roadcuts: (1) the head of Frenchman Springs Coulee (Mackin, 1961, pls. 5B and 6); (2) head of Devils Canyon (Bingham and Walters, 1965, Swanson and Wright, 1976b); (3) head of Horton Grade (sec. 11, T. 14 N., R. 40 E., near Penawawa); (4) north part of Colfax, along Highway 195; (5) Highway 12 at Alpowa Summit, 15 km southeast of Pomeroy; (6) Anatone Butte along the vent system (Swanson and others, 1975, table 1. No. 17); and (7) the lower Grand Coulee area, in which Lefebvre (1970) conducted a detailed investigation of the Roza. The member occurs in scattered outcrops along its vent system in northeast Oregon; it does not occur in Idaho.

Regional stratigraphic relations mapped by Swanson and others (1977) indicate that the Roza overlies progressively older flows eastward from the central Columbia Plateau. The underlying Frenchman Springs Member thins and pinches out eastward, and the Roza near its eastern margin overlies magnetically reversed Grande Ronde Basalt belonging to the informal R2 magnetostratigraphic unit. The member has not been found east of about long 177° 10′ W. The westernmost known exposure is in the Mosier syncline west of Mosier, Oreg., in the Columbia River Gorge, according to R. D. Bentley (unpub. data, 1977).

The Roza Member is slightly richer in MgO but otherwise chemically similar to most flows of Frenchman Springs chemical type (table 2, No. 16).

SQUAW CREEK DIATOMITE BED AND QUINCY DIATOMITE BED

Bingham and Grolier (1966) used the formal names Squaw Creek Diatomite Bed and Quincy Diatomite Bed to designate units beneath and above, respectivel was assigned to the Frenchn Priest Rapids Member. Thes west-central Columbia Plate occurs at these stratigraphic

There has been confusion at the type area for the Qui: part of the Quincy Basin, \ peperite intermixed with diyounger than the diatomite. the Frenchman Hills and the 17, T. 18 N, R. 23 E., Evergre nature of tongues, "dikes" a Roza invading this diatomite by M. J. Grolier (Mackin, 19 Bingham and Grolier (1966). mite to be younger than the I do not believe that the diate flow and invaded by a young pendent indication of two flo only one Roza flow is presen Creek Diatomite Bed. In the lies the peperite disconforma sedimentary deposit below t Nowhere do we know of clea or interbedded with Roza an

The name Quincy Diatomi apparently equivalent to the cause its presumed stratigraph the Priest Rapids is incorrect becomes chiefly a sandstone and merges with the Ellens sequently, the Squaw Creek and reassigned to the Ellens

PRIEST

The Priest Rapids Member all basalt flows above the R Member of the Saddle Mount member for four basalt flows the "area upstream from Washington (pl. 1, fig. G). The type locality is now mostly codam, but the member is poorl

ir vent system more than 150 northeast Oregon. Each of its about 5-8 percent) plagioclase veraging more than 5 mm in roughout the flow. The nature listinguish the Roza from the a generally consists of no more is about 50 m at any site. Most etic polarity (Rietman, 1966), the vent system in extreme polarity (Choiniere and Swandered to be the youngest flow in description of the member is Lefebvre (1970), and Bingham

haracteristics of the member on adcuts: (1) the head of French, pls. 5B and 6); (2) head of rs, 1965, Swanson and Wright, c. 11, T. 14 N., R. 40 E., near, along Highway 195; (5) Highsoutheast of Pomeroy; (6) Anawanson and others, 1975, table Coulee area, in which Lefebvre ation of the Roza. The member its-vent system in northeast

apped by Swanson and others s progressively older flows eastateau. The underlying French-inches out eastward, and the s magnetically reversed Grande ormali R2 magnetostratigraphic deast of about long 177° 10′ W. s in the Mosier syncline west of iver Gorge, according to R. D.

er in MgO but otherwise chemiiman Springs chemical type (ta-

ND QUINCY DIATOMITE BED

the formal names Squaw Creek tite Bed to designate units beneath and above, respectively, the Roza Member. The Squaw Creek was assigned to the Frenchman Springs Member, the Quincy to the Priest Rapids Member. These beds are only locally developed in the west-central Columbia Plateau; little if any sedimentary material occurs at these stratigraphic intervals over most of the plateau.

There has been confusion as to the number of diatomites present at the type area for the Quincy Diatomite Bed in the southwestern part of the Quincy Basin, Wash. The Roza Member here forms a peperite intermixed with diatomite and hence is, at least in part, younger than the diatomite. Excellent exposures in many quarries in the Frenchman Hills and the Quincy basin, for example those in sec. 17, T. 18 N, R. 23 E., Evergreen Ridge quadrangle, reveal the chilled nature of tongues, "dikes" and "sills," and irregular masses of the Roza invading this diatomite. These relations, apparently recognized by M. J. Grolier (Mackin, 1961, p. 26, footnote), were overlooked by Bingham and Grolier (1966), who, incorrectly considering the diatomite to be younger than the Roza, assigned it to the type Quincy. We do not believe that the diatomite was deposited on top of one Roza flow and invaded by a younger Roza flow, as we have found no independent indication of two flows. Instead, the evidence suggests that only one Roza flow is present and that this flow invades the Squaw Creek Diatomite Bed. In these quarries, a thin reworked tuff overlies the peperite disconformably and probably is the only post-Roza sedimentary deposit below the Priest Rapids Member in this area. Nowhere do we know of clear evidence of a diatomite younger than or interbedded with Roza and older than Priest Rapids.

The name Quincy Diatomite Bed is here abandoned because it is apparently equivalent to the Squaw Creek Diatomite Bed and because its presumed stratigraphic position above the Roza and within the Priest Rapids is incorrect. The Squaw Creek thickens westward, becomes chiefly a sandstone, tuffaceous sandstone, and siltstone, and merges with the Ellensburg Formation (Bentley, 1977). Consequently, the Squaw Creek is renamed the Squaw Creek Member and reassigned to the Ellensburg Formation.

# PRIEST RAPIDS MEMBER

The Priest Rapids Member (Bingham and Grolier, 1966) includes all basalt flows above the Roza Member and below the Umatilla Member of the Saddle Mountains Basalt. Mackin (1961) named the member for four basalt flows exposed along the Columbia River in the "area upstream from the Priest Rapids Dam," in central Washington (pl. 1, fig. G). The member here is about 65 m thick. The type locality is now mostly covered by water impounded behind the dam, but the member is poorly exposed in a south-dipping homocline

west of the dam. Nowhere in the vicinity, however, are all four flows well exposed. Cores from two holes, PRE-1 and PRK-3, below either end of the dam provide samples of the four flows; these cores, thoroughly studied by personnel of Atlantic Richfield Hanford Co. (1976, v. 2, p. A 35-A 41) and stored at Rockwell Hanford Operations, Richland, Wash., constitute the principal reference material for the member.

The Priest Rapids overlies the Roza Member and underlies the Beverly Member of the Ellensburg Formation at the type locality (Bentley, 1977); the Umatilla Member is not present. The relation of the Priest Rapids to the Umatilla can be seen in core from drill holes DDH-1 and DDH-3 in the Pasco Basin (fig. 1; Atlantic Richfield Hanford Co., 1976) and in outcrops along the east end of Yakima Ridge, such as along Highway 11 in SE¼SE¼ sec. 12, T. 12 N., R. 23 E., Emerson Nipple and Cairn Hope Peak quadrangles, Washington (Schmincke, 1967a). Farther south, the Priest Rapids and overlying Umatilla are separated by an interbed belonging to the Ellensburg Formation (the Mabton bed of Laval, 1956), well exposed in many parts of the Horse Heaven Hills south of Mabton (Schmincke, 1967a).

The Priest Rapids Member extends for long distances away from the type locality (pl. 1, fig. G). Only one flow is commonly present. although two or more flows occur in northeastern Washington. northern Idaho, and in the Clearwater embayment of western Idaho. At least one of the flows thought to be the single Lolo Creek flow by Bond (1963) belongs to the Priest Rapids Member. The member has not been found south of the Blue Mountains uplift and is not known to occur in northern Oregon except along the Columbia River valley. Reconnaissance mapping shows that it extends into the Spokane area of the northeast Columbia Plateau, far up the St. Joe and St. Maries Rivers in northern Idaho, and into the northern Grand Coulee area in the northern part of the plateau. One or two flows extend west in northern Oregon as far as Mosier (R. D. Bentley, unpub. data, 1977).

Several reference localities are given because of the wide extent of the member. Localities in the eastern part of the plateau include (1) the roadcut along the Pasco-Kahlotus highway at the head of Devils Canyon, Wash., described by Bingham and Walters (1965); (2) the Whitlow quarry along the Pullman-Moscow highway in the SE¼SW¼ sec. 4. T. 14 N., R. 45 E., Pullman, Wash. quadrangle; the Priest Rapids in this general area was described in a study by Brown (1976); (3) a foreset-bedded lava delta in a roadcut 1.5 km southwest of Malden, Wash. (the basal flow in the Priest Rapids Member is pillowed over a wide area southwest of Malden) (Griggs.

1976, fig. 3); (4) a columnar of Idaho, along the highway to 37 N., R. 1 W., Ahsahka qualong Highway 95A above as southeast of St. Maries, Idah St. Maries, St. Joe, and En D. A. Swanson and T. L. Weludes the "rim rock" flows Spokane area.

Reference localities in the southeast side of Sentinel (where two flows in the memblie a thick conglomerate of t of Union Gap, Wash., along Interstate Highway 80 just cuts along Highway 14 abomond and others, 1977).

The upper flow of the Pri reference locality at Senting Basin (Myers, 1973; Atlant across all of the southeaster high magnesium composition ical type by Wright and othe distinctive, as they invariable hand lens is generally nees mall plagioclase phenocryst and olivine. Older flows in the plateau have a high TiC chemically resembling the Finisher P2Os (table 2, No. 1 Rosalia chemical type.

All flows in the Priest R $\epsilon$  polarity and by this can be aphyric flows in the Frenchi vening Roza is missing or po

Several dikes of Lolo chemity and one dike of Rosalia challer south of Orofino, Idah Wright, and D. A. Swanson, much of the Priest Rapids A.

SADDLE

Bingham and Grolier (196 Member "to all the basalt flo ity, however, are all four flows CE-1 and PRK-3, below either the four flows; these cores, tlantic Richfield Hanford Co. at Rockwell Hanford Opera principal reference material

a Member and underlies the ormation at the type locality is not present. The relation of pe seen in core from drill holes is in (fig. 1; Atlantic Richfield flong the east end of Yakima E4SE4 sec. 12, T. 12 N., R. 23 eak quadrangles, Washington the Priest Rapids and overlying d belonging to the Ellensburg 1956), well exposed in many outh of Mabton (Schmincke,

for long distances away from one flow is commonly present, in northeastern Washington, embayment of western Idaho. the single Lolo Creek flow by olds Member. The member has ntains-uplift and is not knowning the Columbia River valley, it extends into the Spokane au, far up the St. Joe and St. and into the northern Grand the plateau. One or two flows as Mosier (R. D. Bentley, un-

n because of the wide extent of part of the plateau include (1); highway at the head of Devgham and Walters (1965); (2) man-Moscow highway in the illman, Wash. quadrangle; the was described in a study by wa delta in a roadcut 1.5 km sal flow in the Priest Rapids southwest of Malden) (Griggs,

1976, fig. 3); (4) a columnar outcrop about 3 km south of Cavendish, Idaho, along the highway to Ahsahka, in the NE¼SW¼ sec. 22, T. 37 N., R. 1 W., Ahsahka quadrangle (Bond, 1963); and (5) roadcuts along Highway 95A above an elevation of 741 m (2,430 ft) 8–13 km southeast of St. Maries, Idaho, in secs. 6–8 and 18, T. 45 N., R. 1 W., St. Maries, St. Joe, and Emida quadrangles (Griggs, 1976, p. 25; D. A. Swanson and T. L. Wright, unpub. data). The member includes the "rim rock" flows of Pardee and Bryan (1926) in the Spokane area.

Reference localities in the western part of the plateau are (1) the southeast side of Sentinel Gap, 15 km north of the type locality, where two flows in the member overlie the Roza Member and underlie a thick conglomerate of the Ellensburg Formation; (2) south end of Union Gap, Wash., along Thorpe Road (fig. 1); (3) roadcuts along Interstate Highway 80 just west of Arlington, Oreg.; and (4) roadcuts along Highway 14 about 7 km east of Bingen, Wash. (Hammond and others, 1977).

The upper flow of the Priest Rapids at the type locality, at the reference locality at Sentinel Gap, in drill cores from the Pasco Basin (Myers, 1973; Atlantic Richfield Hanford Co., 1976), and across all of the southeastern part of the plateau has a relatively high magnesium composition (table 2, No. 18) termed the Lolo chemical type by Wright and others (1973). Flows of this chemistry are distinctive, as they invariably contain small olivine phenocrysts (a hand lens is generally needed for identification) and commonly small plagioclase phenocrysts or glomerophyric clots of plagioclase and olivine. Older flows in the northern and northeastern parts of the plateau have a high TiO<sub>2</sub>-low MgO composition (Griggs, 1976), chemically resembling the Elephant Mountain Member except for higher P<sub>2</sub>O<sub>5</sub> (table 2, No. 17); this composition is designated the Rosalia chemical type.

All flows in the Priest Rapids Member have reversed magnetic polarity and by this can be distinguished from sparsely phyric or aphyric flows in the Frenchman Springs in areas where the intervening Roza is missing or poorly exposed.

Several dikes of Lolo chemical type and reversed magnetic polarity and one dike of Rosalia chemical type occur along the Clearwater River south of Orofino, Idaho (pl. 1, fig. G; W. H. Taubeneck, T. L. Wright, and D. A. Swanson, unpub. data, 1977) and apparently fed much of the Priest Rapids Member on the Columbia Plateau.

#### SADDLE MOUNTAINS BASALT

Bingham and Grolier (1966) applied the name Saddle Mountains Member "to all the basalt flows overlying the Priest Rapids Member 1

1.0

Control of the Market Special State of the Control of the Control

in the Sentinel Gap area \*\*\* [and] \*\*\* in the Yakima Valley," in the west-central part of the Columbia Plateau, Wash. In these two areas, the Pomona is the oldest unit in the Saddle Mountains. Elsewhere, however, flows older than the Pomona but younger than the Priest Rapids have been found. We hereby include all flows younger than the Priest Rapids Member in the Saddle Mountains, which we raise to formational rank as the Saddle Mountains Basalt and subdivide into 10 members and several informal units of differing chemical composition, source regions, and geographic distribution. The Saddle Mountains Basalt as so defined is equivalent to the upper Yakima basalt of Wright and others (1973), except that it includes the Umatilla Member previously considered as a part of the middle Yakima. This change is made on the basis of geochemistry (McDougail, 1976), the presence of the Mabton bed of Laval (1956) below the Umatilla over a relatively wide area, and the discovery that the Umatilla locally fills valleys cut in older rocks, a characteristic shared by the flows in the Saddle Mountains and described later in the paper.

Bingham and Grolier (1966) designated the area "southeast of Sentinel Gap," in the Beverly quadrangle, as the type locality of the Saddle Mountains Basalt. Only one member, the Elephant Mountain, is present at this locality, although the Pomona Member occurs nearby. The formation is nowhere represented by all its members, but more complete reference localities, all in Washington, can be designated as:

- (1) Exposures of the Esquatzel, Pomona, and Elephant Mountain Members in roadcuts along Highway 17 in and just north of the village of Mesa, 40 km north of Pasco in Esquatzel Coulee (Swanson and others, 1977; 1979);
- (2) Upper part of the bluffs on west side of Wallula Gap. Here the Umatilla Member directly overlies the Frenchman Springs Member, and the Pomona, Elephant Mountain, and Ice Harbor Members occur in scattered outcrops (see map of Swanson and others, 1977, 1979, and Atlantic Richfield Hanford Co., 1976).
- (3) Exposures of the Pomona and Elephant Mountain Members in roadcuts along the Mabton-Bickleton road, in SE4SE4 sec. 27, T. 8 N., R. 22 E., and of the Umatilla Member in the W½ sec. 35, T. 8 N., R. 22 E. (Schmincke, 1967a, b);
- (4) In Devils Canyon (SE¼ sec. 21, T. 13 N., R. 34 E.), natural exposures on the canyon wall show a cross section of four paleovalleys eroded into the Wanapum Basalt and filled successively by an unnamed and unassigned Saddle Mountains flow and the Esquatzel, Pomona, and Elephant Mountain Members. About 5 km to the

south, a roadcut across the Sna Canyon (in SE¼ sec. 3, T. 12 N. Lower Monumental Member (Sw Swanson and others, 1977; 1975)

- (5) Exposures of the Umatilla Ridge, and Elephant Mountain i km west of Asotin, secs. 25 and Swanson and others, 1977; 1979
- (6) Exposures of the Pomona and feeder dikes of the Ice Hark km northeast of Ice Harbor Dan of Martindale chemical type in thillslope above the Elephant M Swanson and others, 1977; 1976

Several flows within the Sac signed formal member status be of information. Among these ar Ross (1978), the oldest known i Snake River 'Swanson and oth localities in northeast Oregon (\) commun., 1978). Future work n to formal member rank.

The Saddle Mountains Basalt petrography, age. and paleoma tween about  $13.5 \pm 0.5$  m.y. and Atlantic Richfield Hanford Co., tion, canyon cutting, waning vobut local sedimentary deposits b Basalt constitutes much less the Columbia River Basalt Grochemical diversity, including mabundances, of any formation in

Four of the newly defined I Basalt occur principally in the I Washington: the Wilbur Cree Buford Members (pl. 1, figs. I-I are also found as intracanyon fibia Plateau (Swanson and other by ancestral valleys heading on bers, the Esquatzel and Lower canyon flows along the ancest therefore cover only a very smikilometers along the canyon. Th

n the Yakima Valley," in the ateau, Wash. In these two in the Saddle Mountains. ie Pomona but younger than Ve hereby include all flows er in the Saddle Mountains. he Saddle Mountains Basalt eral informal units of differns, and geographic distribuo defined is equivalent to the iers (1973), except that it inv considered as a part of the on the basis of geochemistry Mabton bed of Laval (1956) vide area, and the discovery cut in older rocks, a characlle Mountains and described

ated the area "southeast of le, as the type locality of the ember, the Elephant Mounthe Pomona Member occurs esented by all its members, all Th Washington, can be

ona, and Elephant Mountain in and just north of the vil-Esquatzel Coulee (Swanson

de of Wallula Gap. Here the renchiman Springs Member, and Ice Harbor Members Swanson and others, 1977, o.. 1976).

phant Mountain Members in ad, in SE44SE4 sec. 27, T. 8 r in the W½ sec. 35, T. 8 N.,

oss section of four paleovalind filled successively by an ains flow and the Esquatzel, obers. About 5 km to the south, a roadcut across the Snake River from the mouth of Devils Canyon (in SE¼ sec. 3, T. 12 N., R. 34 E.) is the type locality of the Lower Monumental Member (Swanson and Wright, 1976b, p. 13-16; Swanson and others, 1977; 1979);

(5) Exposures of the Umatilla, Wilbur Creek, Asotin, Weissenfels Ridge, and Elephant Mountain Members in the Cloverland Grade, 6 km west of Asotin, secs. 25 and 26, T. 10 N., R. 45 E. (Camp, 1976; Swanson and others, 1977; 1979);

(6) Exposures of the Pomona and Elephant Mountain Members and feeder dikes of the Ice Harbor Member in railroad cuts about 2 km northeast of Ice Harbor Dam, in sec. 18, T. 9 N., R. 32 E. A flow of Martindale chemical type in the Ice Harbor Member occurs on the hillslope above the Elephant Mountain (Swanson and others, 1975; Swanson and others, 1977; 1979).

Several flows within the Saddle Mountains Basalt are not assigned formal member status because of limited areal extent or lack of information. Among these are the Bear Creek and Eden flows of Ross (1978), the oldest known intracanyon flow along the ancestral Snake River (Swanson and others, 1977), and andesite at several localities in northeast Oregon (Walker, 1973; W. H. Taubeneck, oral commun., 1978). Future work may result in elevation of such flows to formal member rank.

The Saddle Mountains Basalt contains flows of diverse chemistry, petrography, age, and paleomagnetic polarity. It was erupted between about  $13.5 \pm 0.5$  m.y. and 6 m.y. ago (McKee and others, 1977; Atlantic Richfield Hanford Co., 1976), during a period of deformation, canyon cutting, waning volcanism, and development of thick but local sedimentary deposits between flows. The Saddle Mountains Basalt constitutes much less than 1 percent of the total volume of the Columbia River Basalt Group, yet contains by far the greatest chemical diversity, including major and trace element and isotopic abundances, of any formation in the group.

Four of the newly defined members of the Saddle Mountains Basalt occur principally in the Lewiston Basin of extreme southeast Washington: the Wilbur Creek. Asotin. Weissenfels Ridge, and Buford Members (pl. 1, figs. I-K. O). The Wilbur Creek and Asotin are also found as intracanyon flows toward the center of the Columbia Plateau (Swanson and others, 1977; 1979), channeled westward by ancestral valleys heading on the Uniontown Plateau. Two members, the Esquatzel and Lower Monumental, occur chiefly as intracanyon flows along the ancestral Snake (pl. 1, figs. L, Q). They therefore cover only a very small total area but extend for tens of kilometers along the canyon. The other four members, the Umatilla,

<u>, 4</u>

ः संविद्यक्षात्राच्यात्राच्याक्षेत्रकेत्रकेत्रकेत्रक्षात्राच्याक्ष्यक्षात्रक्षात्रक्षात्रक्षात्रक्षात्रक्षात्र

Pomona, Elephant Mountain, and Ice Harbor, cover relatively wide areas and also occur, at least locally, as canyon fills (pl. 1, figs. H, M, N, P).

Direct evidence (dikes and vent areas) and interpretation based on distribution and field relations suggest that 9 of the 10 members were erupted wholly or in part from fissures near the eastern margin of the Columbia Plateau in southeast Washington and adjacent Idaho and Oregon. This evidence is given in the descriptions of the individual members. The exception, the Ice Harbor Member, was erupted from the central part of the plateau (Swanson and others, 1975; 1977; 1979; Helz, 1978).

# UMATILLA MEMBER

Laval (1956) described two similar flows, which he named the Umatilla and Sillusi, in exposures near McNary Dam, in Washington across the Columbia River from Umatilla, Oreg. Schmincke (1964; 1967a: oral commun.. 1964) interpreted these to be flow units of the Umatilla, and he mistakenly thought that Laval had done likewise. Schmincke further incorrectly thought that Laval had applied the name Sillusi to a distinctly different flow that Schmincke termed the Pomona. These mistakes have led to confusion as to Schmincke's (1967a) usage of the term Umatilla Basalt.

We hereby define the Umatilla as a member, the Umatilla Member, to include the two flows or flow units described by Laval (1956) and designate its type locality as natural exposures and cuts along an abandoned railroad 1 km west of the north abutment of McNary Dam, in the extreme SE4SE4SE4 sec. 4, T. 5 N., R. 28 E., Umatilla quadrangle, Benton County, Wash. (pl. 1, fig H). This corresponds to the suggestion of Atlantic Richfield Hanford Co. (1976). The base of the member is not exposed here, although core holes at the damsite show that it is about 100 m thick and overlies sedimentary deposits (the Mabton bed of Laval, 1956). The Umatilla underlies the Pomona Member on Sillusi Butte overlooking the type locality.

Schmincke (1967a) found the Umatilla to occur throughout much of extreme south-central Washington (pl. 1, fig H) and further work shows it extending as far west as about 14 km west of Bickleton (Steven Strait, oral commun., 1978). The unit has been recognized in drill cores from the Pasco and Walla Walla Basins (Myers, 1973; Ledgerwood and others, 1973: Bush and others, 1973: Atlantic Richfield Hanford Co., 1976), and it occurs on the plateau surface

south of Milton-Freewater, O unpub. data). It occurs as an to a point 2 km east of Selah (along the Resthaven Road (D chemical analyses, 1978). Flc try, and stratigraphic positio Plateau, in and south of the 1977), and in the Troy, Oreg., the Umatilla (pl. 1, fig. H).

Reference localities are (1) the top of the bluff on the wes Richfield Hanford Co., 1976) a east Washington, which include Umatilla vent area (Price, 191979).

-

The Umatilla is very fine g Columbia River flows, and in appearance. Small plagioclas Both flows or flow units at an zones of flow breccia, ramp joi sult, the flows bear some phys

The Umatilla has a distinct terized by lower CaO and high other flows in the Columbia R is very high, about 3,000 ppr 1973; Price, 1974, 1977; Atlan member can be identified by I Member has a normal magneti

Puffer Butte (fig. 1) is a ver dike<sup>3</sup> exposed south of the butte Fields Springs quadrangle, al Ronde Valley near Shumaker (pl. 1, fig. H; Waters, 1961, pl. 2 tilla sources have been found. I in the central plateau flowed t ward from the Puffer Butte are unpub. map. 1978).

This dike, in which Peacock and Fuller (1928) des Plateau A C Waters, and common (1971), is cut h

Harbor, cover relatively wide s canyon fills (pl. 1, figs. H, M,

s) and interpretation based on st that 9 of the 10 members issures near the eastern mareast Washington and adjacent ven in the descriptions of the the Ice Harbor Member, was plateau (Swanson and others,

## MBER

flows, which he named the s near McNary Dam, in liver from Umatilla, Oreg. m, 1964) interpreted these to tistakenly thought that Laval ier incorrectly thought that a distinctly different flow that mistakes have led to confuof the term Umatilla Basalt. s a member, the Umatilla low Thits described by Laval s natural exposures and cuts est of the north abutment of SE4-sec. 4, T. 5 N., R. 28 E., , Wash. (pl. 1, fig H). Thisantie Richfield Hanford Co. exposed here, although core out 100 m thick and overlies of Laval, 1956). The Umatilla si Butte overlooking the type

la to occur throughout much ol. Infig H) and further work out 14 km west of Bickleton e unit has been recognized in Walla Basins (Myers, 1973; and others, 1973; Atlantic ccurs on the plateau surface south of Milton-Freewater, Oreg. (D. A. Swanson and T. L. Wright, unpub. data). It occurs as an intracanyon flow along Yakima Ridge to a point 2 km east of Selah Gap (fig. 1), where it is pillowed in cuts along the Resthaven Road (D. A. Swanson and G. R. Byerly, unpub. chemical analyses, 1978). Flows of similar characteristics, chemistry, and stratigraphic position on and just west of the Uniontown Plateau, in and south of the Lewiston Basin (Camp, 1976; Price, 1977), and in the Troy, Oreg., area (Ross, 1978) are also assigned to the Umatilla (pl. 1, fig. H).

Reference localities are (1) the thickest and best exposed flow near the top of the bluff on the west side of Wallula Gap, Wash. (Atlantic Richfield Hanford Co., 1976) and (2) Puffer Butte, in extreme southeast Washington, which includes both flows and tephra related to a Umatilla vent area (Price, 1974, 1977; Swanson and others, 1977, 1979).

The Umatilla is very fine grained, consistently finer than other Columbia River flows, and in places has an almost "porcellanite" appearance. Small plagioclase and olivine phenocrysts are rare. Both flows or flow units at and near the type locality have upper zones of flow breccia, ramp joints, and some flow banding; as a result, the flows bear some physical resemblance to andesite flows.

The Umatilla has a distinct chemistry (table 2, No. 19) characterized by lower CaO and higher K<sub>2</sub>O and total alkalies than most other flows in the Columbia River Basalt Group. The content of Ba is very high, about 3,000 ppm or more (Ledgerwood and others, 1973; Price, 1974, 1977; Atlantic Richfield Hanford Co., 1976); the member can be identified by Ba content alone. Also, the Umatilla Member has a normal magnetic polarity (Rietman, 1966).

Puffer Butte (fig. 1) is a vent area for the Umatilla Member; a dike<sup>3</sup> exposed south of the butte in the NW¼ sec. 3, T. 6 N., R. 45 E., Fields Springs quadrangle, along the north wall of the Grande Ronde Valley near Shumaker Canyon supplied magma to the vent (pl. 1, fig. H; Waters, 1961, pl. 2B; Price, 1974, 1977). No other Umatilla sources have been found. It is probable that the type Umatilla in the central plateau flowed there along a valley draining westward from the Puffer Butte area (D. A. Swanson and T. L. Wright, unpub. map, 1978).

Million of the Control of the Contro

This dike, in which Peacock and Fuller (1928) described the first occurrence of chlorophaeite on the Columbia Plateau (A. C. Waters, oral commun., 1971), is out by a tunnel on the old Anatone-Enterprise stage road.

#### WILBUR CREEK MEMBER

The Wilbur Creek Member is here named for basalt flows between the Umatilla and Asotin Members on the Uniontown Plateau and in the Lewiston Basin of southeast Washington. The member is poorly exposed, and its type locality is designated as a series of roadcuts along Wilbur Creek (sec. 9 and the SW4SW4 sec. 4, T. 14 N., R. 44 E., Ewartsville quadrangle), about 7 km west of Pullman, Whitman County, Wash. (pl. 1, fig I). Here the member consists of at least two flows that overlie the Priest Rapids Member along an erosional unconformity exposed in a roadcut on the northeast side of Wilbur Creek at 725 m (2,380 ft) elevation. The top of the member is not exposed at the type locality, but scattered outcrops show that the Wilbur Creek is at least 45 m thick. Elsewhere on the Uniontown Plateau, and in the Lewiston Basin, the Wilbur Creek can be seen to overlie the Umatilla Member and underlie, locally with erosional unconformity, the Asotin Member. A good reference locality where this relation is evident is in roadcuts in the Cloverland Grade section between 506 m (1.660 ft) and 540 m (1.770 ft) elevation in the NW4SW4 sec. 25 and NE4SE4 sec. 26, T. 10 N., R. 45 E., Asotin quadrangle (Camp, 1976), in the Lewiston Basin. The member is generally less than 20 m thick and has normal magnetic polarity. based on field determinations only.

The Wilbur Creek Member is sparsely plagioclase-phyric (phenocrysts less than 5 mm across) and fine grained. In the field, it is distinguished from the underlying Umatilla Member by its somewhat coarser grain size and from the overlying Asotin Member by its near lack of olivine phenocrysts. The Wilbur Creek is compositionally similar to but contains more P2Os than the Grande Ronde chemical type (table 2, No. 20). By its petrography, chemistry, and magnetic polarity, the Wilbur Creek Member is tentatively correlated with remnants of a canyon-filling flow 5 km west of Cow Creek (T. 16 N., R. 36 and 37 E.), on Rattlesnake Flat and in the Warden-Othello area (the Warden-Othello flow tongue of Grolier, 1965, p. 106–107; Swanson and others, 1977; 1979) in the central part of the Columbia Plateau; this intracanyon flow has been recognized on the eastern parts of Umtanum and Yakima Ridges west of the Pasco Basin by F. E. Goff (1977; oral commun., 1978).

The Wilbur Creek Member correlates with the Wahluke flow of Atlantic Richfield Hanford Co. (1976), as judged by stratigraphic position, chemistry, and magnetic polarity.

A source for the Wilbur Creek has not been found but is assumed to be near the Lewiston Basin-Uniontown Plateau area, as the flows moved from there down a canyon draining westward.

A single thick hackly jo Wilbur Creek and Weisse Basin of Washington and (Camp, 1976). The member Wash., and the type localit land Grade in the NE¼SE SW¼ sec. 25, T. 10 N., R southwest of Asotin, Asotir (pl. 1. fig. J). The base of t the top at about 585 m (1,5 deposits lie above and beloand elsewhere in the Lewis ible, leading to the develop that characterizes the men

**建筑建筑建设设置的**自然,这个各种产品的小型产品

The flow occurs as an inv flow that has an invasive s tary rocks, at the type loca ton Basin. The top of the siltstone, predominantly st was nonindurated and qui aerodynamically shaped e (Camp, 1976). Other good e Asotin are at about 884 m (SW4NE4 sec. 24, T. 8 N rangle) and at about 75 (NW4NW4 sec. 24, T. 9 quadrangle).

The Asotin Member is spontains more olivine than and less olivine than many Member. The Asotin has that of the basalt of Robine (table 2, Nos. 12 and 21) minor and trace elements. diktytaxitic texture and by tains more MgO and Al2O2 with which it might other netic polarity.

The Asotin Member occi fills a valley eroded into a and possibly Priest Rapid. 1979). A chemically simil: MEMBER

ramed for basalt flows between the Uniontown Plateau and in ungton. The member is poorly enated as a series of roadcuts V4SW4 sec. 4, T. 14 N., R. 44 m west of Pullman, Whitman nember consists of at least two 1ember along an erosional unthe northeast side of Wilbur The top of the member is not ttered outcrops show that the Elsewhere on the Uniontown ie Wilbur Creek can be seen to iderlie, locally with erosional good reference locality where in the Cloverland Grade sec-3 m (1,770 ft) elevation in the 26, T. 10 N., R. 45 E., Asotin wiston Basin. The member is as normal magnetic polarity,

sely plagioclase-phyric (phenograined. In the field, it is distillar Member by its somewhat ing Asotin Member by its near bur Creek is compositionally in the Grande Ronde chemical phy. chemistry, and magnetic is tentatively correlated with 1 west of Cow Creek (T. 16 N., it and in the Warden-Othello of Grolier, 1965, p. 106-107; e central part of the Columbia cen recognized on the eastern es west of the Pasco Basin by

tes with the Wahluke flow of as judged by stratigraphic poity.

not been found but is assumed own Plateau area, as the flows ining westward.

## ASOTIN MEMBER

A single thick hackly jointed basalt flow occurring between the Wilbur Creek and Weissenfels Ridge Members in the Lewiston Basin of Washington and Idaho is defined as the Asotin Member (Camp, 1976). The member crops out particularly well near Asotin, Wash., and the type locality is designated as roadcuts along Cloverland Grade in the NE4SE4 sec. 26 and the NW4 and SW4 of the SW4 sec. 25, T. 10 N., R. 45 E., Asotin quadrangle, 5 km west-southwest of Asotin, Asotin County, extreme southeast Washington (pl. 1, fig. J). The base of the member is at about 543 m (1,780 ft), the top at about 585 m (1,920 ft) (Camp, 1976, fig. 14). Sedimentary deposits lie above and below the Asotin Member at the type locality and elsewhere in the Lewiston Basin. These deposits are easily erodible, leading to the development of a prominent cliff 40 to 50 m high that characterizes the member in many places.

The flow occurs as an invasive flow (Byerly and Swanson, 1978), a flow that has an invasive sill-like relation to the enclosing sedimentary rocks, at the type locality and many other places in the Lewiston Basin. The top of the flow is peperitic and chilled against the siltstone, predominantly subarkosic, which at the time of eruption was nonindurated and quite thin, as indicated by the presence of aerodynamically shaped ejecta sprinkled throughout the peperite (Camp, 1976). Other good exposures of the peperite at the top of the Asotin are at about 884 m (2,900 ft) on Montgomery Ridge, Wash. (SW4NE4 sec. 24, T. 8 N., R. 46 E., Captain John Rapids quadrangle) and at about 750 m (2,470 ft) on Weissenfels Ridge (NW4NW4 sec. 24, T. 9 N., R. 46 E., Lewiston Orchards South quadrangle).

The Asotin Member is sparsely olivine and plagioclase phyric. It contains more olivine than the underlying Wilbur Creek Member and less olivine than many flows of the overlying Weissenfels Ridge Member. The Asotin has a major-element composition similar to that of the basalt of Robinette Mountain (Eckler Mountain Member) table 2, Nos. 12 and 21) but has higher concentrations of most minor and trace elements. It differs also by lacking a coarse-grained diktytaxitic texture and by having no iddingsite after olivine. It contains more MgO and Al2O3 and less FeO than the Pomona Member, with which it might otherwise be confused, and has normal magnetic polarity.

The Asotin Member occurs on the Uniontown Plateau, where it fills a valley eroded into the underlying Wilbur Creek, Umatilla, and possibly Priest Rapids Members (Swanson and others, 1977, 1979). A chemically similar flow occurs near Lind in the central

A source for the Asotin has not been found, but distribution patterns suggest a vent southeast of the Uniontown Plateau.

A normally magnetized basalt flow occurs between probable correlatives of the Wilbur Creek and Esquatzel Members in core holes in the Pasco Basin. This was recognized by workers of the Atlantic Richfield Hanford Co. (Myers, 1973; Ledgerwood and others, 1973; Ward, 1976; Atlantic Richfield Hanford Co., 1976), who correlated the flow with the Huntzinger flow of Mackin (1961) on the basis of chemistry and magnetic polarity. The Huntzinger flow fills a channel, and its stratigraphic relations are obscure. Ward (1976) found a possible correlative of the Huntzinger overlying probable Wilbur Creek Member on Wahatis Peak in the Saddle Mountains (fig. 1); the attitude of columnar jointing suggests that this possible correlative is filling a shallow valley (Ward, 1976, fig. 4d and p. 17). Chemical correlations are not convincing, as the unit shows wide variation in composition for reasons not yet well understood (Ward, 1976). Nonetheless, several analyses in Ward (1976, tables 4 and 5) are similar in major and trace elements to the Asotin (table 2, No. 21; J. S. Fruchter, written commun., 1976). We tentatively suggest that the Huntzinger and Asotin are the same flow but favor retaining the informal name, Huntzinger, until such time as the postulated correlation can be better documented.

## WEISSENFELS RIDGE MEMBER

The name Weissenfels Ridge Member is here introduced for the three or more basalt flows between the underlying Asotin Member and the overlying Elephant Mountain Member in the Lewiston Basin of Washington and Idaho. The type locality is in roadcuts along Weissenfels Ridge, Asotin County, Wash., in the NW4 sec. 24 (projected) and the NE4 sec. 23 (projected), T. 9 N., R. 46 E., Captain John Rapids quadrangle (pl. 1, fig. K). The base of the member, exposed at about 756 m (2,480 ft) elevation, rests on micaceous sandstone and basaltic conglomerate overlying a peperite at the top of the Asotin Member. The member extends to the top of the ridge and is at least 34 m thick.

The Weissenfels Ridge Member is informally subdivided into two units, the basalt of Slippery Creek and the older basalt of Lewiston Orchards. Only the basalt of Lewiston Orchards occurs at the type locality. Both units have normal magnetic polarity.

The basalt of Lewiston Orchards (Camp, 1976) occurs chiefly in that part of the Lewiston Basin in western Idaho. It underlies the

plateau surface on which the built and is particularly well in roadcuts at 380 m (1,250 f sec. 8, T. 35 N., R. 5 W., Lew the unit, consisting of one fic 10 to 15 m thick. Most of the coarse grained and sparsely rarely as large as 1 cm. Olivi ical analysis of the Lewiston be relatively rich in MgO a have not yet been recognized. Lewiston Basin (Camp, 1976

The basalt of Slippery Cr (oral commun., 1976), is wel (NE4 sec. 21, T. 7 N., R. 46 is the upper flow along the s ticularly in sec. 32, T. 8 N., Butte quadrangles. It covers southeast Washington south averaging about 10 m thic. Camp (1976). The Slippery plagioclase phenocrysts 3 m much groundmass olivine v than any other flow in the have seen. The Slippery Crefers from other flows in the 22). Feeder dikes have not

One or more flows near Ar typical basalts of Lewiston (a similar stratigraphic posi Weissenfels Ridge Member type (table 2, No. 18). A poss the mouth of Hackberry Gu 46 E., Black Butte quadrang

ESQ

The name Esquatzel Mer flow occurring in Esquatzel km north of Pasco, Wash. The a hillslope on the north sic between 223 and 241 m (7: 13 N., R. 30 E., Mesa quac Washington (pl. 1, fig. L). unconformity on the Priest

ant of the member that flowed teau (pl. 1, fig J; Swanson and

n found, but distribution pat-Uniontown Plateau.

occurs between probable coruatzel Members in core holes ed by workers of the Atlantic edgerwood and others, 1973; rd Co., 1976), who correlated Mackin (1961) on the basis of Huntzinger flow fills a chanobscure. Ward (1976) found a r overlying probable Wilbur he Saddle Mountains (fig. 1); sts that this possible correla-976, fig. 4d and p. 17). Chemithe unit shows wide variation ell understood (Ward, 1976). d (1976, tables 4 and 5) are the Asotin (table 2, No. 21; 1. We-tentatively suggest that e flow but favor retaining the time as the postulated corre-

# MEMBER

er is here introduced for the e underlying Asotin Member in Member in the Lewiston type docality is in roadcuts y. Wash., in the NW4 sec. 24 ed), NY9 N., R. 46 E., Captain The base of the member, exceptation, rests on micaceous verlying a peperite at the top tends to the top of the ridge

formally subdivided into two the older basalt of Lewiston Orchards occurs at the type etic polarity.

amp, 1976) occurs chiefly in stern Idaho. It underlies the plateau surface on which the town of Lewiston Orchards, Idaho, is built and is particularly well exposed above a sedimentary interbed in roadcuts at 380 m (1,250 ft) along Thain Road, near the center of sec. 8, T. 35 N., R. 5 W., Lewiston Orchards North quadrangle. Here the unit, consisting of one flow, is 37 m thick; elsewhere it averages 10 to 15 m thick. Most of the basalt of Lewiston Orchards is rather coarse grained and sparsely plagioclase-phyric, with phenocrysts rarely as large as 1 cm. Olivine is visible in hand specimen. A chemical analysis of the Lewiston Orchards (table 2, No. 23) shows it to be relatively rich in MgO and poor in K2O. Definite feeder dikes have not yet been recognized, although possible feeders occur in the Lewiston Basin (Camp, 1976).

The basalt of Slippery Creek, a name suggested by S. M. Price (oral commun., 1976), is well exposed at the head of Slippery Creek (NE¼ sec. 21, T. 7 N., R. 46 E., Black Butte quadrangle, Wash.) and is the upper flow along the southern part of Weissenfels Ridge, particularly in sec. 32, T. 8 N., R. 46 E., Weissenfels Ridge and Black Butte quadrangles. It covers most of the plateau surface in extreme southeast Washington south of Asotin Creek and north of Anatone, averaging about 10 m thick. It includes the Uniontown-3 flow of Camp (1976). The Slippery Creek contains moderately abundant plagioclase phenocrysts 3 mm or less in length. At least one flow has much groundmass olivine visible with a hand lens, probably more than any other flow in the Columbia River Basalt Group that we have seen. The Slippery Creek has a chemical composition that differs from other flows in the Saddle Mountains Basalt (table 2, No. 22). Feeder dikes have not been found.

One or more flows near Anatone, Wash., are poorer in olivine than typical basalts of Lewiston Orchards or Slippery Creek but occur at a similar stratigraphic position; they are here included within the Weissenfels Ridge Member. These flows are of the Lolo chemical type (table 2, No. 18). A possible feeder dike occurs on a hillside near the mouth of Hackberry Gulch, in the NE4SE4 sec. 30, T. 7 N., R. 46 E., Black Butte quadrangle (S. M. Price, written commun., 1977).

## ESQUATZEL MEMBER

The name Esquatzel Member is here applied to a phyric basalt flow occurring in Esquatzel Coulee near the community of Mesa, 40 km north of Pasco, Wash. The type locality is 1 km north of Mesa, on a hillslope on the north side of Esquatzel Coulee, at an elevation between 223 and 241 m (730–790 ft) in the NW4NW4 sec. 25, T. 13 N., R. 30 E., Mesa quadrangle, Franklin County, south-central Washington (pl. 1, fig. L). Here the Esquatzel rests with erosional unconformity on the Priest Rapids Member and is overlain by the

Pomona Member. A more accessible reference locality that better exposes lithology but lacks definitive contact relations is a prominent roadcut on the south side of Esquatzel Coulee in Mesa, in the SW4NW4 sec. 25, T. 13 N., R. 30 E. The Esquatzel Member fills a shallow valley eroded into the Priest Rapids Member throughout the Mesa area.

Remnants of one or more intracanyon flows correlated petrographically and chemically with the type Esquatzel occur along an ancestral Snake River canyon from Devils Canyon upstream to the mouth of New York Gulch (Swanson and others, 1977; 1979), a distance of about 52 km (pl. 1, fig. L).

The Esquatzel-Member contains phenocrysts and glomerophyricclots of strongly zoned plagioclase and clinopyroxene less than 5 mm in diameter. The distribution of phenocrysts is quite irregular; some hand samples are highly phyric and others are nearly aphyric, as is well shown at the reference locality in Mesa. The member has a distinctive chemical composition (table 2, No. 24).

The Esquatzel averages 10 m in thickness but reaches 50 m in some canyon-filling remnants. It has normal magnetic polarity (Choiniere and Swanson, 1979).

A source for the Esquatzel Member has not been found with certainty. Its occurrence far up the ancestral Snake River canyon suggests the probability of a source in the eastern part of the Columbia Plateau. On the other hand, three small (less than a 5-m diameter) columnar-jointed knobs surrounded by Holocene sand south of Eltopia in T. 11 N., R. 30 E. (Swanson and others, 1977, 1979) have Esquatzel-type petrography and chemistry. The knobs are alined in a northwest direction, similar to the trend of known dikes in the area, suggesting the remote possibility that they are eroded pluglike bodies protruding above the neighboring Elephant Mountain Member. Alternatively, they may be glacial erratics deposited during the Missoula floods in late Pleistocene time. Paleomagnetic studies could determine if the blocks have been rotated after cooling. The largest (northernmost) of these knobs was destroyed by blasting during preparation of new farmland in 1975.

The Esquatzel Member is probably equivalent to the informal Gable Mountain member of Atlantic Richfield Hanford Co. (1976), as judged by stratigraphic position, chemical composition, and magnetic polarity.

#### POMONA MEMBER

Schmincke (1967a) gave the name Pomona Basalt to a prominent, easily recognized flow that is widespread in south-central Washington and adjacent Oregon. We hereby formalize the name as the Pomona Member and designate the type locality as that from

which Schmincke named the i yon Road (old Highway 97) at 17, T. 14 N., R. 19 E., Pomona Pomona, Yakima County, sou Neither the base nor the topolocality, but many exposures Pomona is interbedded with vellensburg Formation (Water Pomona). The Esquatzel Mem to underlie the Pomona; this rof the Esquatzel. The Elephan est flow known to overlie the along Rattlesnake Ridge east R. 20 E., Elephant Mountain in south-central Washington.

The member covers much of bia Plateau from the Saddle M (fig. 1; pl. 1, fig. M) to norther the Columbia River at leas (Schmincke, 1967a) and may Ocean, as it is similar in all Lookout in southwest Washir. cent work indicates its prese tracanyon flow along an ance: in extreme southeast Washing Columbia Plateau (pl. 1, fig. & son and others, 1977, 1979). the canyon from a source in mouth of the canyon in the Coulee (Tps. 12 and 13 N., Rs into a broad basin across wh peperite is commonly develor unconsolidated vitric ash nea 1967a).

Good reference localities for in addition to those given by cooling units overlain by the cuts along Highway 17, 1 km sive relations into a vitric tur road cuts and natural exposur Dam on the north side of the upriver to the west half of se rangle, (3) spectacular colum yon flow in roadcut and roac

1100000

reference locality that better contact relations is a promilatzel Coulee in Mesa, in the The Esquatzel Member fills a apids Member throughout the

yon flows correlated petrope Esquatzel occur along an vils Canyon upstream to the nd others, 1977; 1979), a dis-

enocrysts and glomerophyric dinopyroxene less than 5 mm rysts is quite irregular; some thers are nearly aphyric, as in Mesa. The member has a 2, No. 24).

ickness but reaches 50 m in normal magnetic polarity

has not been found with cercestral Snake River canyon the eastern part of the Cohree small (less than a 5-m rrounded by Holocene sand (Swanson and others, 1977, y and chemistry. The knobs milar to the trend of known ote possibility that they are we the neighboring Elephant ev may be glacial erratics ate Pleistocene time. Paleohe blocks have been rotated ost) of these knobs was deof new farmland in 1975.

equivalent to the informal chfield Hanford Co. (1976), as mical-composition, and mag-

mona Basalt to a prominent, despread in south-central ereby formalize the name as e type locality as that from which Schmincke named the unit, specifically, roadcuts along Canyon Road (old Highway 97) and a nearby quarry in the NE¼ sec. 17, T. 14 N., R. 19 E., Pomona quadrangle, near the community of Pomona, Yakima County, south-central Washington (pl. 1, fig. M). Neither the base nor the top of the member is exposed at the type locality, but many exposures in adjacent areas show that the Pomona is interbedded with volcaniclastic sedimentary rocks of the Ellensburg Formation (Waters, 1955, pl. 1 [his Wenas flow is the Pomona]). The Esquatzel Member contains the youngest flow known to underlie the Pomona; this relation is exposed at the type locality of the Esquatzel. The Elephant Mountain Member contains the oldest flow known to overlie the Pomona, as indicated by relations along Rattlesnake Ridge east of Donald Pass (secs. 19–22, T. 12 N., R. 20 E., Elephant Mountain quadrangle) and at many other places in south-central Washington.

The member covers much of the southwestern part of the Columbia Plateau from the Saddle Mountains in south-central Washington (fig. 1; pl. 1, fig. M) to northernmost Oregon. It extends west along the Columbia River at least as far as Mosier, Oreg. (pl. 1) (Schmincke, 1967a) and may have reached nearly to the Pacific Ocean, as it is similar in all respects to the basalt of Pack Sack Lookout in southwest Washington (Snavely and others, 1973). Recent work indicates its presence in nearly 50 remnants of an intracanyon flow along an ancestral Snake River canyon from Asotin in extreme southeast Washington to the Pasco Basin in the central Columbia Plateau (pl. 1, fig. M; Swanson and Wright, 1976b; Swanson and others, 1977, 1979). The flow presumably advanced down the canyon from a source in western Idaho, emptying from the mouth of the canyon in the lower part of what is now Old Maid Coulee (Tps. 12 and 13 N., Rs. 30 and 31 E., Mesa East quadrangle) into a broad basin across which the flow moved as a sheetflood. A peperite is commonly developed where the Pomona ploughed into unconsolidated vitric ash near the margin of the flow (Schmincke, .1967a)... ...

Good reference localities for the Pomona Member in Washington, in addition to those given by Schmincke (1967a, b), include (1) two cooling units overlain by the Elephant Mountain Member in roadcuts along Highway 17, 1 km north of Mesa, (2) peperite and invasive relations into a vitric tuff in the Ellensburg Formation in railroad cuts and natural exposures 3 to 6 km upstream from Ice Harbor Dam on the north side of the Snake River from the center of sec. 18 upriver to the west half of sec. 4, T. 9 N., R. 32 E., Levey SE quadrangle, (3) spectacular columnar jointing in a remnant of intracanyon flow in roadcut and roadside quarry along Hastings Hill Road

, V

The Pomona Member consists in most places of a single sparsely phyric flow of Pomona chemical type (table 2, No. 25; Wright and others, 1973). The flow can be subdivided into two units in a few places, as 6 km upstream from Ice Harbor Dam and 1 km north of Mesa; but these units are not traceable far, are commonly associated with peperites and invasive flows (Schmincke, 1967a), and presumably represent gushes of one major eruptive event.

The member is characterized petrographically by small commonly wedge-shaped phenocrysts of plagioclase (generally less than 5 mm long), together with scattered clinopyroxene and olivine. Some plagioclase phenocrysts are riddled with clinopyroxene inclusions. Modal analyses show low plagioclase-pyroxene ratios, generally less than 1 (Schmincke, 1967a). Locally, the flow contains large clots (to 10 cm or more across) of plagioclase, pyroxene (including very rare hypersthene), and olivine; the best locality for observing such clots is in a quarry on the east side of Devils Canyon (SW<sup>1</sup>4SW<sup>1</sup>4 sec. 22, T. 13 N., R. 34 E., Lower Monumental Dam quadrangle).

The Pomona averages about 30 m thick outside the ancestral Snake River canyon. Its maximum preserved thickness in the ancient canyon is 110 m near the mouth of the Tucannon River (fig. 1). It has reversed magnetic polarity (Rietman, 1966; Choiniere and Swanson, 1979) and is about 12 m.y. old (McKee and others, 1977). A definite feeder dike has not been found, although a dike matching many of the Pomona's characteristics cuts Grande Ronde Basalt along Wapshilla Creek, a tributary of the lower Salmon River draining Craig Mountain, western Idaho (pl. 1, fig. M; S. P. Reidel, oral commun., 1976, 1978).

Schmincke (1967a) studied the Pomona in detail, and his paper is the best source of additional information.

## ELEPHANT MOUNTAIN MEMBER

Waters (1955) named the Elephant Mountain flow from exposures near Elephant Mountain (chiefly in secs. 22 and 27, T. 12 N., R. 20 E., Elephant Mountain quadrangle), on Rattlesnake Ridge about 16 km southeast of Yakima, Yakima County, south-central Washington. Schmincke (1967a) considered this flow to be regionally extensive throughout south-central Washington and redesignated it the Elephant Mountain Basalt Member. He recognized an overlying but otherwise similar flow at several places in south-central Washington from the eastern Horse Heaven Hills north to Sentinel Gap and named it the Ward Gap Basalt Member from outcrops at

Ward Gap (NE4SE4 sec. 20, '6.5 km west of Prosser, Wash. We here assign both Schmi Gap Basalt Members to the Eldure followed by Atlantic Richard (pl. 1, fig. N) is that phant Mountain. The name Wincluded in the Elephant Moutype Elephant Mountain. War ity for the member.

Only two flows are known Member west of the Columbialar characteristics occur in the eral localities east of the rive: the member. Such flows crop (NE4 sec. 23, T. 11 N., R. 30 f of Scooteny Reservoir (secs. 2 quadrangle).

**特别等情的,是是自己的** 

The member occurs as a sl south of Clarkston, Wash. (Ca. 1979) and appears to spill into the basin about 7 km west of ( Silcott quadrangle). Remnant. occur along an ancestral Snake km upriver from Clarkston as 5 km north-northwest of Si the Palouse River and Devils 1977, 1979). The Wenaha flo-Ronde River valley near Troy tively correlated with the E chemistry, magnetic polarity, a because a series of intracanyon drainage of Asotin Creek nea Lewiston Basin areas (Swansoi

The member is composed of a flows of Elephant Mountain chand others, 1973). Its thickness m in intracanyon remnants ale 10 N., R. 44 E., Potter Hill quare River near Skookum Canyon a Haas quadrangle). The member netic polarity (Rietman, 1966; about 10.5 m.y. old (McKee an

The Elephant Mountain is c

Hay quadrangle, and (4) columquarry just east of Silcott, SW¼ uadrangle.

most places of a single sparsely to (table 2, No. 25; Wright and livided into two units in a few farbor Dam and 1 km north of the far, are commonly associated hmincke, 1967a), and presumatuptive event.

graphically by small commonly lase (generally less than 5 mm copyroxene and olivine. Some with clinopyroxene inclusions. -pyroxene ratios, generally less the flow contains large clots (to, pyroxene (including very rare ocality for observing such clots ils Canyon (SW4SW4 sec. 22, tal Dam quadrangle).

o thick outside the ancestral preserved thickness in the anof the Tucannon River (fig. 1). Lietman, 1966; Choiniere and old (McKee and others, 1977). Ind, although a dike matching is cuts Grande Ronde Basalt the lower Salmon River drainpl. Pring. M; S. P. Reidel, oral

ona in detail, and his paper is

## IN MEMBER

Mountain flow from exposures cs. \$22 and 27, T. 12 N., R. 20 on Rattlesnake Ridge about County, south-central Wash-d this flow to be regionally shington and redesignated it r. He recognized an overlying ral places in south-central eaven Hills north to Sentinel alt Member from outcrops at

` ₹

Ward Gap (NE4SE4 sec. 20, T. 8 N., R. 24 E., Prosser quadrangle), 6.5 km west of Prosser, Wash.

We here assign both Schmincke's Elephant Mountain and Ward Gap Basalt Members to the Elephant Mountain Member, the procedure followed by Atlantic Richfield Hanford Co. (1976). The type locality (pl. 1, fig. N) is that designated by Waters (1955) on Elephant Mountain. The name Ward Gap is abandoned and the flow is included in the Elephant Mountain because of its similarity to the type Elephant Mountain. Ward Gap is designated a reference locality for the member.

Only two flows are known to occur in the Elephant Mountain Member west of the Columbia River, but three or more flows of similar characteristics occur in the same stratigraphic position at several localities east of the river in Washington and are assigned to the member. Such flows crop out in the area 5 km south of Eltopia (NE¼ sec. 23, T. 11 N., R. 30.E., Eltopia quadrangle) and just south of Scooteny Reservoir (secs. 26 and 27, T. 14 N., R. 30 E., Mesa quadrangle).

The member occurs as a sheetlike flow in the Lewiston Basin south of Clarkston, Wash. (Camp, 1976; Swanson and others, 1977, 1979) and appears to spill into an ancestral Snake River channel in the basin about 7 km west of Clarkston (sec. 22, T. 11 N., R. 45 E., Silcott quadrangle). Remnants of one or more intracanyon flows occur along an ancestral Snake River canyon from a point about 20 km upriver from Clarkston across the Lewiston Basin to a point 5 km north-northwest of Silcott, and between the mouth of the Palouse River and Devils Canyon (fig. 1; Swanson and others, 1977, 1979). The Wenaha flow of Walker (1973), in the Grande Ronde River valley near Troy, Oreg. (fig. 1; Ross, 1978), is tentatively correlated with the Elephant Mountain on the basis of chemistry, magnetic polarity, and gross stratigraphic position, and because a series of intracanyon flow remnants of the member in the drainage of Asotin Creek nearly connect the Grande Ronde and Lewiston Basin areas (Swanson and others, 1977, 1979).

The member is composed of nearly aphyric generally fine-grained flows of Elephant Mountain chemical type (table 2, No. 26: Wright and others, 1973). Its thickness averages about 30 m; it reaches 150 m in intracanyon remnants along Asotin Creek (sec. 26 and 34, T. 10 N., R. 44 E., Potter Hill quadrangle) and 100 m along the Snake River near Skookum Canyon (secs. 20 and 21, T. 13 N., R. 35 E., Haas quadrangle). The member has transitional and normal magnetic polarity (Rietman, 1966; Choiniere and Swanson, 1979) and is about 10.5 m.y. old (McKee and others, 1977).

The Elephant Mountain is only slightly less extensive than the

Pomona in south-central Washington and adjacent Oregon (Schmincke 1967a, fig. 20; Shannon and Wilson, Inc., 1973), but there is no evidence that it extended westward through the Columbia River Gorge (pl. 1, fig N).

All flows in the member are thought to have been erupted in extreme southeast Washington and adjacent Oregon and (or) Idaho (pl. 1, fig. N). A feeder dike occurs discontinuously from sec. 4, T. 6 N., R. 42 E., Diamond Peak quadrangle, southeast Washington, to at least as far south as sec. 19, T. 5 N., R. 43 E., Troy quadrangle, northeast Oregon (Ross, 1978; Swanson and others, 1977, 1979). Another dike of Elephant Mountain chemical type occurs in the headwaters of Cache Creek, extreme northeast Oregon (S. P. Reidel, oral commun., 1976, 1978).

#### **BUFORD MEMBER**

Walker (1973) gave the informal name Buford flow to a fine- to medium-grained very sparsely plagioclase- and olivine-phyric flow overlying sedimentary deposits in the Buford Creek area of extreme northeast Oregon. Subsequent work (Ross, 1978; Price, 1977; Swanson and others, 1977, 1979) showed that this flow extends north and west from Buford Creek and that it is of post-Elephant Mountain age, judged by stratigraphic relations in the Grande Ronde Valley.

The Buford flow is hereby raised to member status, with its type locality as designated by Walker (1973) about 7.5 km north-northeast of Flora, Oreg. (fig. 1), in a small quarry on the east side of Highway 3 at 1,225 m (4,020 ft) elevation in the NE4NE4 sec. 2, T. 5 N., R. 44 E., Flora quadrangle, Wallowa County, extreme north-east Oregon (pl. 1, fig. 0). A good reference locality is above a white tuff in a roadcut along Highway 129, 8 km northeast of Anatone, Wash. (fig. 1), in the SE4NW4 sec. 5, T. 8 N., R. 46 E., Weissenfels Ridge quadrangle, southeast Washington.

The Buford Member everywhere consists of one basalt flow, generally 20 to 30 m thick, with reversed magnetic polarity (Price, 1977; Ross, 1978; Swanson and Wright, unpub. data, 1977). The Buford has a major-element chemical composition (table 2, No. 27) similar to some flows in the Grande Ronde Basalt except that it has generally lower Na<sub>2</sub>O for a given MgO content.

The Buford Member is the youngest known basalt on the plateau surface of extreme southeast Washington and northeast Oregon. The age relation of the Buford to the Ice Harbor and Lower Monumental Members is not clear. We believe that it is older than both, as it does not appear to have filled canyons eroded into the Elephant Mountain Member, as do the Ice Harbor and Lower Monumental Members. This implies that the Buford was erupted relatively soon after the

Elephant Mountain. The sou distribution (pl. 1, fig. 0) sug adjacent parts of Idaho or Or ICE H

Flows and minor tephra y Member crop out along the Dam area and were termed t and others (1973). This name Member, and the type locality on the south side of the Snake in SE4SE4 sec. 22, T. 9 N., Walla County, southeast Wa

Two thick flows, separated several thin, discontinuous f tain Member in a shallow sy flow, about 15 m thick and phenocrysts and glomerocry: olivine and has reversed ma others, 1976; Choiniere and nate this flow as the basalt of north side of the Snake Riv downstream from the type loc ence localities, all in Washin clude (1) the highest cliffs alc about 3 km west of Reese (fig Junction quadrangle, (2) a qu in the SW4NE4 sec. 14, T. : rangle, and (3) exposures 5.5 side of Highway 395, NW4 se rangle. The basalt of Martine mally named units in the Ice 1977, 1979).

The tephra, associated this totaling about 15 m in thic sparsely phyric with respect olivine and have transitions 1978; Helz and others, 1976; rocks are assigned to the in Island, named for a small isla ity of the member. A good re Island is a quarry 9.5 km is SW4SE4 sec. 29, T. 10 N., R sand sometimes makes roads four-wheel-drive vehicles.

ngton and adjacent Oregon n and Wilson, Inc., 1973), but I westward through the Colum-

ght to have been erupted in exacent Oregon and (or) Idaho (pl. ntinuously from sec. 4, T. 6 N., e, southeast Washington, to at N., R. 43 E., Troy quadrangle, inson and others, 1977, 1979). n chemical type occurs in the northeast Oregon (S. P. Reidel,

# MBER

name Buford flow to a fine- to ioclase- and olivine-phyric flow e Buford Creek area of extreme (Ross, 1978; Price, 1977; Swanhat this flow extends north and t is of post-Elephant Mountain is in the Grande Ronde Valley. to member status, with its type (1978) about 7.5 km northsmall quarry on the east side of ation in the NE4NE4 sec. 2, T. allowa County, extreme northerence locality is above a white 9, 8 km northeast of Anatone, 5, T. 8 N., R. 46 E., Weissenfels

consists of one basalt flow, genersed magnetic polarity (Price, right, unpub. data, 1977). The al composition (table 2, No. 27) Ronde Basalt except that it has

gO content.

st known basalt on the plateau gton and northeast Oregon. The Harbor and Lower Monumental t it is older than both, as it does ded into the Elephant Mountain Lower Monumental Members. rupted relatively soon after the Elephant Mountain. The source for the Buford is unknown, but its distribution (pl. 1, fig. O) suggests extreme southeast Washington or adjacent parts of Idaho or Oregon.

## ICE HARBOR MEMBER

Flows and minor tephra younger than the Elephant Mountain Member crop out along the lower Snake River in the Ice Harbor Dam area and were termed the flows at Ice Harbor Dam by Wright and others (1973). This name is here formalized as the Ice Harbor Member, and the type locality is designated as an abandoned quarry on the south side of the Snake River 2.6 km west of Ice Harbor Dam, in SE4SE4 sec. 22, T. 9 N., R. 31 E., Humorist quadrangle, Walla Walla County, southeast Washington (pl. 1, fig. P).

Two thick flows, separated by a deposit of tephra associated with several thin, discontinuous flows, occur above the Elephant Mountain Member in a shallow syncline at the type locality. The lower flow, about 15 m thick and markedly columnar, contains single phenocrysts and glomerocrysts of clinopyroxene, plagioclase, and olivine and has reversed magnetic polarity (Helz, 1978; Helz and others, 1976; Choiniere and Swanson, 1979). We informally designate this flow as the basalt of Martindale, a railroad siding on the north side of the Snake River in Franklin County about 3.5 km downstream from the type locality of the Ice Harbor Member. Reference localities, all in Washington, for the basalt of Martindale include (1) the highest cliffs along both sides of the Walla Walla River about 3 km west of Reese (fig. 1), in sec. 21, T. 7 N., R. 32 E., Zangar Junction quadrangle, (2) a quarry about 12 km west of Kennewick, in the SW4NE4 sec. 14, T. 8 N., R. 28 E., Badger Mountain quadrangle, and (3) exposures 5.5 km southwest of Eltopia along the east

side of Highway 395, NW4 sec. 27, T. 11 N., R. 30 E., Eltopia quad-

rangle. The basalt of Martindale is the most extensive of the informally named units in the Ice Harbor Member (Swanson and others,

1977, 1979).

The tephra, associated thin flows, and the overlying thick flow, totaling about 15 m in thickness above the Martindale flow, are sparsely phyric with respect to plagioclase, magnetite, and rarely olivine and have transitional to normal magnetic polarity (Helz, 1978; Helz and others, 1976; Choiniere and Swanson, 1979). These rocks are assigned to the informally named unit, basalt of Goose Island, named for a small island in the Snake River at the type locality of the member. A good reference locality for the basalt of Goose Island is a quarry 9.5 km northwest of Ice Harbor Dam, in the SW4SE4 sec. 29, T. 10 N., R. 31 E., Levey SW quadrangle; drifting sand sometimes makes roads to this quarry impassable to all but four-wheel-drive vehicles.

The basalts of Martindale and Goose Island have distinctly different chemistries (Helz, 1978; table 2, No. 29-30), designated Ice Harbor 1 chemical type and Ice Harbor 2 chemical type, respectively, by Wright and others (1973). The names of these chemical types are hereby changed to Martindale and Goose Island chemical types, respectively, to agree with the informal stratigraphic terminology.

North of the Ice Harbor area, sparsely phyric flows with olivine and plagioclase phenocrysts and glomerocrysts to 2 cm in diameter and normal magnetic polarity (Helz, 1978; Helz and others, 1976; Choiniere and Swanson, 1979) occur stratigraphically above the Elephant Mountain Member and below the basalt of Goose Island. The relation of these flows, which have a chemistry termed the Basin City chemical type by Helz and others (1976) (table 2, No. 28), to the basalt of Martindale is uncertain; field relations suggest that the basalt of Basin City is older (Helz and others, 1976; Helz, 1978). These olivine and plagioclase-phyric flows are considered to be part of the Ice Harbor Member and are here assigned to the informal unit, the basalt of Basin City, named for a small community 11 km west of Mesa, Franklin County. Reference localities for the basalt of Basin City include (1) the area just northwest of two small lakes in the SW4NE4 sec. 20, T. 12 N., R. 30 E., Mesa quadrangle, 7 km northwest of Eltopia, and (2) the area 1.5 km north of Basin City in secs. 14 and 24, T. 13 N., R. 29 E., Mesa quadrangle. The Basin City occupies a narrow graben cutting the Elephant Mountain Member at both of these localities (Swanson and others, 1975).

The Ice Harbor Member is generally about 15 m, nowhere more than-30 m, thick. It occurs as a narrow belt of outcrops separated by younger alluvial deposits extending about 90 km north-northwest from near the Washington-Oregon border south of Reese (fig. 1; Swanson and others, 1977, 1979). The member caps the highest bluff on the west side of Wallula Gap (Ledgerwood and others, 1973; Swanson and others, 1975) and occurs along the Red Mountain-Badger Mountain line of plunging anticlines between Benton City and Wallula Gap and in a core hole (DDH-3) in north Richland (Myers, 1973; Atlantic Richfield Hanford Co., 1976); only the basalt of Martindale has been identified at these three localities.

Many dikes and vent areas for flows in the Ice Harbor Member have been located along the elongate, north-northwest belt of major outcrops (pl. 1, fig. P; Swanson and others, 1975; 1977, 1979). The member is about 8.5 m.y. old (McKee and others, 1977) and is the product of the youngest known eruptive activity in the central Columbia Plateau.

Helz (1978) has completed an exhaustive study of the Ice Harbor Member, stressing petrogenetic implications, and her work should be consulted by those interest the member.

LOWER MON

COLUMBIA R

A nearly aphyric flow overl: m above the present Snake R Dam, Walla Walla County, s show that this flow partly fil eroded into rocks as young as flow is here named the Lower is in a prominent roadcut 1 k sec. 3, T. 12 N., R. 34 E., Lowe fig. Q), where the member is

The age relation of the Ice I bers cannot be firmly establish ferred interpretation is that th occurs within a canyon whose the Ice Harbor Member. Who nations support this interpreta for the Lower Monumental A the Ice Harbor (McKee and o

Many remnants of one or me the Lower Monumental occur River from the type locality up a distance of about 150 km ald Swanson and others, 1977, 19 thick; locally it thickens to at larity (Choiniere and Swanson

The member is composition but is distinguished from it ch (table 2, No. 31) contents. It Mountain Member in the fie shows moderately abundant (so folivine in the Lower Mos Elephant Mountain Member.

The Lower Monumental Nerupted in the eastern part of flowed down the ancestral Sne was produced by the younger lumbia River Basalt Group.

Camp (1976), with the concreted a dike in the Lewist Monumental Member. Howev up the northwest wall of Tenr

Island have distinctly differ-29-30), designated Ice Hartemical type, respectively, by of these chemical types are se Island chemical types, restratigraphic terminology.

stratigraphic terminology. ly phyric flows with olivine rocrysts to 2 cm in diameter 978; Helz and others, 1976; stratigraphically above the the basalt of Goose Island. ve a chemistry termed the hers (1976) (table 2, No. 28), ; field relations suggest that nd others, 1976; Helz, 1978). iws are considered to be part re assigned to the informal or a small community 11 km ice localities for the basalt of thwest of two small lakes in E., Mesa quadrangle, 7 km .5 km north of Basin City in quadrangle. The Basin City Ele<del>ph</del>ant Mountain Member d others, 1975).

about 15 m, nowhere more belt of outcrops separated by out 90 km north-northwest rder south of Reese (fig. 1; tember caps the highest bluff dgerwood and others, 1973; s along the Red Mountainiclines between Benton City (DDH-3) in north Richland Co., 1976); only the basalt less three localities.

s in the Ice Harbor Member forth-northwest belt of major hers, 1975; 1977, 1979). The and others, 1977) and is the re activity in the central Co-

stive study of the Ice Harbor ations, and her work should be consulted by those interested in further information concerning the member.

#### LOWER MONUMENTAL MEMBER

A nearly aphyric flow overlies poorly consolidated river gravel 80 m above the present Snake River just south of Lower Monumental Dam, Walla Walla County, southeast Washington. Field relations show that this flow partly filled an ancestral Snake River canyon eroded into rocks as young as the Elephant Mountain Member. The flow is here named the Lower Monumental Member; its type locality is in a prominent roadcut 1 km south of the dam in the NW4SE4 sec. 3, T. 12 N., R. 34 E., Lower Monumental Dam quadrangle (pl. 1, fig. Q), where the member is about 30 m thick.

The age relation of the Ice Harbor and Lower Monumental Members cannot be firmly established on stratigraphic grounds. Our preferred interpretation is that the Lower Monumental is younger, as it occurs within a canyon whose lower end appears to be eroded into the Ice Harbor Member. Whole-rock potassium-argon age determinations support this interpretation, indicating an age of about 6 m.y. for the Lower Monumental Member, about 2.5 m.y. younger than the Ice Harbor (McKee and others, 1977).

Many remnants of one or more intracanyon flows correlated with the Lower Monumental occur along the present course of the Snake River from the type locality upstream to the mouth of Asotin Creek, a distance of about 150 km along the course of the river (pl. 1, fig. Q; Swanson and others, 1977, 1979). The member averages about 25 m thick; locally it thickens to about 60 m. It has normal magnetic polarity (Choiniere and Swanson, 1979).

The member is compositionally similar to the Lolo chemical type but is distinguished from it chiefly by slightly higher Na2O and K2O (table 2, No. 31) contents. It can be confused with the Elephant Mountain Member in the field, but inspection with a hand lens shows moderately abundant (about 2.5–3 percent) microphenocrysts of olivine in the Lower Monumental not generally seen in the Elephant Mountain Member.

The Lower Monumental Member is interpreted to have been erupted in the eastern part of the Columbia Plateau and to have flowed down the ancestral Snake River as far as the type locality. It was produced by the youngest known volcanic activity in the Columbia River Basalt Group.

Camp (1976), with the concurrence of Swanson and Wright, interpreted a dike in the Lewiston Basin as a feeder for the Lower Monumental Member. However, this dike has been found to extend up the northwest wall of Tenmile Creek Canyon (about 6 km south-

-1255

east of Asotin) to, but not through, the capping Pomona Member. We now believe that the dike is older than the Pomona and may be a feeder for flows in the Weissenfels Ridge Member.

## REFERENCES CITED

Atlantic Richfield Hanford Company, 1976, Preliminary feasibility study of storage of radioactive wastes in Columbia River basalts: ERDA Rept. ARH-ST-137, v. 1, text, 168 p., v. 2, app., 264 p.

Baksi, A. K., and Watkins, N. D., 1973, Volcanic production rates—comparison of oceanic ridges, islands, and the Columbia Plateau basalts: Science, v. 180, p. 493-496.

Beeson, M. H., Moran, M. R., and Olson, F. L., 1976, Geochemical data on Columbia River basalt stratigraphy in western Oregon: Geol. Soc. America Abs. with Programs, v. 8, no. 3, p. 354.

Bentley, R. D., 1977, Stratigraphy of the Yakima Basalts and structural evolution of the Yakima ridges in the western Columbia Plateau, in Brown, E. H., and Ellis, R. C., eds., Geological excursions in the Pacific Northwest: Bellingham, Western Washington Univ. Press, p. 339-389.

Bentley, R. D., and Cockerham, R. S., 1973, The stratigraphy of the Picture Gorge Basalt (PGB), northcentral Oregon: Geol. Soc. America Abs. with Programs, v. 5, no. 1, p. 9.

Berggren, W. A., 1972, A Cenozoic time-scale—some implications for regional geology and paleobiogeography: Lethaia, v. 5, no. 2, p. 195-215.

Berggren, W. A., and Van Couvering, J. A., 1974, The late Neogene-Biostratigraphy, geochronology, and paleoclimatology of the last 15 million years in marine and continental sequences: Palaeogeography, Palaeoclimatology, Palaeoecology, v. 16, p. 1-216.

Bingham, J. W., and Grolier, M. J., 1966, The Yakima Basalt and Ellensburg Formation of south-central Washington: U.S. Geol. Survey Bull. 1224-G, 15 p.

Bingham, J. W., and Walters, K. L., 1965, Stratigraphy of the upper part of the Yakima Basalt in Whitman and eastern Franklin Counties, Washington, in Geological Survey Research 1965; U.S. Geol. Survey Prof. Paper 525-C, p. C87-C90.

Bond, J. G., 1963, Geology of the Clearwater embayment: Idaho Bur. Mines and Geology Pamph. 128, 83 p.

Brown, J. C., 1976, Well construction and stratigraphic information: Pullman Test Observation Well, Pullman, Washington: Washington State Univ. Coll. Eng. Research Rept. 76/15-6, 35 p.

Bush, J. H., Morton, H. A., Anderson, J. V., Crosby, J. W., 3d, and Siems, B. A., 1973, Test-observation well near Walla Walla, Washington—Description, stratigraphic relationships, and preliminary results: Washington State Univ. Coll. Eng. Rept. 73/15-66, 38 p.

Byerly, Gary, and Swanson, Don, 1978, Invasive Columbia River basalt flows along the northwestern margin of the Columbia Plateau, north-central Washington: Geol. Soc. America Abs. with Programs, v. 10, no. 3, p. 98.

Camp, V.E., 1976, Petrochemical stratigraphy and structure of the Columbia River basalt, Lewiston Basin area, Idaho-Washington: Washington State Univ., Pullman, Ph.D. Dissert, 201 p.

Camp, V. E., Price, S. S., and Reidel, S. P., 1978, Descriptive summary of the Grande Ronde Basalt type section, Columbia River Basalt Group: Rockwell Hanford Operations Document, RHO-BWI-LD-15, Richland, Wash., 26 p. Choiniere, S. R., and Swanson, D. A.,
Miocene basalts of the northern (
Washington: Am. Jour. Sci. (in proceed)
Cockerham, R. S., and Bentley, R. D.
tween Clarno and Butte Creek, O
v. 5, no. 1, p. 23.

Dickinson, W. R., and Vigrass, L. W., Grant, and Harney Counties, Ore Bull. 58, 109 p.

Diery, H. D., and McKee, Bates, 1969 area: Northwest Sci., v. 43, p. 47 Fruchter, J. S., and Baldwin, S. F., 1 ment swarm, central Oregon, and Bull., v. 36, p. 514-516.

Gibson, I. L., 1969, A comparative acc River Plateau and eastern Icelan Gill, J. B., and McDougall, Ian, 1973. Miocene-Pliocene volcanism in F

Goff, F. E., 1977, Stratigraphy and t Washington: Am. Geophys. Unio Gray, Jane, and Kittleman, L. R.,

basalt and associated floras of ear Sci., v. 265, p. 257-291.

Griggs, A. B., 1976, The Columbia R Washington, Idaho, and Montan: Grolier, M. J., 1965, Geology of part

Washington: Johns Hopkins Uni Hammond, P. E., Bentley, R. D., Bro 1977, Volcanic stratigraphy and ington, in Brown, E. H., and Ellis Northwest: Bellingham, Western

Helz, R. T., 1978, The petrogenesis Washington—A chemical and e University Park, Ph.D. Dissert.,

Helz, R. T., Wright, T. L., and Swa chemical trends in the youngest northwest U.S.A.: Internat. Ass Symposium Andean and Antarct

Hogenson, G. M., 1964, Geology and gon: U.S. Geol. Survey Water-St Holden, G. S., and Hooper, P. R., 197

basalt section, Rocky Canyon, we p. 215-225.

Holmgren, D. A., 1967, The Yakima Washington Univ., Seattle, M.S.—1970, K/Ar dates and paleor Washington, in Gilmour, E. H., Columbia River Basalt Sympos Press, p. 201–207.

Hooper, P. R., 1974, Petrology and ch
 basalt, Idaho: Geol. Soc. Americ
 Hooper, P. R., Camp, V. E., Kleck. V
 Magnetic polarity and stratigra

capping Pomona Member. We in the Pomona and may be a lge Member.

#### TTED

- minary feasibility study of storage of ts: ERDA Rept. ARH-ST-137, v. 1,
- sic production rates—comparison of Plateau basalts: Science, v. 180, p.
- 976, Geochemical data on Columbia : Geol. Soc. America Abs. with Pro-
- Basalts and structural evolution of Plateau, in Brown, E. H., and Ellis, fic Northwest: Bellingham, Western
- e stratigraphy of the Picture Gorge c. America Abs. with Programs, v. 5,
- some implications for regional geolo. 2, p. 195-215.
- In The Tate Neogene-Biostratigraphy, last 15 million years in marine and alaeocilimatology, Palaeoecology, v.
- kima Basait and Ellensburg Forma-. Survey Bull. 1224—G, 15 p.
- atigraphy of the upper part of the Franklin Counties, Washington, in Surgey Prof. Paper 525-C, p. C87-
- ayment: Idaho Bur. Mines and Geol-
- igraphic information: Pullman Test ashington State Univ. Coll. Eng. Re-
- by, J. W., 3d, and Siems, B. A., 1973, shington—Description, stratigraphic ington State Univ. Coll. Eng. Rept.
- e Columbia River basalt flows along-Plateau, north-central Washington: 10, no. 3, p. 98.—
- and structure of the Columbia River ington: Washington State Univ.,
- 1978, Descriptive summary of the River Basalt Group: Rockwell Han-15, Richland, Wash., 26 p.

- Choiniere, S. R., and Swanson, D. A., 1979, Magnetostratigraphy and correlation of Miocene basalts of the northern Oregon coast and Columbia Plateau, southeast Washington; Am. Jour. Sci. (in press).
- Cockerham, R. S., and Bentley, R. D., 1973, Picture Gorge and Yakima Basalt between Clarno and Butte Creek, Oregon: Geol. Soc. America Abs. with Programs,
- Dickinson, W. R., and Vigrass, L. W., 1965, Geology of the Suplee-Izee area, Crook, Grant, and Harney Counties, Oregon: Oregon Dept. Geol. and Mineral Industries Bull. 58, 109 p.
- Diery, H. D., and McKee, Bates, 1969, Stratigraphy of the Yakima Basalt in the type area: Northwest Sci., v. 43, p. 47-64.
- Fruchter, J. S., and Baldwin, S. F., 1975, Correlations between dikes of the Monument swarm, central Oregon, and Picture Gorge Basalt flows: Geol. Soc. America Bull., v. 86, p. 514-516.
- Gibson, I. L., 1969, A comparative account of flood basalt volcanism of the Columbia River Plateau and eastern Iceland: Bull. Volcanol., v. 33, p. 419-437.
- Gill, J. B., and McDougall, Ian, 1973, Biostratigraphic and geological significance of Miocene-Pliocene volcanism in Fiji: Nature, v. 241, p. 176-180.
- Goff, F. E., 1977, Stratigraphy and tectonics of east Umtanum Ridge, south-central Washington: Am. Geophys. Union Trans. (EOS), v. 59, no. 12, p. 1248.
- Gray, Jane, and Kittleman, L. R., 1967, Geochronometry of the Columbia River basalt and associated floras of eastern Washington and western Idaho: Am. Jour. Sci., v. 265, p. 257-291.
- Griggs, A. B., 1976, The Columbia River Basalt Group in the Spokane quadrangle, Washington, Idaho, and Montana: U.S. Geol. Survey Bull. 1413, 39 p.
- Grolier, M. J., 1965, Geology of part of the Big Bend area in the Columbia Plateau, Washington: Johns Hopkins Univ., Baltimore, Ph.D. Dissert., 267 p.
- Hammond, P. E., Bentley, R. D., Brown, J. C., Ellingson, J. A., and Swanson, D. A., 1977, Volcanic stratigraphy and structure of the southern Cascade Range, Washington, in Brown, E. H., and Ellis, R. C., eds., Geological excursions in the Pacific Northwest: Bellingham, Western Washington Univ. Press, p. 127-169.
- Helz, R. T., 1978, The petrogenesis of the Ice Harbor Member, Columbia Plateau, Washington—A chemical and experimental study: Pennsylvania State Univ., University Park, Ph.D. Dissert., 284 p.
- Helz, R. T., Wright, T. L., and Swanson, D. A., 1976, Petrogenetic significance of chemical trends in the youngest unit of Yakima Basalt on the Columbia Plateau, northwest U.S.A.: Internat. Assoc. Volcanology Chemistry of Earth's Interior, Symposium Andean and Antarctic Volcanology Problems Proc., p. 465-481.
- Hogenson, G. M., 1964, Geology and ground water of the Umatilla River basin, Oregon: U.S. Geol. Survey Water-Supply Paper.1620, 162 p.
- Holden, G. S., and Hooper, P. R., 1976, Petrology and chemistry of a Columbia River basalt section, Rocky Canyon, west-central Idaho: Geol. Soc. America Bull., v. 87, p. 215-225.
- Holmgren, D. A., 1967, The Yakima-Ellensburg unconformity, central Washington: Washington Univ., Seattle, M.S. Thesis, 69 p.
- Hooper, P. R., 1974, Petrology and chemistry of the Rock Creek flow, Columbia River basalt, Idaho: Geol. Soc. America Bull., v. 85, p. 15-26.
- Hooper, P. R., Camp, V. E., Kleck, W. D., Reidel, S. P., and Sundstrum, C. E., 1976, Magnetic polarity and stratigraphy of the southeastern part of the Columbia

Hooper, P. R., Knowles, C. R., and Watkins, N. D., 1979, Magnetostratigraphy of the Imnaha and Grande Ronde Basalts in the southeast part of the Columbia Plateau: Am. Jour. Sci. (in press).

Jackson, D. B., 1975, Description of the geoelectric section, Rattlesnake Hills Unit 1 well, Washington: U.S. Geol. Survey Jour. Research, v. 3, no. 6, p. 665-669.

Kennett, J. P., and Watkins, N. D., 1974, Late Miocene-early Pliocene paleomagnetic stratigraphy, paleoclimatology, and biostratigraphy in New Zealand: Geol. Soc. America Bull., v. 85, p. 1385-1398.

Kienle, C. F., Sheriff, S. D., and Bentley, R. D., 1978, Tectonic significance of the paleomagnetism of the Frenchman Springs basalt, Oregon and Washington: \_\_\_\_\_Geol. Soc. America Abs. with Programs, v.=10=nor-3, p. 111-112.

Kleck, W. D., 1973, Geology of the Columbia River basalt in and near the Imnaha River Valley, Oregon: Geol. Soc. America Abs. with Programs, v. 5, no. 1, p. 67-68.

——1976, Chemistry, petrography, and stratigraphy of the Columbia River Group in the Imnaha River Valley region, eastern Oregon and western Idaho: Washington State Univ., Pullman, Ph.D. Dissert., 203 p.

Laval, W. N., 1956, Stratigraphy and structural geology of portions of south-central Washington: Washington Univ., Seattle, Ph.D. Dissert., 208 p.

Ledgerwood, R. K., Brown, D. J., Waters, A. C., and Meyers, C. W., 1973, Identification of Yakima Basalt flows in the Pasco Basin: Atlantic Richfield Hanford Co., U.S. Atomic Energy Comm. Rept. ARH-2768.

Lefebvre, R. H., 1970, Columbia River basalts of the Grand Coulee area, in Gilmour, E. H., and Stradling, Dale, eds., Proceedings Second Columbia River Basalt Symposium: Cheney, Eastern Washington State Coll. Press, p. 1-38.

Lindsley, D. H., 1960. Geology of the Spray quadrangle, Oregon, with special emphasis on the petrography and magnetic properties of the Picture Gorge basalt: Johns Hopkins Univ., Baltimore, Ph.D. Dissert., 236 p.

Lindsley, D. H., Smith, Douglas, and Haggerty, S. E., 1971, Petrography and mineral chemistry of a differentiated flow of Picture Gorge Basalt near Spray, Oregon: Carnegie Inst. Washington Yearbook 69, p. 264-285.

McDougall, Ian, 1976, Geochemistry and origin of basalt of the Columbia River Group, Oregon and Washington: Geol. Soc. America Bull., v. 87, p. 777-792.

McDougail, Ian, and Page, R. W., 1975, Toward a physical time-scale for the Neogene—data from the Australian region, in Saito, T., and Burckle, L. H., eds., Late Neogene epoch boundaries: New York, Am. Museum Nat. History, Micropaleontology Press, p. 75-84.

McDougall, Ian, Saemundsson, Kristjan, Johannesson, Haukur, Watkins, N. D., and Kristjansson, Leo, 1977, Extension of the geomagnetic polarity time scale to 6.5 m.y.—K-Ar dating, geological and paleomagnetic study of a 3,500-m lava succession in western Iceland: Geol. Soc. America Bull., v. 88, p. 1-15.

McKee, E. H., Swanson, D. A., and Wright, T. L., 1977, Duration and volume of Columbia River basalt volcanism, Washington, Oregon, and Idaho: Geol. Soc. America Abs. with Programs, v. 9, no. 4, p. 463-464.

Mackin, J. H., 1961, A stratigraphic section in the Yakima Basalt and Ellensburg Formation in south-central Washington: Washington Div. Mines and Geology Rept. Inv. 19, 45 p.

Myers, C. W., 1973, Yakima Basalt flows near Vantage, and from core holes in the Pasco Basin, Washington: California Univ., Santa Cruz, Ph.D. Dissert., 147 p.

Nathan, Simon, and Fruchter, J. S raphy of the Picture Gorge and trai Oregon: Geol. Soc. Americ Newcomb, R. C., 1965, Geology and basin, Washington-Oregon: W Supply Bull. 21, 151 p.

Caracter Sec.

Newman, K. R., 1970, Palynology of pany of California Rattlesnake Gilmour, E. H., and Stradling, Basalt Symposium: Cheney, Ea

Oles, K. F., and Enlows, H. E., 19' Wheeler County, Oregon: Oregon 62 p.

Osawa, Masumi, and Goles, G. G.. River basalts, in Gilmour, E.H. Columbia River Basalt Sympo Press, p. 55-71.

Pardee, J. T., and Bryan, Kirk, 1920 the lavas of the Columbia Plate Prof. Paper 140-A, 17 p.

Peacock, M. A., and Fuller, R. E., 19 from the Columbia River Plates

Price, S. M., 1974, A geochemical cl. Columbia River basalt: Atlant Comm. Rept. ARH-SA-202, 29

——1977, An evaluation of dike-fi Joseph swarm, Columbia Rive 320 p.

Price, W. H., Knowles, C. R., and Bo the Camas Prarie area, Idaho: G. p. 773.

Raymond, J. R., and Tillson, D. D., south-central Washington: Aton BNWL-776, 126 p.

Reidel, S. P., 1978, Stratigraphy and lower Salmon and adjacent Sr. Pullman, Ph.D. Dissert., 415 p.

Pullman, Ph.D. Dissert., 415 p. Rietman, J. D., 1966, Remanent mag ton State: Stanford Univ., Stanfo

Robinson, P. T., 1975, Reconnaissance southwestern part of the Blue M gon: U.S. Geol. Survey Misc. Ge

Robyn, T. L., 1977, Geology and petr Oregon Univ., Eugene, Ph.D. Di

Robyn, T. L., Hoover, J. D., and Thaye Strawberry Volcanics, NE Orego no. 4, p. 488-489.

Ross, M. E., 1978, Stratigraphy, struc a portion of the Grande Ronde-B Idaho Univ., Moscow, Ph.D. Diss

Schmincke, H.-U., 1964, Petrology, ps Formation and interbedded Yal Johns Hopkins Univ., Baltimore,

- s. with Programs, v. 8, no. 3, p. 383, 1976, Composition and differentia-Group: Geol. Soc. America Abs. with
- 1., 1979, Magnetostratigraphy of the southeast part of the Columbia
- ric section, Rattlesnake Hills Unit 1 Research, v. 3, no. 6, p. 665-669. liocene-early Pliocene paleomagnetic igraphy in New Zealand: Geol. Soc.
- . 1978. Tectonic significance of the s basalt, Oregon and Washington: 10, no. 3, p. 111-112.
- iver basalt in and near the Imnaha Abs. with Programs, v. 5, no. 1, p.
- craphy of the Columbia River Group Oregon and western Idaho: Washing-33 p.
- geology of portions of south-central D. Dissert., 208 p.
- and Meyers, C. W., 1973, Identificassin: Atlantic Richfield Hanford Co.,
- the Grand Coulee area, in Gilmour, Second-Columbia River Basalt Sym-Coll. Press, p. 1–38.
- adrangle, Oregon, with special emoperties of the Picture Gorge basalt: ert., 236 p.
- 5. E., 1971, Petrography and mineral Gorge Basalt near Spray, Oregon: 264-285.
- n of basalt of the Columbia River America Bull., v. 87, p. 777-792. ard a physical time-scale for the in Saito, T., and Burckle, L. H., eds., Am. Museum Nat. History, Micro-
- esson, Haukur, Watkins, N. D., and omagnetic polarity time scale to 6.5 netic study of a 3,500-m lava succes-Buil.; v. 88, p. 1-15.
- , 1977, Duration and volume of Co-Oregon, and Idaho: Geol. Soc. Amer-464.
- the Yakima Basalt and Ellensburg ashington Div. Mines and Geology
- 'antage, and from core holes in the Santa Cruz, Ph.D. Dissert., 147 p.

- Nathan, Simon, and Fruchter, J. S., 1974, Geochemical and paleomagnetic stratigraphy of the Picture Gorge and Yakima Basalts (Columbia River Group) in central Oregon: Geol. Soc. America Bull., v. 85, p. 63-76.
- Newcomb, R. C., 1965, Geology and ground-water resources of the Walla Walla River basin, Washington-Oregon: Washington [State] Div. Water Resources, Water Supply Bull. 21, 151 p.
- Newman, K. R., 1970, Palynology of interflow sediments from the Standard Oil Company of California Rattlesnake Hills No. 1 well, Benton County, Washington, in Gilmour, E. H., and Stradling, Dale, eds., Proceedings Second Columbia River Basalt Symposium: Cheney, Eastern Washington State Coll. Press, p. 201-207.
- Oles, K. F., and Enlows, H. E., 1971, Bedrock geology of the Mitchell quadrangle, Wheeler County, Oregon: Oregon Dept. Geology and Mineral Industries Bull. 72, 62 n.
- Osawa, Masumi, and Goles, G. G., 1970, Trace-element abundances in Columbia River basalts, in Gilmour, E.H., and Stradling, Dale, eds., Proceedings Second Columbia River Basalt Symposium: Cheney, Eastern Washington State Coll. Press, p. 55-71.
- Pardee, J. T., and Bryan, Kirk, 1926, Geology of the Latah Formation in relation to the lavas of the Columbia Plateau\_near Spokane, Washington: U.S. Geol. Survey Prof. Paper 140-A, 17 p.
- Peacock, M. A., and Fuller, R. E., 1928, Chlorophaeite, sideromelane and palagonite from the Columbia River Plateau: Am. Mineralogist, v. 13, p. 360-383.
- Price, S. M., 1974, A geochemical classification of dikes of the Grande Ronde Swarm, Columbia River basalt: Atlantic Richfield Hanford Co., U.S. Atomic Energy Comm. Rept. ARH-SA-202, 29 p.
- ——1977, An evaluation of dike-flow correlations indicated by geochemistry, Chief Joseph swarm, Columbia River basalt: Idaho Univ., Moscow, Ph.D. Dissert., 320 p.
- Price, W. H., Knowles, C. R., and Bond, J. G., 1973, Columbia River basalt dikes of the Camas Prarie area, Idaho: Geol. Soc. America Abs. with Programs, v. 5, no. 7, p. 773.
- Raymond, J. R., and Tillson, D. D., 1968, Evaluation of a thick basalt sequence in south-central Washington: Atomic Energy Comm. Research and Devel. Rept., BNWL-776, 126 p.
- Reidel, S. P., 1978, Stratigraphy and petrogenesis of the Grande Ronde Basalt in the lower Salmon and adjacent Snake River Canyon: Washington State Univ., Puilman, Ph.D. Dissert., 415 p.
- Rietman, J. D., 1966, Remanent magnetization of the late Yakima Basalt, Washington State: Stanford Univ., Stanford, Calif., Ph.D. Dissert., 87 p.
- Robinson, P. T., 1975, Reconnaissance geologic map of the John Day Formation in the southwestern part of the Blue Mountains and adjacent areas; north-central Oregon: U.S. Geol. Survey Misc. Geol. Inv. Map I-872, scale 1:125,000.
- Robyn, T. L., 1977, Geology and petrology of the Strawberry Volcanics, NE Oregon: Oregon Univ., Eugene, Ph.D. Dissert., 197 p.
- Robyn, T. L., Hoover, J. D., and Thayer, T. P., 1977, Geology and geochronology of the Strawberry Volcanics, NE Oregon: Geol. Soc. America Abs. with Programs, v. 9, no. 4, p. 488-489.
- Ross, M. E., 1978, Stratigraphy, structure, and petrology of Columbia River basalt in a portion of the Grande Ronde-Blue Mountains area of Oregon and Washington: Idaho Univ., Moscow, Ph.D. Dissert., 407 p.
- Schmincke, H.-U., 1964, Petrology, paleocurrents, and stratigraphy of the Ellensburg Formation and interbedded Yakima Basalt flows, south-central Washington: Johns Hopkins Univ., Baltimore, Ph.D. Dissert., 426 p.

The state of the s

——1967b, Fused tuff and peperites in south-central Washington: Geol. Soc. America Bull., v. 78, p. 319-330.

Shannon and Wilson, Inc., 1973, Geologic studies of Columbia River basalt structures and age of deformation, The Dalles-Umatilla region, Washington and Oregon; Boardman Nuclear Project: Shannon and Wilson, Inc. Report to Portland General Electric Co., 52 p.

Siems, B. A., Bush, J. H., and Crosby, J. W., 3d, 1974, TiO<sub>2</sub> and geophysical logging criteria for Yakima Basalt correlation, Columbia Plateau: Geol. Soc. America Bull., v. 85, p. 1061-1068.

Smith, G. O., 1901, Geology and water resources of a portion of Yakima County, Washington: U.S. Geol. Survey Water-Supply Paper 55, 68 p.

Snavely, P. D., Jr., MacLeod, N. S., and Wagner, H. C., 1973, Miocene tholeitic basalts of coastal Oregon and Washington and their relations to coeval basalts of the Columbia Plateau: Geol. Soc. America Bull., v. 84, p. 387-424.

Stout, M. L., 1961, Diabasic and gabbroic intrusions in the Frost Mountain area, south-central Cascade Mountains, Washington: Am. Jour. Sci., v. 259, p. 348-352.

Swanson, D. A., 1967, Yakima Basalt of the Tieton River area, south-central Washington: Geol. Soc. Americ Bull., v. 78, p. 1077-1110.

——1969, Reconnaissance geologic map of the east half of the Bend quadrangle, Crook, Wheeler, Jefferson, Wasco, and Deschutes Counties, Oregon: U.S. Geol. Survey Misc. Geol. Inv. Map I-568, scale 1:250,000.

——1978, Geologic map of the Tieton River area, Yakima County, south-central Washington: U.S. Geol. Survey Misc. Field Inv. Map MF-968, scale 1:48,000.

Swanson, D. A., and Wright, T. L., 1976a, Magnetostratigraphic units in the Yakima Basalt, southeast Washington: Geol. Soc. America Abs. with Programs, v. 8, no. 3, p. 413-414.

1976b, Guide to field trip between Pasco and Pullman, Washington, emphasizing stratigraphy, vent areas, and intracanyon flows of Yakima Basalt: Geol. Soc. America, Cordilleran Sec. Mtg., Pullman, 1976, Field Guide No. 1, 33 p.

Swanson, D. A., Wright, T. L., Camp, V. E., Gardner, J. N., Helz, R. T., Price, S. A., and Ross, M. E., 1977, Reconnaissance geologic map of the Columbia River Basalt Group, Pullman and Walla Walla quadrangles, southeast Washington and adjacent Idaho: U.S. Geol. Survey Open-File Rept. 77-100, scale 1:250,000.

Swanson, D. A., Wright, T. L. Camp, V. E., Gardner, J. N., Helz, R. T., Price, S. M., Reidel, S. P., and Ross, M. E., 1979, Reconnaissance geologic map of the Columbia River Basalt Group, Pullman and Walla Walla quadrangles, southeast Washington and adjacent Idaho: U.S. Geol. Survey Misc. Geol. Inv. Map I-1139, scale 1:250.000.

Swanson, D. A., Wright, T. L., and Helz, R. T., 1975, Linear vent systems and estimated rates of magma production and eruption for the Yakima Basalt on the Columbia Plateau: Am. Jour. Sci., v. 275, p. 877-905.

Tabor, R. W., Waitt, R. B., Jr., Frizzell, V. A., Jr., Swanson, D. A., Byerly, G. R., and Bentley, R. D., 1979, Geologic map of the Wenatchee 1:100,000 quadrangle, Washington: U.S. Geol. Survey Misc. Geol. Inv. Map (in press).

Taubeneck, W. H., 1970, Dikes of Columbia River basalt in northeastern Oregon. western Idaho, and southeastern Washington, in Gilmour, E. H., and Stradling, Dale, eds., Proceedings Second Columbia River Basalt Symposium: Cheney, Eastern Washington State Coll. Press, p. 73-96.

Taylor, T. L., 1976, The basalt stratigraphy and structure of the Saddle Mountains of south-central Washington: Washington State Univ., Pullman, M.S. thesis, 116 p. Walker, G. W., 1973, Contrasting con flows in Union and Wallowa Cou Bull., v. 84, p. 425-430.

Ward, A. W., Jr., 1976, Petrology as River basalt, Washington: Atlan Waters, A. C., 1955, Geomorphology Yakima East quadrangle: Geol.

——1961, Stratigraphic and litholo Jour. Sci., v. 259, p. 583-611.
Watkins, N. D., and Baksi, A. K., 19

the Columbia River, Steens and Idaho: Am. Jour. Sci., v. 274, p. Wilcox, R. E., and Fisher, R. V., 196 Grant County, Oregon: U.S. C 1:62,500.

Wright, T. L., Grolier, M. J., and Swe the stratigraphy of the Columbia 371-386.

Wright, T. L., and Hamilton, M. S., identification and correlation of i Wright, T. L., Swanson, D. A., Helz, F element, and glass chemistry of C

1971 and 1977: U.S. Geol. Surve

four upper Yakima Basalt flows in rica Bull., v. 78, p. 1385-1422. central Washington: Geol. Soc. Amer-

es of Columbia River basalt structures illa region, Washington and Oregon; 'ilson, Inc. Report to Portland General

1, 1974, TiO2 and geophysical logging olumbia Plateau: Geol. Soc. America

rces of a portion of Yakima County, ply Paper 55, 68 p.

gner, H. C., 1973, Miocene tholeitic and their relations to coeval basalts of Bull., v. 84, p. 387-424.

rusions in the Frost Mountain area, egton: Am. Jour. Sci., v. 259, p. 348-

ieton River area, south-central Wash-1077-1110.

he east half of the Bend quadrangle, eschutes Counties, Oregon: U.S. Geol. 1:250.000.

areā, Yakima County, south-central d Inv. Map MF-968, scale 1:48,000. netostratigraphic units in the Yakima America Abs. with Programs, v. 8, no.

and Pullman, Washington, emphasizyon flows of Yakima Basalt: Geol. Soc. 1976, Field Guide No. 1, 33 p. ardner, J. N., Helz, R. T., Price, S. A.

reologic map of the Columbia River adrangles, southeast Washington and ile Rept. 77-100, scale 1:250,000. ardner, J. N., Helz, R. T., Price, S. M., maissance geologic map of the Columa Walla quadrangles, southeast Washvey Misc. Geol. Inv. Map I-1139, scale

., 1975. Linear vent systems and estiuption for the Yakima Basalt on the p. 877, 905.

Jr., Swanson, D. A., Byerly, G. R., and he Wenatchee 1:100,000 quadrangle, l. Inv. Map (in press).

River basalt in northeastern Oregon, ton, in Gilmour, E. H., and Stradling, River Basalt Symposium: Cheney, 73-96.

at structure of the Saddle Mountains of ate Univ., Pullman, M.S. thesis, 116 p.

7.

Thayer, T. P., and Brown, C. E., 1966a, Local thickening of basalts and late Tertiary silicic volcanism in the Canyon City quadrangle, northeastern Oregon, in Geological Survey Research 1966: U.S. Geol. Survey Prof. Paper 550-C, p. C73-C78.

1966b, Columbia River Group, in Changes in stratigraphic nomenclature by the U.S. Geological Survey 1965: U.S. Geol. Survey Bull. 1244-A, p. A23-A25.

Uppuluri, V. R., 1974, Prineville chemical type: a new basalt type in the Columbia River Group: Geol. Soc. America Bull., v. 85, p. 1315-1318.

Vallier, T. L., and Hooper, P. R., 1976, Geologic guide to Hells Canyon, Snake River: Geol. Soc. America, Cordilleran Sec. Mtg., Pullman, Wash., 1976, Field Guide No. 5, 38 p.

Walker, G. W., 1973, Contrasting compositions of the youngest Columbia River basalt flows in Union and Wallowa Counties, northeastern Oregon: Geol. Soc. America Bull., v. 84, p. 425-430.

Ward, A. W., Jr., 1976, Petrology and chemistry of the Huntzinger flow, Columbia River basalt, Washington: Atlantic Richfield Hanford Co., Rept. ARH-272, 52 p.

Waters, A. C., 1955, Geomorphology of south-central Washington, illustrated by the Yakima East quadrangle: Geol. Soc. America Bull., v. 66, p. 663-684.

——1961, Stratigraphic and lithologic variations in the Columbia River basalt: Am. Jour. Sci., v. 259, p. 583-611.

Watkins, N. D., and Baksi, A. K., 1974, Magnetostratigraphy and oroclinal folding of the Columbia River, Steens and Owyhee basalts in Oregon, Washington, and Idaho: Am. Jour. Sci., v. 274, p. 148-189.

Wilcox, R. E., and Fisher, R. V., 1966, Geologic map of the Monument quadrangle, Grant County, Oregon: U.S. Geol. Survey Geol. Quad. Map GQ-541, scale 1:62,500.

Wright, T. L., Grolier, M. J., and Swanson, D. A., 1973, Chemical variation related to the stratigraphy of the Columbia River basalt: Geol. Soc. America Bull., v. 84, p. 371-386.

Wright, T. L., and Hamilton, M. S., 1978, A computer-assisted graphical method for identification and correlation of igneous rock chemistries; Geology, v. 6, p. 16-20.

Wright, T. L., Swanson, D. A., Helz, R. T., and Byerly, G. R., 1979, Major oxide, trace element, and glass chemistry of Columbia River basalt samples collected between 1971 and 1977; U.S. Geol. Survey Open-File Rept. 79-711, 13 p.

GPO 689-035/12